


圖例 NOTATION

- ZONES**
- COMMERCIAL C 商業
 - RESIDENTIAL (GROUP A) R(A) 住宅(甲類)
 - RESIDENTIAL (GROUP B) R(B) 住宅(乙類)
 - GOVERNMENT, INSTITUTION OR COMMUNITY G(C) 政府、機構或社區
 - OPEN SPACE O 休憩用地
 - OTHER SPECIFIED USES OU 其他指定用途
 - GREEN BELT GB 綠化地帶
- COMMUNICATIONS**
- RAILWAY AND STATION 鐵路及車站
 - RAILWAY AND STATION (UNDERGROUND) 鐵路及車站(地下)
 - RAILWAY AND STATION (ELEVATED) 鐵路及車站(高架)
 - MAJOR ROAD AND JUNCTION 主要道路及路口
 - ELEVATED ROAD 高架道路
- MISCELLANEOUS**
- BOUNDARY OF PLANNING SCHEME 規劃範圍界線
 - URBAN RENEWAL AUTHORITY DEVELOPMENT SCHEME PLAN AREA 市區重建局發展計劃範圍
 - BUILDING HEIGHT CONTROL ZONE BOUNDARY 建築物高度管制區界線
 - MAXIMUM BUILDING HEIGHT (IN METRES ABOVE PRINCIPAL DATUM) 最高建築物高度(在主水平基準上若干米)
 - PETROL FILLING STATION P F S 加油站

土地用途及面積一覽表 SCHEDULE OF USES AND AREAS

USES	大約面積及百分比		用途
	公頃 HECTARES	% 百分比	
COMMERCIAL	1.21	0.31	商業
RESIDENTIAL (GROUP A)	137.73	35.55	住宅(甲類)
RESIDENTIAL (GROUP B)	14.46	3.73	住宅(乙類)
GOVERNMENT, INSTITUTION OR COMMUNITY	44.93	11.60	政府、機構或社區
OPEN SPACE	41.43	10.69	休憩用地
OTHER SPECIFIED USES	46.82	12.09	其他指定用途
GREEN BELT	28.50	7.36	綠化地帶
NULLAH	0.09	0.02	明渠
MAJOR ROAD ETC.	67.17	17.34	主要道路等
URBAN RENEWAL AUTHORITY DEVELOPMENT SCHEME PLAN AREA	5.06	1.31	市區重建局發展計劃範圍
TOTAL PLANNING SCHEME AREA	387.40	100.00	規劃範圍總面積

夾附的《註釋》屬這份圖則的一部分 THE ATTACHED NOTES ALSO FORM PART OF THIS PLAN



香港城市規劃委員會依據城市規劃條例擬備的觀塘南部(九龍規劃區第14區部分)分區計劃大綱圖
TOWN PLANNING ORDINANCE, HONG KONG TOWN PLANNING BOARD
KOWLOON PLANNING AREA No. 14 (PART) - KWUN TONG (SOUTH) - OUTLINE ZONING PLAN

SCALE 1:5000 比例尺



規劃署遵照城市規劃委員會指示擬備
 PREPARED BY THE PLANNING DEPARTMENT UNDER
 THE DIRECTION OF THE TOWN PLANNING BOARD

圖則編號 PLAN No. **S/K14S/21A**

KOWLOON PLANNING AREA NO. 14 (PART)

DRAFT KWUN TONG (SOUTH) OUTLINE ZONING PLAN NO. S/K14S/21A

(Being a Draft Plan for the Purposes of the Town Planning Ordinance)

NOTES

(N.B. These form part of the Plan)

- (1) These Notes show the uses or developments on land falling within the boundaries of the Plan which are always permitted and which may be permitted by the Town Planning Board, with or without conditions, on application. Where permission from the Town Planning Board for a use or development is required, the application for such permission should be made in a prescribed form. The application shall be addressed to the Secretary of the Town Planning Board, from whom the prescribed application form may be obtained.
- (2) Any use or development which is always permitted or may be permitted in accordance with these Notes must also conform to any other relevant legislation, the conditions of the Government lease concerned, and any other Government requirements, as may be applicable.
- (3)
 - (a) No action is required to make the existing use of any land or building conform to this Plan until there is a material change of use or the building is redeveloped.
 - (b) Any material change of use or any other development (except minor alteration and/or modification to the development of the land or building in respect of the existing use which is always permitted) or redevelopment must be always permitted in terms of the Plan or, if permission is required, in accordance with the permission granted by the Town Planning Board.
 - (c) For the purposes of subparagraph (a) above, “existing use of any land or building” means -
 - (i) before the publication in the Gazette of the notice of the first statutory plan covering the land or building (hereafter referred as ‘the first plan’),
 - a use in existence before the publication of the first plan which has continued since it came into existence; or
 - a use or a change of use approved under the Buildings Ordinance which relates to an existing building; and
 - (ii) after the publication of the first plan,
 - a use permitted under a plan which was effected during the effective period of that plan and has continued since it was effected; or

- a use or a change of use approved under the Buildings Ordinance which relates to an existing building and permitted under a plan prevailing at the time when the use or change of use was approved.
- (4) Except as otherwise specified by the Town Planning Board, when a use or material change of use is effected or a development or redevelopment is undertaken, as always permitted in terms of the Plan or in accordance with a permission granted by the Town Planning Board, all permissions granted by the Town Planning Board in respect of the site of the use or material change of use or development or redevelopment shall lapse.
 - (5) Road junctions, alignments of roads and railway tracks, and boundaries between zones may be subject to minor adjustments as detailed planning proceeds.
 - (6) Temporary uses (expected to be 5 years or less) of any land or buildings are always permitted as long as they comply with any other relevant legislation, the conditions of the Government lease concerned, and any other Government requirements, and there is no need for these to conform to the zoned use or these Notes. For temporary uses expected to be over 5 years, the uses must conform to the zoned use or these Notes.
 - (7) The following uses or developments are always permitted on land falling within the boundaries of the Plan except where the uses or developments are specified in Column 2 of the Notes of individual zones:
 - (a) provision, maintenance or repair of plant nursery, amenity planting, open space, rain shelter, refreshment kiosk, road, bus/public light bus stop or lay-by, cycle track, Mass Transit Railway station entrance, Mass Transit Railway structure below ground level, taxi rank, nullah, public utility pipeline, electricity mast, lamp pole, telephone booth, telecommunications radio base station, automatic teller machine and shrine;
 - (b) geotechnical works, local public works, road works, sewerage works, drainage works, environmental improvement works, marine related facilities, waterworks (excluding works on service reservoir) and such other public works co-ordinated or implemented by Government; and
 - (c) maintenance or repair of watercourse and grave.
 - (8) In any area shown as 'Road', all uses or developments except those specified in paragraph (7) above and those specified below require permission from the Town Planning Board:

toll plaza, on-street vehicle park and railway track.
 - (9) Unless otherwise specified, all building, engineering and other operations incidental to and all uses directly related and ancillary to the permitted uses and developments within the same zone are always permitted and no separate permission is required.
 - (10) In these Notes, "existing building" means a building, including a structure, which is physically existing and is in compliance with any relevant legislation and the conditions of the Government lease concerned.

KOWLOON PLANNING AREA NO. 14 (PART)

DRAFT KWUN TONG (SOUTH)
OUTLINE ZONING PLAN NO. S/K14S/21A

Schedule of Uses

	<u>Page</u>
COMMERCIAL (1)	1
RESIDENTIAL (GROUP A)	3
RESIDENTIAL (GROUP B)	7
GOVERNMENT, INSTITUTION OR COMMUNITY	9
OPEN SPACE	11
OTHER SPECIFIED USES	12
GREEN BELT	18

COMMERCIAL (1)

Column 1 Uses always permitted	Column 2 Uses that may be permitted with or without conditions on application to the Town Planning Board
Ambulance Depot Commercial Bathhouse/Massage Establishment Eating Place Educational Institution Exhibition or Convention Hall Government Use (not elsewhere specified) Information Technology and Telecommunications Industries Institutional Use (not elsewhere specified) Library Market Off-course Betting Centre Office Place of Entertainment Place of Recreation, Sports or Culture Private Club Public Clinic Public Convenience Public Transport Terminus or Station Public Utility Installation Public Vehicle Park (excluding container vehicle) Radar, Telecommunications Electronic Microwave Repeater, Television and/or Radio Transmitter Installation Recyclable Collection Centre Religious Institution Research, Design and Development Centre School Shop and Services Social Welfare Facility (excluding those involving residential care) Training Centre Utility Installation for Private Project	Broadcasting, Television and/or Film Studio Cargo Handling and Forwarding Facility Government Refuse Collection Point Hospital Hotel Mass Transit Railway Vent Shaft and/or Other Structure above Ground Level other than Entrances Petrol Filling Station Wholesale Trade

Planning Intention

This zone is intended primarily for commercial developments, which may include shop, service, place of entertainment and eating place serving the needs of local workers.

(Please see next page)

COMMERCIAL (1) (Cont'd)

Remarks

- (1) No new development, or addition, alteration and/or modification to or redevelopment of an existing building shall result in a total development and/or redevelopment in excess of a maximum plot ratio of 12.0, and the maximum building heights, in terms of metres above Principal Datum, as stipulated on the Plan, or the plot ratio and height of the existing building, whichever is the greater.
- (2) In determining the maximum plot ratio for the purposes of paragraph (1) above, any floor space that is constructed or intended for use solely as car park, loading/unloading bay, plant room and caretaker's office, provided such uses and facilities are ancillary and directly related to the development or redevelopment, may be disregarded.
- (3) Where the permitted plot ratio as defined in Building (Planning) Regulations is permitted to be exceeded in circumstances as set out in Regulation 22(1) or (2) of the said Regulations, the plot ratio for the building on land to which paragraph (1) applies may be increased by the additional plot ratio by which the permitted plot ratio is permitted to be exceeded under and in accordance with the said Regulation 22(1) or (2), notwithstanding that the relevant maximum plot ratio specified in paragraph (1) above may thereby be exceeded.
- (4) Based on the individual merits of a development or redevelopment proposal, minor relaxation of the plot ratio/building height restrictions stated in paragraph (1) above may be considered by the Town Planning Board on application under section 16 of the Town Planning Ordinance.

RESIDENTIAL (GROUP A)

Column 1 Uses always permitted	Column 2 Uses that may be permitted with or without conditions on application to the Town Planning Board
Ambulance Depot	Commercial Bathhouse/Massage
Flat	Establishment
Government Refuse Collection Point (on land designated "Residential (Group A)3" only)	Eating Place
Government Use (not elsewhere specified)	Educational Institution
House	Exhibition or Convention Hall
Library	Government Refuse Collection Point (not elsewhere specified)
Market	Hospital
Place of Recreation, Sports or Culture	Hotel
Public Clinic	Institutional Use (not elsewhere specified)
Public Transport Terminus or Station (excluding open-air terminus or station)	Mass Transit Railway Vent Shaft and/or
Residential Institution	Other Structure above Ground Level
School (in free-standing purpose-designed building only)	other than Entrances
Social Welfare Facility	Office
Utility Installation for Private Project	Petrol Filling Station
	Place of Entertainment
	Private Club
	Public Convenience
	Public Transport Terminus or Station (not elsewhere specified)
	Public Utility Installation
	Public Vehicle Park (excluding container vehicle)
	Religious Institution
	School (not elsewhere specified)
	Shop and Services
	Training Centre

(Please see next page)

RESIDENTIAL (GROUP A) (Cont'd)

In addition, the following uses are always permitted (a) on the lowest three floors of a building, taken to include basements; or (b) in the purpose-designed non-residential portion of an existing building, both excluding floors containing wholly or mainly car parking, loading/unloading bays and/or plant room :

Eating Place
Educational Institution
Institutional Use (not elsewhere specified)
Off-course Betting Centre
Office
Place of Entertainment
Private Club
Public Convenience
Recyclable Collection Centre
School
Shop and Services
Training Centre

Planning Intention

This zone is intended primarily for high-density residential developments. Commercial uses are always permitted on the lowest three floors of a building or in the purpose-designed non-residential portion of an existing building.

Remarks

- (1) On land designated “Residential (Group A)” and “Residential (Group A)3”, no new development, or addition, alteration and/or modification to or redevelopment of an existing building shall result in the plot ratio for the building upon development and/or redevelopment in excess of 7.5 for a domestic building or 9.0 for a building that is partly domestic and partly non-domestic, or the plot ratio of the existing building, whichever is the greater. Except where the plot ratio is permitted to be exceeded under paragraphs (9) and/or (10) hereof, under no circumstances shall the plot ratio for the domestic part of any building, to which this paragraph applies, exceed 7.5.
- (2) On land designated “Residential (Group A)” and “Residential (Group A)3”, for a non-domestic building to be erected on the site, the maximum plot ratio shall not exceed 9.0 except where the plot ratio is permitted to be exceeded under paragraphs (9) and/or (10) hereof.

(Please see next page)

RESIDENTIAL (GROUP A) (Cont'd)

Remarks (Cont'd)

- (3) On land designated “Residential (Group A)1”, no new development, or addition, alteration and/or modification to or redevelopment of an existing building shall result in a total development and/or redevelopment in excess of a maximum domestic gross floor area of 134,352m².
- (4) On land designated “Residential (Group A)2”, no new development, or addition, alteration and/or modification to or redevelopment of an existing building shall result in a total development and/or redevelopment in excess of the maximum domestic and non-domestic plot ratio of 4.5 and 1.5 respectively, and the maximum building height of 150 metres above Principal Datum (mPD), or the plot ratio and height of the existing building, whichever is the greater.
- (5) For the purpose of paragraphs (1) and (4), on land designated “Residential (Group A)”, “Residential (Group A)2” and “Residential (Group A)3”, no addition, alteration and/or modification to or redevelopment of an existing building shall result in a total development and/or redevelopment in excess of the relevant maximum domestic and/or non-domestic plot ratio(s), or the domestic and/or non-domestic plot ratio(s) of the existing building, whichever is the greater, subject to, as applicable-
 - (a) the plot ratio(s) of the existing building shall apply only if any addition, alteration and/or modification to or redevelopment of an existing building is for the same type of building as the existing building, i.e. domestic, non-domestic, or partly domestic and partly non-domestic building; or
 - (b) the maximum domestic and/or non-domestic plot ratio(s) stated in paragraphs (1) and (4) above shall apply if any addition, alteration and/or modification to or redevelopment of an existing building is not for the same type of building as the existing building, i.e. domestic, non-domestic, or partly domestic and partly non-domestic building.
- (6) On land designated “Residential (Group A)” abutting both Hiu Ming Street and Hiu Kwong Street and land designated “Residential (Group A)3”, no new development, or addition, alteration and/or modification to or redevelopment of an existing building shall result in a total development and/or redevelopment in excess of the maximum building height, in terms of mPD, as stipulated on the Plan, or the height of the existing building, whichever is the greater.
- (7) In determining the relevant maximum plot ratio for the purposes of paragraphs (1), (2) and (4) above, area of any part of the site that is occupied or intended to be occupied by free-standing purpose-designed buildings (including both developed on ground and on podium level) solely for accommodating Government, institution or community facilities including school(s) as may be required by Government shall be deducted in calculating the relevant site area.

(Please see next page)

RESIDENTIAL (GROUP A) (Cont'd)

Remarks (Cont'd)

- (8) In determining the relevant maximum plot ratio/gross floor area for the purposes of paragraphs (1) to (4) above, any floor space that is constructed or intended for use solely as car park, loading/unloading bay, plant room and caretaker's office, or caretaker's quarters and recreational facilities for the use and benefit of all the owners or occupiers of the domestic building or domestic part of the building, provided such uses and facilities are ancillary and directly related to the development or redevelopment, may be disregarded.
- (9) Where the permitted plot ratio as defined in Building (Planning) Regulations is permitted to be exceeded in circumstances as set out in Regulation 22(1) or (2) of the said Regulations, the plot ratio/gross floor area for the building on land to which paragraphs (1), (2), (3) or (4) above applies may be increased by the additional plot ratio by which the permitted plot ratio is permitted to be exceeded under and in accordance with the said Regulation 22(1) or (2), notwithstanding that the relevant maximum plot ratio/gross floor area specified in paragraphs (1) to (4) above may thereby be exceeded.
- (10) Based on the individual merits of a development or redevelopment proposal, minor relaxation of the plot ratio/gross floor area/building height restrictions stated in paragraphs (1) to (4) and (6) above may be considered by the Town Planning Board on application under section 16 of the Town Planning Ordinance.

RESIDENTIAL (GROUP B)

Column 1 Uses always permitted	Column 2 Uses that may be permitted with or without conditions on application to the Town Planning Board
Flat Government Use (Police Reporting Centre, Post Office only) House Library Residential Institution School (in free-standing purpose-designed building only) Utility Installation for Private Project	Ambulance Depot Eating Place Educational Institution Government Refuse Collection Point Government Use (not elsewhere specified) Hospital Hotel Institutional Use (not elsewhere specified) Market Mass Transit Railway Vent Shaft and/or Other Structure above Ground Level other than Entrances Off-course Betting Centre Office Petrol Filling Station Place of Entertainment Place of Recreation, Sports or Culture Private Club Public Clinic Public Convenience Public Transport Terminus or Station Public Utility Installation Public Vehicle Park (excluding container vehicle) Recyclable Collection Centre Religious Institution School (not elsewhere specified) Shop and Services Social Welfare Facility Training Centre

Planning Intention

This zone is intended primarily for medium-density residential developments where commercial uses serving the residential neighbourhood may be permitted on application to the Town Planning Board.

(Please see next page)

RESIDENTIAL (GROUP B) (Cont'd)

Remarks

- (1) No new development, or addition, alteration and/or modification to or redevelopment of an existing building shall result in a total development and/or redevelopment in excess of a maximum plot ratio of 5.0, or the plot ratio of the existing building, whichever is the greater.
- (2) In determining the maximum plot ratio for the purposes of paragraph (1), any floor space that is constructed or intended for use solely as car park, loading/unloading bay, plant room and caretakers' office or caretakers' quarters and recreational facilities for the use and benefit of all the owners or occupiers of the domestic building or domestic part of the building, provided such uses and facilities are ancillary and directly related to the development or redevelopment, may be disregarded.
- (3) Based on the individual merits of a development or redevelopment proposal, minor relaxation of the plot ratio restriction stated in paragraph (1) above may be considered by the Town Planning Board on application under section 16 of the Town Planning Ordinance.

GOVERNMENT, INSTITUTION OR COMMUNITY

Column 1 Uses always permitted	Column 2 Uses that may be permitted with or without conditions on application to the Town Planning Board
Ambulance Depot Animal Quarantine Centre (in Government building only) Broadcasting, Television and/or Film Studio Cable Car Route and Terminal Building Eating Place (Canteen, Cooked Food Centre only) Educational Institution Exhibition or Convention Hall Field Study/Education/Visitor Centre Government Refuse Collection Point Government Use (not elsewhere specified) Hospital Institutional Use (not elsewhere specified) Library Market Place of Recreation, Sports or Culture Public Clinic Public Convenience Public Transport Terminus or Station Public Utility Installation Public Vehicle Park (excluding container vehicle) Recyclable Collection Centre Religious Institution Research, Design and Development Centre School Service Reservoir Social Welfare Facility Training Centre Wholesale Trade	Animal Boarding Establishment Animal Quarantine Centre (not elsewhere specified) Columbarium Correctional Institution Crematorium Driving School Eating Place (not elsewhere specified) Flat Funeral Facility Helicopter Landing Pad Helicopter Fuelling Station Holiday Camp Hotel House Mass Transit Railway Vent Shaft and/or Other Structure above Ground Level other than Entrances Off-course Betting Centre Office Petrol Filling Station Place of Entertainment Private Club Radar, Telecommunications Electronic Microwave Repeater, Television and/or Radio Transmitter Installation Refuse Disposal Installation (Refuse Transfer Station only) Residential Institution Sewage Treatment/Screening Plant Shop and Services Utility Installation for Private Project Zoo

Planning Intention

This zone is intended primarily for the provision of Government, institution or community facilities serving the needs of the local residents and/or a wider district, region or the territory. It is also intended to provide land for uses directly related to or in support of the work of the Government, organizations providing social services to meet community needs, and other institutional establishments.

(Please see next page)

GOVERNMENT, INSTITUTION OR COMMUNITY (Cont'd)

Remarks

- (1) On land designated “Government, Institution or Community (1)”, no new development, or addition, alteration and/or modification to or redevelopment of an existing building shall result in a total development and/or redevelopment in excess of the maximum building heights, in terms of metres above Principal Datum, as stipulated on the Plan, or the height of the existing building, whichever is the greater.
- (2) Based on the individual merits of a development or redevelopment proposal, minor relaxation of the building height restrictions stated in paragraph (1) above may be considered by the Town Planning Board on application under section 16 of the Town Planning Ordinance.

OPEN SPACE

Column 1 Uses always permitted	Column 2 Uses that may be permitted with or without conditions on application to the Town Planning Board
Aviary Barbecue Spot Field Study/Education/Visitor Centre Park and Garden Pavilion Pedestrian Area Picnic Area Playground/Playing Field Promenade Public Convenience Sitting Out Area Zoo	Cable Car Route and Terminal Building Eating Place Government Refuse Collection Point Government Use (not elsewhere specified) Holiday Camp Mass Transit Railway Vent Shaft and/or Other Structure above Ground Level other than Entrances Place of Entertainment Place of Recreation, Sports or Culture Private Club Public Transport Terminus or Station Public Utility Installation Public Vehicle Park (excluding container vehicle) Religious Institution Service Reservoir Shop and Services Tent Camping Ground Utility Installation for Private Project

Planning Intention

This zone is intended primarily for the provision of outdoor open-air public space for active and/or passive recreational uses serving the needs of local residents as well as the general public.

OTHER SPECIFIED USES

Column 1 Uses always permitted	Column 2 Uses that may be permitted with or without conditions on application to the Town Planning Board
-----------------------------------	---

For “Business” only

Schedule I: for open-air development or for building other than industrial or industrial-office building[@]

Ambulance Depot	Broadcasting, Television and/or Film Studio
Commercial Bathhouse/Massage Establishment	Bus Depot (on land designated “OU (Business 1)” only)
Eating Place	Cargo Handling and Forwarding Facility
Educational Institution	Government Refuse Collection Point
Exhibition or Convention Hall	Government Use (not elsewhere specified)
Government Use (Police Reporting Centre, Post Office only)	Hotel
Information Technology and Telecommunications Industries	Mass Transit Railway Vent Shaft and/or Other Structure above Ground Level other than Entrances
Institutional Use (not elsewhere specified)	Non-polluting Industrial Use (not elsewhere specified)
Library	Petrol Filling Station
Non-polluting Industrial Use (excluding industrial undertakings involving the use/storage of Dangerous Goods [△])	School (not elsewhere specified)
Off-course Betting Centre	Social Welfare Facility (excluding those involving residential care)
Office	Warehouse (excluding Dangerous Goods Godown)
Place of Entertainment	Wholesale Trade
Place of Recreation, Sports or Culture	
Private Club	
Public Clinic	
Public Convenience	
Public Transport Terminus or Station	
Public Utility Installation	
Public Vehicle Park (excluding container vehicle)	
Radar, Telecommunications Electronic Microwave Repeater, Television and/or Radio Transmitter Installation	
Recyclable Collection Centre	
Religious Institution	
Research, Design and Development Centre	
School (excluding free-standing purpose-designed building and kindergarten)	
Shop and Services	
Training Centre	
Utility Installation for Private Project	

(Please see next page)

OTHER SPECIFIED USES (Cont'd)

Column 1 Uses always permitted	Column 2 Uses that may be permitted with or without conditions on application to the Town Planning Board
<u>For "Business" only</u> (Cont'd)	
Schedule II: for industrial or industrial-office building [@]	
Ambulance Depot	Broadcasting, Television and/or Film Studio
Art Studio (excluding those involving direct provision of services or goods)	Bus Depot (on land designated "OU (Business 1)" only)
Cargo Handling and Forwarding Facility (not elsewhere specified)	Cargo Handling and Forwarding Facility (Container Freight Station, free-standing purpose-designed Logistics Centre only)
Eating Place (Canteen only)	Industrial Use (not elsewhere specified)
Government Refuse Collection Point	Mass Transit Railway Vent Shaft and/or Other Structure above Ground Level other than Entrances
Government Use (not elsewhere specified)	Off-course Betting Centre
Information Technology and Telecommunications Industries	Office (not elsewhere specified)
Non-polluting Industrial Use (excluding industrial undertakings involving the use/storage of Dangerous Goods ^Δ)	Petrol Filling Station
Office (excluding those involving direct provision of customer services or goods)	Place of Recreation, Sports or Culture (not elsewhere specified)
Public Convenience	Private Club
Public Transport Terminus or Station	Shop and Services (not elsewhere specified) (ground floor only except Ancillary Showroom [#] which may be permitted on any floor)
Public Utility Installation	Vehicle Repair Workshop
Public Vehicle Park (excluding container vehicle)	Wholesale Trade
Radar, Telecommunications Electronic Microwave Repeater, Television and/or Radio Transmitter Installation	
Recyclable Collection Centre	
Research, Design and Development Centre	
Shop and Services (Motor-vehicle Showroom on ground floor, Service Trades only)	
Utility Installation for Private Project	
Warehouse (excluding Dangerous Goods Godown)	

In addition, for building without industrial undertakings involving offensive trades or the use/storage of Dangerous Goods^Δ, the following use is always permitted :

Office

(Please see next page)

OTHER SPECIFIED USES (Cont'd)

For "Business" only (Cont'd)

In addition, the following uses are always permitted in the purpose-designed non-industrial portion on the lower floors (except basements and floors containing wholly or mainly car parking, loading/unloading bays and/or plant room) of an existing building, provided that the uses are separated from the industrial uses located above by a buffer floor or floors and no industrial uses are located within the non-industrial portion:

In addition, the following uses may be permitted with or without conditions on application to the Town Planning Board in the purpose-designed non-industrial portion on the lower floors (except basements and floors containing wholly or mainly car parking, loading/unloading bays and/or plant room) of an existing building, provided that the use is separated from the industrial uses located above by a buffer floor or floors and no industrial uses are located within the non-industrial portion:

- Commercial Bathhouse/Massage Establishment
- Eating Place
- Educational Institution
- Exhibition or Convention Hall
- Institutional Use (not elsewhere specified)
- Library
- Off-course Betting Centre
- Office
- Place of Entertainment
- Place of Recreation, Sports or Culture
- Private Club
- Public Clinic
- Religious Institution
- School (excluding kindergarten)
- Shop and Services
- Training Centre

- Social Welfare Facility (excluding those involving residential care)

- @ An industrial or industrial-office building means a building which is constructed for or intended to be used by industrial or industrial-office purpose respectively as approved by the Building Authority.
- △ Dangerous Goods refer to substances classified as Dangerous Goods and requiring a licence for their use/storage under the Dangerous Goods Ordinance (Cap. 295).
- # Ancillary Showroom requiring planning permission refers to showroom use of greater than 20% of the total usable floor area of an industrial firm in the same premises or building.

(Please see next page)

OTHER SPECIFIED USES (Cont'd)

For "Business" only (Cont'd)

Planning Intention

This zone is intended primarily for general business uses. A mix of information technology and telecommunications industries, non-polluting industrial, office and other commercial uses are always permitted in new "business" buildings. Less fire hazard-prone office use that would not involve direct provision of customer services or goods to the general public is always permitted in existing industrial or industrial-office buildings.

Remarks

- (1) No new development, or addition, alteration and/or modification to or redevelopment of an existing building shall result in a total development and/or redevelopment in excess of a maximum plot ratio of 12.0, and the maximum building heights, in terms of metres above Principal Datum, as stipulated on the Plan, or the plot ratio and height of the existing building, whichever is the greater.
- (2) In determining the maximum plot ratio for the purposes of paragraph (1) above, any floor space that is constructed or intended for use solely as car park, loading/unloading bay, plant room and caretaker's office, provided such uses and facilities are ancillary and directly related to the development or redevelopment, may be disregarded.
- (3) Where the permitted plot ratio as defined in Building (Planning) Regulations is permitted to be exceeded in circumstances as set out in Regulation 22(1) or (2) of the said Regulations, the plot ratio for the building on land to which paragraph (1) applies may be increased by the additional plot ratio by which the permitted plot ratio is permitted to be exceeded under and in accordance with the said Regulation 22(1) or (2), notwithstanding that the relevant maximum plot ratio specified in paragraph (1) above may thereby be exceeded.
- (4) Based on the individual merits of a development or redevelopment proposal, minor relaxation of the plot ratio/building height restrictions stated in paragraph (1) above may be considered by the Town Planning Board on application under section 16 of the Town Planning Ordinance.

(Please see next page)

OTHER SPECIFIED USES (Cont'd)

Column 1 Uses always permitted	Column 2 Uses that may be permitted with or without conditions on application to the Town Planning Board
-----------------------------------	---

For "Petrol Filling Station" only

Petrol Filling Station

Government Use
Utility Installation not Ancillary to the
Specified Use

Planning Intention

This zone is intended primarily for the provision of petrol filling stations serving the needs of local residents as well as the general public.

(Please see next page)

OTHER SPECIFIED USES (Cont'd)

Column 1 Uses always permitted	Column 2 Uses that may be permitted with or without conditions on application to the Town Planning Board
-----------------------------------	---

For "Sewage Treatment Plant" only

Sewage Treatment/Screening Plant	Government Use (not elsewhere specified) Utility Installation not Ancillary to the Specified Use
----------------------------------	---

Planning Intention

This zone is intended primarily for the provision of sewage treatment/screening plant serving the needs of the general public.

Remarks

- (1) No new development, or addition, alteration and/or modification to or redevelopment of an existing building shall result in a total development and/or redevelopment in excess of the maximum building height, in terms of metres above Principal Datum, as stipulated on the Plan, or the height of the existing building, whichever is the greater.
- (2) Based on the individual merits of a development or redevelopment proposal, minor relaxation of the building height restrictions stated in paragraph (1) above may be considered by the Town Planning Board on application under section 16 of the Town Planning Ordinance.

GREEN BELT

Column 1 Uses always permitted	Column 2 Uses that may be permitted with or without conditions on application to the Town Planning Board
Agricultural Use Barbecue Spot Government Use (Police Reporting Centre only) Nature Reserve Nature Trail On-Farm Domestic Structure Picnic Area Public Convenience Tent Camping Ground Wild Animals Protection Area	Animal Boarding Establishment Broadcasting, Television and/or Film Studio Cable Car Route and Terminal Building Columbarium (within a Religious Institution or extension of existing Columbarium only) Crematorium (within a Religious Institution or extension of existing Crematorium only) Field Study/Education/Visitor Centre Flat Government Refuse Collection Point Government Use (not elsewhere specified) Helicopter Landing Pad Holiday Camp House Mass Transit Railway Vent Shaft and/or Other Structure above Ground Level other than Entrances Petrol Filling Station Place of Recreation, Sports or Culture Public Transport Terminus or Station Public Utility Installation Public Vehicle Park (excluding container vehicle) Radar, Telecommunications Electronic Microwave Repeater, Television and/or Radio Transmitter Installation Religious Institution Residential Institution School Service Reservoir Social Welfare Facility Utility Installation for Private Project Zoo

Planning Intention

The planning intention of this zone is primarily for the conservation of the existing natural environment amid the built-up areas/at the urban fringe, to safeguard it from encroachment by urban type development, and to provide additional outlets for passive recreational activities. There is a general presumption against development within this zone.

KOWLOON PLANNING AREA NO. 14 (PART)

**DRAFT KWUN TONG (SOUTH)
OUTLINE ZONING PLAN NO. S/K14S/21A**

EXPLANATORY STATEMENT

KOWLOON PLANNING AREA NO. 14 (PART)

**DRAFT KWUN TONG (SOUTH)
OUTLINE ZONING PLAN NO. S/K14S/21A**

<u>Contents</u>	<u>Page</u>
1. INTRODUCTION	1
2. AUTHORITY FOR THE PLAN AND PROCEDURES	1
3. OBJECT OF THE PLAN	3
4. NOTES OF THE PLAN	43
5. THE PLANNING SCHEME AREA	4
6. POPULATION	4
7. BUILDING HEIGHT RESTRICTIONS IN KWUN TONG BUSINESS AREA	4
8. LAND USE ZONINGS	
8.1 Commercial (1)	6
8.2 Residential (Group A)	6
8.3 Residential (Group B)	98
8.4 Government, Institution or Community	9
8.5 Open Space	10
8.6 Other Specified Uses	10
8.7 Green Belt	11
9. COMMUNICATIONS	12
10. URBAN RENEWAL AUTHORITY DEVELOPMENT SCHEME PLAN AREAS	1342
11. UTILITY SERVICES	13
12. IMPLEMENTATION	13

KOWLOON PLANNING AREA NO. 14 (PART)

DRAFT KWUN TONG (SOUTH) OUTLINE ZONING PLAN NO. S/K14S/21A

(Being a Draft Plan for the Purposes of the Town Planning Ordinance)

EXPLANATORY STATEMENT

Note: For the purposes of the Town Planning Ordinance, this statement shall not be deemed to constitute a part of the Plan.

1. INTRODUCTION

This explanatory statement is intended to assist an understanding of the draft Kwun Tong (South) Outline Zoning Plan (OZP) No. S/K14S/21A ~~(the Plan)~~. It reflects the planning intention and objectives of the Town Planning Board (the Board) for the various land use zonings of the Plan.

2. AUTHORITY FOR THE PLAN AND PROCEDURES

- 2.1 On 9 January 1959, the draft Ngau Tau Kok Village - Proposed Layout Plan No. LK 15/24/2, being the first statutory plan covering the western part of the Kwun Tong area, was gazetted under section 5 of the Town Planning Ordinance (the Ordinance). On 9 June 1959, the then Governor-in-Council (G in C) under the then section 8(1) of the Ordinance, approved the draft Layout Plan. In January 1964, the approved Layout Plan was referred back to the Board for amendment. On 25 September 1964, the Ngau Tau Kok Village Layout Plan No. LK 14/17, which replaced the Plan No. LK 15/24/2, was gazetted under section 5 of the Ordinance, and was subsequently approved by the then G in C on 9 March 1965 under the then section 8(1) of the Ordinance.
- 2.2 On 9 May 1984, the Board was directed under section 3 of the Ordinance to prepare a draft statutory plan for the Kwun Tong and Lam Tin areas. On 26 August 1986, the approved Ngau Tau Kok Village Layout Plan was referred back to the Board for amendment under section 12(1)(b)(ii) of the Ordinance. On 11 December 1987, the draft Kwun Tong OZP No. S/K14/1 was exhibited for public inspection under section 5 of the Ordinance. The OZP was subsequently amended twice and exhibited for public inspection under section 6(7) and 7 of the Ordinance. On 1 May 1990, the then G in C agreed to refer the OZP No. S/K14/4 to the Board for further consideration and amendment under section 9(1)(c) of the Ordinance.
- 2.3 Under the power delegated by the then Governor, the then Secretary for Planning, Environment and Lands, directed the Board on 3 February 1993, under section 3(1)(a) of the Ordinance, to prepare a separate draft OZP for the Anderson Road Quarries and the adjoining area to tie in with the rehabilitation scheme of Anderson Road Quarries. In this connection, the land north of Sau Mau Ping Road was excised from the draft Kwun Tong OZP and the OZP was

re-named as the draft Kwun Tong (South) OZP. On 21 May 1993, the draft Kwun Tong (South) OZP No. S/K14S/1 was exhibited for public inspection under section 5 of the Ordinance. The OZP was subsequently amended four times and exhibited for public inspection under section 7 of the Ordinance.

- 2.4 On 14 September 1999, the Chief Executive in Council (CE in C), under section 9(1)(a) of the Ordinance, approved the draft Kwun Tong (South) OZP, which was subsequently renumbered as S/K14S/6. On 19 September 2000, the CE in C referred the approved OZP No. S/K14S/6 to the Board for amendment under section 12(1)(b)(ii) of the Ordinance. The OZP was subsequently amended once and exhibited for public inspection under section 5 of the Ordinance.
- 2.5 On 10 July 2001, the CE in C, under section 9(1)(a) of the Ordinance, approved the draft Kwun Tong (South) OZP, which was subsequently renumbered as S/K14S/8. On 25 September 2001, the CE in C referred the approved OZP No. S/K14S/8 to the Board for amendment under section 12(1)(b)(ii) of the Ordinance. The OZP was subsequently amended once and exhibited for public inspection under section 5 of the Ordinance.
- 2.6 On 16 March 2004, the CE in C, under section 9(1)(a) of the Ordinance, approved the draft Kwun Tong (South) OZP, which was subsequently renumbered as S/K14S/10. On 5 October 2004, the CE in C referred the approved OZP No. S/K14S/10 to the Board for amendment under section 12(1)(b)(ii) of the Ordinance. The OZP was subsequently amended three times and exhibited for public inspection under section 5 or 7 of the Ordinance.
- 2.7 On 27 March 2007, the CE in C, under section 9(1)(a) of the Ordinance, approved the draft Kwun Tong (South) OZP, which was subsequently renumbered as S/K14S/14. On 5 June 2007, the CE in C referred the approved OZP No. S/K14S/14 to the Board for amendment under section 12(1)(b)(ii) of the Ordinance.
- 2.8 On 5 October 2007, the draft Kwun Tong (South) OZP No. S/K14S/15, mainly indicating two areas of the Plan replaced by the draft Urban Renewal Authority (URA) Kwun Tong Town Centre (KTTC) – Main Site Development Scheme Plan (DSP) No. S/K14S/URA1/1 and the draft URA KTTC – Yuet Wah Street Site DSP No. S/K14S/URA2/1, was exhibited for public inspection under section 5 of the Ordinance.
- 2.9 On 15 July 2008, the CE in C, under section 9(1)(a) of the Ordinance, approved the draft Kwun Tong (South) OZP, which was subsequently renumbered as S/K14S/16. On 7 February 2012, the CE in C referred the approved OZP No. S/K14S/16 to the Board for amendment under section 12(1)(b)(ii) of the Ordinance. The OZP was subsequently amended once and exhibited for public inspection under section 5 of the Ordinance.
- 2.10 On 4 June 2013, the CE in C, under section 9(1)(a) of the Ordinance, approved the draft Kwun Tong (South) OZP, which was subsequently renumbered as S/K14S/18. On 1 April 2014, the CE in C referred the approved OZP No. S/K14S/18 to the Board for amendment under section 12(1)(b)(ii) of the Ordinance. The OZP was subsequently amended once and exhibited for public inspection under section 5 of the Ordinance.

- 2.11 On 21 July 2015, the CE in C, under section 9(1)(a) of the Ordinance, approved the draft Kwun Tong (South) OZP, which was subsequently renumbered as S/K14S/20. On 18 October 2016, the CE in C referred the approved Kwun Tong (South) OZP No. S/K14S/20 to the Board for amendment under section 12(1)(b)(ii) of the Ordinance. The reference back of the OZP was notified in the Gazette on 28 October 2016 under section 12(2) of the Ordinance.
- 2.12 On 3 November 2017, the draft Kwun Tong (South) OZP No. S/K14S/21, incorporating amendments mainly to include the rezoning of a site at Ting On Street from “Government, Institution or Community” (“G/IC”) to “Residential (Group A)3” and inclusion of ‘Art Studio (excluding those involving direct provision of services or goods)’ as a Column 1 use in Schedule II for industrial or industrial-office (I-O) building of the “Other Specified Uses” annotated “Business” (“OU(B)”) zone was exhibited for public inspection under section 5 of the Ordinance. *During the two-month exhibition period, a total of 103 valid representations were received. On 26 January 2018, the representations were published for three weeks for public comment and a total of 5 comments were received. After giving consideration to the representations and comments, the Board on 27 July 2018 noted the supportive representations, and decided not to uphold the remaining representations and that no amendment should be made to the draft OZP to meet the representations.*
- 2.13 *On _____ 2018, the CE in C, under section 9(1)(a) of the Ordinance, approved the draft Kwun Tong (South) OZP, which was subsequently renumbered as S/K14S/22. On _____ 2018, the approved Kwun Tong (South) OZP No. S/K14S/22 (the Plan) was exhibited for public inspection under section 9(5) of the Ordinance.*

3. OBJECT OF THE PLAN

- 3.1 The object of the Plan is to indicate the broad land use zonings and major transport network so that development and redevelopment of land within the Planning Scheme Area (the Area) can be put under statutory planning control.
- 3.2 The Plan is to illustrate the broad principles of development and to provide guidance for more detailed planning within the Area. It is a small-scale plan and the transport alignments and boundaries between the land use zones may be subject to minor adjustments as detailed planning proceeds.
- 3.3 Since the Plan is to show broad land use zonings, there would be situations in which small strips of land not intended for building development purposes and carry no development right under the lease, such as the areas restricted for garden, slope maintenance and access road purposes, are included in the residential zones. The general principle is that such areas should not be taken into account in plot ratio calculation. Development within residential zones should be restricted to building lots carrying development right in order to maintain the character and amenity of the Kwun Tong (South) area and not to overload the road network in this area.

4. NOTES OF THE PLAN

- 4.1 Attached to the Plan is a set of Notes which shows the types of uses or developments which are always permitted within the Area and in particular zones and which may be permitted by the Board, with or without conditions, on application. The provision for application for planning permission under section 16 of the Ordinance allows greater flexibility in land use planning and control of development to meet changing needs.
- 4.2 For the guidance of the general public, a set of definitions that explains some of the terms used in the Notes may be obtained from the Technical Services Division of the Planning Department and can be downloaded from the Board's website at <http://www.info.gov.hk/tpb>.

5. THE PLANNING SCHEME AREA

- 5.1 The Area is located in East Kowloon within the Kwun Tong District. It is bounded by Hoi Bun Road, Shun Yip Street and Ngau Tau Kok Road to the west; Chun Wah Road and Sau Mau Ping Road to the north; and Lei Yue Mun Road and King Yip Street to the south. The eastern boundary largely follows the district administrative boundary for the Kwun Tong District. The boundary of the Area is shown in a heavy broken line on the Plan and includes the two areas designated as "URA KTTC DSP Area". It covers about 387 hectares of land.
- 5.2 The Area can be separated into two portions in terms of land use. The portion to the south-west of Kwun Tong Road, which was formed by reclamation in the 1950s, is the Kwun Tong Business Area (KTBA), which is one of the major employment centres in the main urban area. The area is under transformation to meet the changing needs of the non-polluting industrial and business sectors. The portion to the northeast of Kwun Tong Road and Lei Yue Mun Road is predominantly occupied by residential developments, particularly public housing estates.

6. POPULATION

Based on the 2011 Population Census, the population of the Area was estimated by the Planning Department as about 307,900 persons. It is estimated that the planned population of the Area would be about 318,700 persons.

7. BUILDING HEIGHT RESTRICTIONS IN KWUN TONG BUSINESS AREA

- 7.1 As revealed from the public consultations undertaken under the Study of Urban Design Guidelines for Hong Kong (2003), the community was in general support of the initiative to instigate height control in the statutory plans to protect views to the ridgelines from popular vantage points. In taking this forward, proposals for building height restriction for the Kwun Tong and Kowloon Bay Business Areas were prepared and put forward for public consultation between May and July 2004. The proposals were generally

supported by the community as a means to preserve the views to the ridgelines and to enhance the urban environment.

- 7.2 In main, the building height restrictions are to preserve the views to the Kowloon Ridgelines from the vantage points recommended in the Urban Design Guidelines Study, taking into account the local area context and the need to maintain visually compatible building masses in the wider setting. There are four height bands – 100 metres above Principal Datum (mPD), 130mPD, 160mPD and 200mPD imposed for the commercial, business and industrial developments in KTBA, for preserving views to the ridgelines and reinforcing discernible district centre character at the main activity node of the Mass Transit Railway (MTR) Kwun Tong Station and KTTC. These height bands help achieve a stepped height profile for visual permeability, reduce the solidness of KTBA and maintain a more intertwined relationship with the Victoria Harbour edge. Sharp contrast and significant visual barrier to adjacent major residential development such as Laguna City is also avoided.
- 7.3 Building height restrictions for Government, institution or community (GIC) and utility sites in KTBA in height bands of 15mPD and 40mPD are also incorporated to provide visual relief to the high density environment of KTBA.
- 7.4 A minor relaxation clause in respect of the building height restrictions is incorporated into the Notes of the Plan in order to provide incentive for development/redevelopments with design merits/planning gains. Each application for minor relaxation of building height restriction under section 16 of the Ordinance will be considered on its own merits and the relevant criteria for consideration of such relaxation are as follows:
- (a) amalgamating smaller sites for achieving better urban design and local area improvements;
 - (b) accommodating the bonus plot ratio granted under the Buildings Ordinance in relation to surrender/dedication of land/area for use as public passage/street widening;
 - (c) providing better streetscape/good quality street level public urban space;
 - (d) providing separation between buildings to enhance air ventilation and visual permeability;
 - (e) accommodating building design to address specific site constraints in achieving the permissible plot ratio under the Plan; and
 - (f) other factors such as the need for tree preservation, innovative building design and planning merits that would bring about improvements to townscape and amenity of the locality, provided that no adverse landscape and visual impacts would be resulted from the innovative building design.
- 7.5 However, for existing buildings where the building height has already exceeded the maximum building height restrictions in terms of mPD and/or number of

storeys as stipulated on the Plan, there is a general presumption against such application for minor relaxation unless under exceptional circumstances.

- 7.6 Building height restrictions have also been incorporated for some development sites outside KTBA. The criteria as mentioned in paragraphs 7.4 and 7.5 above are also relevant for consideration of application for minor relaxation of the building height restrictions for these sites.

8. LAND USE ZONINGS

8.1 “Commercial (1)” (“C(1)”) - Total Area 1.21 ha

8.1.1 This zone is intended primarily for commercial developments, which may include shop, service, place of entertainment and eating place serving the needs of local workers.

8.1.2 There are a total of seven sites under “C(1)” zoning. They are located in KTBA to the south of Kwun Tong Road. These commercial sites, which are either located near road junctions or major transport interchanges, have been developed to provide commercial facilities for the workers. Multi-storey car parks are incorporated in some of the developments.

8.1.3 A maximum plot ratio of 12.0 is imposed on these commercial sites so as not to aggravate the existing traffic problems in the Area. In the circumstances set out in Regulation 22 of the Building (Planning) Regulations, the above specified maximum plot ratio may be increased by what is permitted to be exceeded under Regulation 22. This is to maintain flexibility for unique circumstances such as dedication of part of a site for road widening or public uses.

8.1.4 Developments and redevelopments in the “C(1)” sites are subject to maximum building heights of 100mPD or 130mPD as stipulated on the Plan.

8.1.5 To provide design/architectural flexibility, minor relaxation of the plot ratio/building height restrictions may be considered by the Board on application under section 16 of the Ordinance. The criteria given in paragraphs 7.4 and 7.5 above would be relevant for the assessment of minor relaxation of building height restriction. However, for any existing building with plot ratio already exceeding the restriction as stipulated in the Notes, there is a general presumption against such application for minor relaxation of the plot ratio restriction unless under exceptional circumstances. Each application will be considered on its own merits.

8.2 “Residential (Group A)” (“R(A)”) - Total Area 137.73 ha

8.2.1 This zone is intended primarily for high-density residential developments. Commercial uses are always permitted on the lowest

three floors of a building or in the purpose-designed non-residential portion of an existing building.

8.2.2 Existing public rental housing (PRH) estates in the Area include Lok Wah (North and South) Estate, Upper Ngau Tau Kok Estate, Sau Mau Ping Estate, Sau Mau Ping South Estate, Wo Lok Estate, Wan Hon Estate, Tsui Ping (North and South) Estate, Kai Tin Estate, Ping Tin Estate, On Tin Estate, Hing Tin Estate, Lam Tin Estate and Tak Tin Estate. Existing Home Ownership Scheme developments include Lok Nga Court, Lei On Court, On Kay Court, Chun Wah Court, Cheung Wo Court, Hong Tin Court, Hong Yat Court, Hiu Lai Court, Po Pui Court, Hong Wah Court and Hong Ying Court. Existing public housing developments under the Hong Kong Housing Society include Lotus Tower and Kwun Tong Garden Estate Phase II.

8.2.3 A site along Sau Ming Road, which is zoned “R(A)2”, is being developed for PRH cum community hall development. To prevent massive and out-of-context development, the site is subject to a maximum building height of 150mPD as stated in the Notes, a maximum domestic plot ratio of 4.5 and a maximum non-domestic plot ratio of 1.5. Various GIC facilities including a community hall, a small public library and a study area would be provided within the development. A site abutting both Hiu Ming Street and Hiu Kwong Street is reserved for PRH development and is subject to maximum building heights of 80mPD (for the upper platform and its adjoining slope) and 150mPD (for the lower platform) as shown on the Plan. A site abutting both Ting On Street and Ngau Tau Kok Road, which is zoned “R(A)3”, is proposed for public housing development and is subject to a maximum building height of 110mPD as shown on the Plan. To increase building permeability and allow more wind penetration, two setbacks shall be provided along Ting On Street and Ngau Tau Kok Road and a stepped terrace architectural design shall be adopted for minimizing the podium structure at the “R(A)3” site. In order to minimize any adverse air ventilation impact on the surrounding low to medium-rise developments, a quantitative air ventilation assessment is required at the detailed design stage to explore more opportunity on scheme improvement.

8.2.4 A wide range of GIC facilities such as primary schools, community halls, children and youth centres, elderly centres, local open space, indoor games halls, markets and shopping centres are provided within these estates to serve the residents. Some of the community facilities are free-standing within the housing estates. They are as follows:

<u>Name of Estate</u>	<u>No. of Free-standing Facilities</u>
Lok Wah Estate	2 primary schools and 1 community centre
Tsui Ping Estate	1 primary school
Lam Tin Estate	1 municipal services building
Ping Tin Estate	2 primary schools
Sau Mau Ping Estate	4 primary schools
Upper Ngau Tau Kok Estate	1 primary school

These school and GIC facilities, existing or planned, are zoned “R(A)” on the OZP so as to allow for flexibility in the comprehensive planning and development of these large residential sites.

- 8.2.5 Existing private residential developments include those to the north/west of KTTC, as well as those at On Wah Street, Ting On Street, Hiu Kwong Street and Kai Tin Road.
- 8.2.6 In the consideration of the overall transport, environmental and infrastructural constraints as well as the adequacy in the provision of community facilities envisioned in the Kowloon Density Study Review, completed in early 2002, developments or redevelopments within this zone are subject to specific control on plot ratios except otherwise specified in the Notes, i.e. a maximum plot ratio of 7.5 for a domestic building and a maximum plot ratio of 9.0 for a partly domestic and partly non-domestic building. In calculating the gross floor areas for these developments/redevelopments, the sites for free-standing purpose-designed buildings that are used solely for accommodating school or other GIC facilities, including those located on ground and on building podium, are not to be taken as parts of the site.
- 8.2.7 The northern part of Sceneway Garden which is a comprehensive private residential development above the public transport interchange is within the “R(A)1” zone. The southern part of the development is built on top of the MTR Lam Tin Station on the other side of Lei Yue Mun Road which falls within the Cha Kwo Ling, Yau Tong, Lei Yue Mun OZP, that is outside the Plan area. A landscaped deck is built over the road linking the two parts of the development together. To ensure that the intensity of this private development is under statutory planning control, a maximum domestic gross floor area is imposed under the Notes of the Plan.
- 8.2.8 In the circumstances set out in Regulation 22 of the Building (Planning) Regulations, the above specified maximum plot ratios or gross floor areas may be increased by what is permitted to be exceeded under Regulation 22. This is to maintain flexibility for unique circumstances such as dedication of part of a site for road widening or public uses.
- 8.2.9 To provide design/architectural flexibility, minor relaxation of the plot ratio/gross floor area/building height restrictions may be considered by the Board on application under section 16 of the Ordinance. The criteria given in paragraphs 7.4 and 7.5 above would be relevant for the assessment of minor relaxation of building height restriction. However, for any existing building with plot ratio/gross floor area already exceeding the restrictions as stipulated in the Notes, there is a general presumption against such application for minor relaxation of the plot ratio/gross floor area restrictions unless under exceptional circumstances. Each application will be considered on its own merits.

8.3 “Residential (Group B)” (“R(B)”) - Total Area 14.46 ha

- 8.3.1 This zone is intended primarily for medium-density residential developments where commercial uses serving the residential neighbourhood may be permitted on application to the Board. The private residential developments along Kung Lok Road, Hong Lee Road, Yuet Wah Street, Tin Heung Street and upper sections of Hong Ning Road and Hip Wo Street fall within this zone.
- 8.3.2 Developments within this zone are subject to a maximum plot ratio of 5.0 in order to restrain traffic growth which will otherwise overload the existing and planned road network.
- 8.3.3 To provide design/architectural flexibility, minor relaxation of the plot ratio restriction may be considered by the Board on application under section 16 of the Ordinance. However, for any existing building with plot ratio already exceeding the restriction as stipulated in the Notes, there is a general presumption against such application for minor relaxation of the plot ratio restriction unless under exceptional circumstances. Each application will be considered on its own merits.

8.4 “Government, Institution or Community” (“G/IC”) - Total Area 44.93 ha

- 8.4.1 This zone is intended primarily for the provision of GIC facilities serving the needs of the local residents and/or a wider district, region or the territory. It is also intended to provide land for uses directly related to or in support of the work of the Government, organizations providing social services to meet community needs, and other institutional establishments.
- 8.4.2 Major existing GIC facilities include United Christian Hospital at Sau Nga Road, Ngau Tau Kok Jockey Club Clinic at Ting On Street, Lam Tin Polyclinic at Kai Tin Road, Ngau Tau Kok Government Offices at On Wah Street, Hong Kong Public Records Building at Tsui Ping Road, various social welfare facilities at Kung Lok Road, Kwun Tong Road, Fuk Tong Road and Fuk Ning Road, two vocational training centres at Wan Hon Street and Tsui Ping Road, two Municipal Services Buildings at Ngau Tau Kok Road and Shui Wo Street, two divisional police stations at Hong Ning Road and Lei Yue Mun Road, two sub-divisional fire stations at Hoi Yuen Road and Kai Tin Road, a Disciplined Services Quarters at Wo Hong Path, a market complex at Yee On Street, a sports centre at Hiu Kwong Street, a swimming pool complex at Tsui Ping Road, service reservoirs, pumping stations, electricity substations, telephone exchanges, community centres, churches, a higher educational facility and a number of primary and secondary schools.
- 8.4.3 Developments and redevelopments in the “G/IC(1)” sites in KTBA to the south of Kwun Tong Road are subject to a maximum building height of 15mPD or 40mPD as stipulated on the Plan.

8.4.4 To provide design/architectural flexibility, minor relaxation of the building height restriction may be considered by the Board on application under section 16 of the Ordinance pursuant to the criteria given in paragraphs 7.4 and 7.5 above. Each application will be considered on its own merits.

8.5 “Open Space” (“O”) - Total Area 41.43 ha

8.5.1 This zone is intended primarily for the provision of outdoor open-air public space for active and/or passive recreational uses serving the needs of local residents as well as the general public.

8.5.2 Major existing open spaces in the Area include Kwun Tong Recreation Ground, Hong Ning Road Recreation Ground, Sau Ming Road Park, Hoi Bun Road Park, Lam Tin Park, Hong Ning Road Park, the playgrounds at On Tak Road, Kung Lok Road, Yuet Wah Street, Sau Nga Road, Hiu Ming Street, Tsun Yip Street, and a number of rest gardens/sitting-out areas at various locations. Additional sites have been reserved at Kai Tin Road and Tseung Kwan O Road.

8.5.3 Soccer pitches and play-areas are also provided on top of the decked service reservoirs and local open spaces are provided within public housing estates and comprehensive private housing developments.

8.6 “Other Specified Uses” (“OU”) - Total Area 46.82 ha

8.6.1 This zoning covers land allocated for specific uses which include Business, Petrol Filling Station and Sewage Treatment Plant.

8.6.2 About 45.57 ha of land is zoned “OU” annotated “Business” (“OU(B)”). This zone is intended primarily for general business uses. A mix of information technology and telecommunications industries, non-polluting industrial, office and other commercial uses are always permitted in new “business” buildings. Less fire hazard-prone office use that would not involve direct provision of customer services or goods to the general public is always permitted in existing industrial and I-O buildings. As it is not possible to phase out existing polluting and hazardous industrial uses all at once on land zoned “OU(B)”, it is necessary to ensure compatibility of the uses within the same industrial or I-O building and in KTBA until the whole area is transformed to cater for the new non-polluting business uses. The setting back of buildings to cater for the future increase in traffic demand may also be required. The setback requirements are stipulated in departmental outline development plans and enforced through lease modification process where appropriate.

8.6.3 A site at How Ming Street to the northwest of Tsun Yip Street Playground is zoned “OU(B)1”. It is also for general employment uses with the same planning intention as stated in paragraph 8.6.2. However, in order to make provision for redevelopment of the vacated bus depot if necessary, ‘Bus Depot’ use is included in Column 2 of the

“OU(B)1” zone to allow the Board to scrutinise any submitted proposals to its satisfaction.

- 8.6.4 Developments and redevelopments in the “OU(B)” and “OU(B)1” sites are subject to a maximum plot ratio of 12.0. Reference should be made to the relevant Town Planning Board Guidelines. In the circumstances set out in Regulation 22 of the Building (Planning) Regulations, the above specified maximum plot ratio may be increased by what is permitted to be exceeded under Regulation 22. This is to maintain flexibility for unique circumstances such as dedication of part of a site for road widening or public uses.
- 8.6.5 The sewage treatment plant at Wing Yip Street zoned “OU” annotated “Sewage Treatment Plant” is intended primarily for the provision of sewage treatment/screening plant serving the needs of the general public.
- 8.6.6 Developments and redevelopments in the “OU(B)” and “OU(B)1” sites are subject to maximum building heights ranging from 100mPD to 200mPD as stipulated on the Plan. Development and redevelopment in the “OU” annotated “Sewage Treatment Plant” site is subject to a maximum building height of 15mPD.
- 8.6.7 To provide design/architectural flexibility, minor relaxation of the plot ratio/building height restrictions may be considered by the Board on application under section 16 of the Ordinance. The criteria given in paragraphs 7.4 and 7.5 above would be relevant for the assessment of minor relaxation of building height restriction. However, for any existing building with plot ratio already exceeding the restriction as stipulated in the Notes, there is a general presumption against such application for minor relaxation of the plot ratio restriction unless under exceptional circumstances. Each application will be considered on its own merits.
- 8.6.8 The petrol filling stations at Kwun Tong Road and Hiu Kwong Street zoned “OU” annotated “Petrol Filling Station” are intended primarily for the provision of petrol filling stations serving the needs of local residents as well as the general public.
- 8.7 “Green Belt” (“GB”) - Total Area 28.50 ha
- 8.7.1 The planning intention of this zone is primarily for the conservation of the existing natural environment amid the built-up areas/at the urban fringe, to safeguard it from encroachment by urban type development, and to provide additional outlets for passive recreational activities. There is a general presumption against development within this zone. Development within this zone will be carefully controlled and development proposals will be assessed on individual merits taking into account the relevant Town Planning Board Guidelines.
- 8.7.2 It includes the closed Ma Yau Tong West and Ma Yau Tong Central landfill sites. Restoration works for recreational after-use are currently in

progress. Part of Lam Tin Park and hillslopes at various locations are also within this zone.

9. COMMUNICATIONS

9.1 Roads

9.1.1 The primary distributors in the Area include Kwun Tong By-pass and Tseung Kwan O Road. Kwun Tong By-pass along the southwestern boundary of the Area links Eastern Harbour Crossing in the southeast and Tseung Kwan O Tunnel via Tseung Kwan O Road in the northeast. This By-pass also forms part of the road network connecting the Eastern Harbour Crossing to the approaches of the Tate's Cairn Tunnel portal at Diamond Hill. Tseung Kwan O Road links Tseung Kwan O New Town via Tseung Kwan O Tunnel, which forms the principal access from the main urban areas to the New Town.

9.1.2 Major district distributors in the Area include Kwun Tong Road, Lei Yue Mun Road and Wai Yip Street. These distributors, running in a northwest and southeast direction, connect the Area, in particular KTBA, with Central and West Kowloon. The business area is also served by local distributors including Hung To Road, Lai Yip Street, Tsun Yip Street and Hoi Yuen Road.

9.1.3 Sau Mau Ping Road, Tsui Ping Road, Hip Wo Street and Hong Ning Road are the major local distributors in the north-eastern part of the Area. The main function of these roads is to serve the residents of the public and private housing developments in the Area. Sau Mau Ping Road at the northern edge of the Area together with Shun Lee Tsuen Road and Po Lam Road also provide external linkages to Central and West Kowloon to the west, and Sai Kung and Tseung Kwan O to the east.

9.2 Mass Transit Railway

The existing MTR Kwun Tong Line runs along Kwun Tong Road and Lei Yue Mun Road on elevated tracks. It connects Tseung Kwan O Line with interchange at MTR Yau Tong Station for harbour crossing. There are two stations in the Area, namely, MTR Ngau Tau Kok Station and MTR Kwun Tong Station.

9.3 Public Transport

Apart from the MTR, the Area is also well served by various modes of public transport including bus and public light bus. A number of bus termini are conveniently located to serve the residential, commercial, business and industrial developments in the Area.

10. URBAN RENEWAL AUTHORITY DEVELOPMENT SCHEME PLAN AREAS

- 10.1 Two areas have been designated as “URA DSP Areas”. The land use zonings of the areas are depicted on the relevant URA DSPs and they will be implemented by the URA.
- 10.2 The DSP for KTTC – Main Site covers an area of about 4.63 ha. The site is intended for comprehensive development/redevelopment of the area for residential, Government and/or commercial uses with the provision of open space and other community and supporting facilities. The DSP for KTTC – Yuet Wah Street Site covers an area of about 0.43 ha. The site is developed as a high-density residential development with Kwun Tong Community Health Centre in the podium serving the wider district.
- 10.3 On 15 July 2008, the CE in C, under section 9(1)(a) of the Ordinance, approved the draft URA KTTC – Main Site DSP and draft URA KTTC – Yuet Wah Street Site DSP which were subsequently renumbered as S/K14S/URA1/2 and S/K14S/URA2/2 respectively. On 12 September 2008, the approved URA KTTC – Main Site DSP No. S/K14S/URA1/2 and approved URA KTTC – Yuet Wah Street Site DSP No. S/K14S/URA2/2 were exhibited for public inspection under section 9(5) of the Ordinance.

11 UTILITY SERVICES

- 11.1 The Area is well served with piped water supply, drainage and sewerage systems. Electricity, gas and telephone services are also available. No difficulty is envisaged in meeting the future requirements. Improvement works to the existing drainage and sewerage systems may be required for the possible change of stormwater flow due to topographic changes arising from development.
- 11.2 The project of “East Kowloon Sewerage Improvement and Pollution Control” undertaken by the Drainage Services Department to improve the existing sewerage system and abate the pollution problem in East Kowloon has been completed.

12. IMPLEMENTATION

- 12.1 Although existing uses non-conforming to the statutory zoning are tolerated, any material change of use and any other development/redevelopment must be always permitted in terms of the Plan or, if permission is required, in accordance with the permission granted by the Board. The Board has published a set of guidelines for the interpretation of existing use in the urban and new town areas. Any person who intends to claim an “existing use right” should refer to the guidelines and will need to provide sufficient evidence to support his claim. The enforcement of the zonings mainly rests with the Buildings Department, the Lands Department and the various licensing authorities.

- 12.2 The Plan provides a broad land use framework within which more detailed non-statutory plans for the Area are prepared by the Planning Department. These detailed plans are used as the basis for public works planning and site reservation within the Government. Disposal of sites is undertaken by the Lands Department. Public works projects are co-ordinated by the Civil Engineering and Development Department in conjunction with the client departments and the works departments, such as the Highways Department and the Architectural Services Department. In the course of implementation of the Plan, the Kwun Tong District Council would also be consulted as appropriate.
- 12.3 Planning applications to the Board will be assessed on individual merits. In general, the Board, in considering the planning applications will take into account all relevant planning considerations which may include departmental outline development plans and guidelines published by the Board. The outline development plans are available for public inspection at the Planning Department. Guidelines published by the Board are available from the Board's website, the Secretariat of the Board and the Technical Services Division of the Planning Department. Application forms and Guidance Notes for planning applications can be downloaded from the Board's website and are available from the Secretariat of the Board and the Technical Services Division and relevant District Planning Office of the Planning Department. Applications should be supported by such materials as the Board thinks appropriate to enable it to consider the applications.