REDEVELOPMENT OF NO. 42 GRAMPIAN ROAD, KOWLOON, HONG KONG

NOISE IMPACT ASSESSMENT REPORT

27 October 2026

Report No.: RT25382-NIA-04r2

Prepared By:

BeeXergy Consulting Limited (BXG)
Phone: (852) 3568-4701
Address: Units 2501, 2503 & 2504, 25/F, AIA Financial Centre
712 Prince Edward Road East
Kowloon, Hong Kong
Email: info@beexergy.com

Project:	REDEVELOPMENT OF NO. 42 GRAMPIAN ROAD, KOWLOON, HONG KONG NOISE IMPACT ASSESSMENT REPORT
Report No.:	RT25382-NIA-04r2

Revision	Issue Date	Description	Author	Checker	Approver
01	21/11/2025	Issued for Comment	VS	LY	HM
02	10/03/2026	Issued for Comment	VS	LY	HM
03	10/07/2026	Issued for Comment	Various	HC	HM
04r2	27/10/2026	Issued for Comment	Various	HC	HM

Prepared By:

Various

Checked by

Harmony Chuh

Senior Engineer

Approved by:

Henry Mak

Director

Disclaimer:

- This report is prepared and submitted by BeeXergy Consulting Limited with all reasonable skill to the best of our knowledge, incorporating our Terms and Conditions and taking account of the resources devoted to it by agreement with the client.
- We disclaim any responsibility to the client and others in respect of any matters outside the project scope.
- This report is confidential to the client and we accept no responsibility of whatsoever nature to third parties to whom this report, or any part thereof, is made known. Any such party relies upon the report at their own risk.

TABLE OF CONTENT

1. INTRODUCTION 1
1.1. BACKGROUND 1
1.2. PROJECT LOCATION 1
1.3. PROJECT DESCRIPTION 1
1.4. STRUCTURE OF THE REPORT 2
2. ROAD TRAFFIC NOISE IMPACT ASSESSMENT 3
2.1. INTRODUCTION 3
2.2. ASSESSMENT CRITERIA 3
2.3. NOISE SENSITIVE RECEIVERS 3
2.4. ASSESSMENT METHODOLOGY 3
2.5. ASSESSMENT RESULTS – BASE CASE SCENARIO 4
2.6. CONCLUSION 4
3. FIXED NOISE IMPACT ASSESSMENT 5
3.1. RELEVANT LEGISLATION, STANDARDS AND GUIDELINES 5
3.2. IDENTIFICATION AND EVALUATION OF FIXED NOISE IMPACT 6
3.3. CONCLUSION 8
4. CONCLUSION 9

FIGURES

Figure 1.1	Location of Application Site
Figure 2.1a – 2.1c	Location of Noise Sensitive Receivers for Road Traffic Noise Assessment
Figure 3.1	Location of Major Fixed Noise Sources, Representative NSRs and NAPs for Fixed Noise Impact Assessment

APPENDICES

Appendix 1.1	Master Layout Plan
Appendix 2.1	Year 2045 Peak Hour Traffic Forecast
Appendix 2.2	Detailed Results of Road Traffic Noise Assessment
Appendix 3.1	Calculation for Fixed Noise Impact Assessment
Appendix 3.2	Reference Catalogue for Sound Power Level of AC Outdoor Unit adopted at The Grandeur

1. INTRODUCTION

1.1. BACKGROUND

1.1.1. The Project Proponent proposes to develop a 19-storey composite building comprising residential flats at 42 Grampian Road (hereafter called "the Proposed Development").

1.1.2. BeeXergy Consulting Limited was commissioned by the Project Proponent to undertake a Noise Impact Assessment (NIA) supporting its planning application under Section 16 of the Town Planning Ordinance (TPO) for the Proposed Development.

1.2. PROJECT LOCATION

1.2.1. The Application Site is located in Kowloon City district, with a site area of approximately 345.131m^2. It is currently bounded by bounded by Gar Fook Court to the north, J17 to the east, and Grampian Road Substation to the south. The Application Site is currently zoned as "Residential (Group B)" annotated "R(B)" under the Approved Ma Tau Kok (KPA 10) Outline Zoning Plan No. S/K10/30. **Figure 1.1** shows the location of Application Site and its environs.

1.3. PROJECT DESCRIPTION

1.3.1. The Proposed Development will convert the existing permitted uses to residential flats. The key development parameters are summarised in **Table 1.1** and the Master Layout Plan provided by the Project Architect is enclosed in **Appendix 1.1**.

Table 1.1 Key Development Parameters of the Proposed Development

No. of Storeys	19
Gross Floor Area (GFA)	Flat: 2,070.69m^2
Building Height	Not more than +80 mPD
Proposed Floor Use	B/F – 1/F: Lobby, Carpark, M/E Plant Room 2/F – 3/F: M/E Plant Room 4/F to 18/F: Flats
Tentative Population Intake Year	2030
Total No. of Flats	30

1.4. STRUCTURE OF THE REPORT

1.4.1. This NIA Report comprises the following sections:

- Section 1 introduces the project background;
- Section 2 presents the road traffic noise impact assessment;
- Section 3 presents the fixed noise impact assessment; and
- Section 4 summarizes the findings of this NIA.

2. ROAD TRAFFIC NOISE IMPACT ASSESSMENT

2.1. INTRODUCTION

2.1.1. The potential road traffic noise impact on the Proposed Development due to the nearby existing roads has been assessed. Practicable noise mitigation measures have been recommended, where necessary.

2.2. ASSESSMENT CRITERIA

2.2.1. Table 4.1 of Chapter 9 of the HKPSG provides the assessment criteria for road traffic noise impact at noise sensitive uses which rely on opened windows for ventilation. **Table 2.1** summarizes the adopted road traffic noise criteria for noise sensitive uses with openable windows at the Proposed Development.

Table 2.1 Road Traffic Noise Criteria for Noise Sensitive Uses

Location	Facility / Room	Noise Criteria, $L_{10\ (1\ hour)}$, dB(A)
4/F – 18/F	Flat (Bedroom, Living Room)	70
Notes: [1] The above standards apply to noise sensitive uses which rely on opened windows for ventilation and should be viewed as the maximum permissible noise levels assessed at 1m from the external façade.		

2.3. NOISE SENSITIVE RECEIVERS

2.3.1. Noise assessment points (NAPs) have been provided for noise sensitive uses with openable windows at the Proposed Development. The respective criteria for all types of noise sensitive uses with openable windows have been listed in **Table 2.1**. The locations of noise sensitive receivers (NSRs) for road traffic noise assessment are shown in **Figures 2.1a** to **2.1c**.

2.4. ASSESSMENT METHODOLOGY

2.4.1. The road traffic noise impact from the existing and planned road network has been assessed within 300m assessment area on the future NSRs within the Proposed Development. The road traffic noise model adopts the methodology outlined in the Calculation of Road Traffic Noise (CRTN) developed by the UK Department of Transport. The road traffic noise would be presented in terms of noise levels exceeded for 10% of the one-hour period for the hour having the peak traffic flow $L_{10(1hour)}$ under various traffic forecast scenarios. Representative NAPs, key building structures with noise screening effects, topographical contours and road segments with traffic flow data have been inputted into the model in predicting the potential traffic noise impacts.

2.4.2. Traffic flow of the existing roads within 300m assessment area have been forecasted

by the Project traffic consultant. As stated in CRTN, the traffic flow used for assessment shall be the maximum traffic projection within 15 years upon occupancy of the development. The assessment has been undertaken based on the projected PM peak hourly traffic flows in Year 2045, which corresponds to the maximum projected traffic conditions within 15 years upon occupancy of the Proposed Development, i.e. Year 2030. The traffic forecast data with endorsement by the Transport Department has been enclosed in **Appendix 2.1**.

2.5. ASSESSMENT RESULTS – BASE CASE SCENARIO

2.5.1. Predicted peak hourly road traffic noise levels at the representative NSRs at the Proposed Development are summarized in **Table 2.2** and

2.5.2. **Table** 2.3 below. Detailed breakdown of the road traffic noise assessment results under unmitigated case scenario are presented in **Appendix 2.2**.

Table 2.2 Summary of Predicted Road Traffic Noise Levels (Unmitigated Case Scenario)

Floor	Facility / Room	Noise Criteria, dB(A)	Predicted Maximum $L_{10\ (1\ hour)}$, dB(A)
4/F – 18/F	Flat (Bedroom, Living Room)	70	70

Table 2.3 Road Traffic Noise Levels Compliance Rate

Total No. of NAP	**90**
Total No. of NAP with Noise Exceedance	**0**
Compliance Rate	**100%**

2.5.3. The assessment results revealed that all the residential flats under the unmitigated case scenario comply with assessment criteria.

2.6. CONCLUSION

2.6.1. Operational road traffic noise impact on the planned noise sensitive uses within the Proposed Development has been assessed. The assessment results revealed that 100% compliance rate could be achieved and no adverse traffic noise impact on the Proposed Development is anticipated.

3. FIXED NOISE IMPACT ASSESSMENT

3.1. RELEVANT LEGISLATION, STANDARDS AND GUIDELINES

3.1.1. The relevant legislation, standards and guidelines applicable to the fixed noise impact assessment include:

- Noise Control Ordinance (NCO) (Cap. 400);
- Technical Memorandum for the Assessment of Noise from Places Other Than Domestic Premises, Public Places or Construction Sites (IND-TM);
- Hong Kong Planning Standards and Guidelines (HKPSG);
- Good Practices on Pumping System Noise Control; and
- Good Practices on Ventilation System Noise Control.

3.1.2. IND-TM stipulates the appropriate Acceptable Noise Level (ANL) for fixed noise sources. The ANL is dependent on the area sensitivity rating of a NSR, as defined in Table 1 of the IND-TM (reproduced in **Table 3.1**). The area sensitivity rating of a NSR is determined by the type of area where the NSR is located and the presence of any influencing factors (IFs) such as major roads and industrial areas.

Table 3.1 Area Sensitivity Ratings

Type of Area Containing NSR	Degree to which NSR is affected by IF		
	Not Affected	Indirectly Affected	Directly Affected
Rural area, including country parks or village type developments	A	B	B
Low density residential area consisting of low-rise or isolated high-rise developments	A	B	C
Urban area	B	C	C
Area other than those above	B	B	C

3.1.3. The HKPSG also states that in order to plan for a better environment, all planned fixed noise sources should be located and designed that when assessed in accordance with the IND-TM, the level of the intruding noise at the façade of the nearest existing sensitive use should be at least 5 dB(A) below the appropriate ANL shown in Table 2 of IND-TM or, in the case of the background being 5 dB(A) lower than the ANL, should not be higher than the background. The ANLs stipulated in the IND-TM are provided in **Table 3.2**.

Table 3.2 Acceptable Noise Levels

Time Period	Area Sensitivity Rating		
	A	B	C
Day (0700 to 1900 hours)	60	65	70
Evening (1900 to 2300 hours)			
Night (2300 to 0700 hours)	50	55	60

3.1.4. The Application Site is located in an area contains mainly low-rise residential buildings and schools in the surroundings. The type of area where the NSRs at the Proposed Development located is classified as "Low density residential area". No major roads and industrial areas are identified in the surroundings of the Application Site. As the Proposed Development will not be affected by IF, Area Sensitivity Rating of "A" has been assigned for the NSRs at the Proposed Development.

3.2. IDENTIFICATION AND EVALUATION OF FIXED NOISE IMPACT

Noise Sensitive Receivers

3.2.1. Existing NSRs and planned noise sensitive uses identified on the relevant Outline Zoning Plans and other relevant published land use plans, including development applications approved by the Town Planning Board have been identified. The first layer of representative NSRs within the 300m assessment area are listed in **Table 3.3** below and their locations are illustrated in **Figure 3.1.**

Table 3.3 Representative Noise Sensitive Receivers

NSR ID	Location	Nature of Use	Existing/ Planned	Separation Distance from the Project Site
NSR01	Residential Development to the North of the Application Site	Residential	Existing	<5m
NSR02	Residential Development to the East of the Application Site	Residential	Existing	<5m
NSR03	Residential Development to the South of the Application Site	Residential	Existing	~30m
NSR04	Residential Development to the West of the Application Site	Residential	Existing	~20m

Fixed Noise Impact on the Proposed Development

Identification of Fixed Noise Sources

3.2.2. A number of existing fixed noise sources have been identified within 300m assessment area through desktop study and site visit conducted on 17 November 2025. **Figure 3.1** indicates the locations of existing major fixed noise sources that may affect the Proposed Development. Information of the identified major fixed noise sources are

summarized in **Table 3.4**.

Table 3.4 Information of the Identified Fixed Noise Sources

Source ID	Location	Equipment	Approximate Shortest Horizontal Distance to the Project Site
S01	Kowloon City Plaza	Air-cooled Chiller	104m
S02a	Pooi To Middle School	Air-cooled Chiller	187m
S02b	Pooi To Middle School	AC Outdoor Unit	111m
S03	Munsang College	AC Outdoor Unit	161m
S04	Swatow Christian Church Kowloon City	Air-cooled Chiller	67m
S05	Iu Shan School	AC Outdoor Unit	104m
S06a	The Grandeur	AC Outdoor Unit	144m
S06b	The Grandeur	AC Outdoor Unit	164m

3.2.3. The Grampian Road Substation and Junction Road Substation are identified at the south of the Proposed Development. The substations are an enclosed structure and no noticeable noise from the substation was observed during site visit. As such, no adverse fixed noise impact from the substation is anticipated.

3.2.4. Detailed calculations of fixed noise assessment at NSRs are shown in **Appendix 3.1**, fixed noise assessment point with shortest distance to the noise sources is selected to demonstrate worst case scenario, all results complied with relevant noise standard, therefore, no adverse fixed noise impact to the Proposed Development is expected.

Fixed Noise Impact from the Proposed Development

Impact Identification and Evaluation

3.2.5. According to the latest development scheme, potential fixed noise sources within the Proposed Development include the E&M plant rooms at B/F to 3/F.

3.2.6. To ensure the fixed plant noise generated by the Proposed Development would not cause excessive impact to neighbouring noise sensitive uses, potential fixed noise sources within the Proposed Development shall be properly designed to meet the relevant noise criteria as stipulated in Chapter 9 of the HKPSG.

3.2.7. Provisions shall be made to control the fixed noise sources by suitable at source noise control measures such as silencers and acoustic linings when necessary. As such, it is anticipated that the fixed plant noise impact on the surrounding NSRs due to the operation of the Proposed Development will not exceed the relevant noise criteria under the HKPSG and NCO.

Recommended Mitigation Measures

3.2.8. The following noise mitigation measures are recommended to control noise emissions from planned fixed plant noise sources within the Proposed Development:

- All the noisy plants should be installed within plant room or with acoustic enclosure;
- Select quieter plant / equipment during procurement; and
- Provide suitable at-source noise control measures such as silencers and acoustic linings when necessary.

3.3. CONCLUSION

3.3.1. A number of existing fixed noise sources have been identified within 300m assessment area. Given all results of fixed noise assessment complied with relevant noise standard, no insurmountable fixed noise impact on the Proposed Development is anticipated.

3.3.2. To ensure the fixed plant noise generated by the Proposed Development would not cause excessive impact to neighbouring noise sensitive uses, fixed noise sources within the Proposed Development shall be properly designed to meet the relevant noise criteria as stipulated in Chapter 9 of the HKPSG. Provisions shall be made to control the fixed noise sources by suitable at source noise control measures such as silencers and acoustic linings when necessary. As such, it is anticipated that the fixed plant noise impact on the surrounding NSRs due to the operation of the Proposed Development will not exceed the relevant noise criteria under the HKPSG and NCO.

4. CONCLUSION


4.1.1. A 19-storey composite building comprising residential flats is proposed at 42 Grampian Road. This NIA Report addressed the potential road traffic noise and fixed noise impacts during the operation of the Proposed Development.

4.1.2. Road traffic noise impact on the planned noise sensitive uses within the Proposed Development has been assessed. From the assessment results, no adverse road traffic noise impact on the Proposed Development is anticipated.

4.1.3. Fixed noise impact on the Proposed Development has also been assessed. Based on the assessment, no insurmountable fixed noise impact on the Proposed Development is anticipated.

4.1.4. Fixed noise sources within the Proposed Development shall be properly designed to meet the relevant noise criteria as stipulated in Chapter 9 of the HKPSG. Suitable at source noise control measures such as silencers and acoustic linings shall be provided when necessary.

FIGURE 1.1
LOCATION OF APPLICATION SITE



Copyright by BeeXergy Consulting Limited

LEGEND:

Site Boundary

	Prepared	Checked	Approved
Initial	LY	LY	HM
Date	20251030	20251030	20251030

Project Title

Redevelopment of No. 42 Grampian Road, Kowloon, Hong Kong

DrawingTitle

Location of Application Site and its Environs

Drawing No.

FIGURE 1.1

Rev.

0

Scale:


A4 - 1:1400

BXG

BeeXergy Consulting Limited

FIGURE 2.1A – 2.1C
LOCATION OF NOISE SENSITIVE RECEIVERS FOR ROAD TRAFFIC NOISE ASSESSMENT

Copyright Reserved



LEGEND

Noise Assessment Point

	Prepared	Checked	Approved
Initial	Various	HC	HM
Date	20261023	20261023	20261023

Project Title

REDEVELOPMENT OF NO. 42 GRAMPIAN ROAD, KOWLOON, HONG KONG

NOISE IMPACT ASSESSMENT REPORT


Figure Title

Locations of Noise Assessment Points for Road Traffic Noise Impact Assessment (4/F)

Figure No.	**Rev.**
2.1a	1

BXG

Copyright Reserved



LEGEND

Noise Assessment Point

	Prepared	Checked	Approved
Initial	Various	HC	HM
Date	20261023	20261023	20261023

Project Title

REDEVELOPMENT OF NO. 42 GRAMPIAN ROAD, KOWLOON, HONG KONG

NOISE IMPACT ASSESSMENT REPORT


Figure Title

Locations of Noise Assessment Points for Road Traffic Noise Impact Assessment (5/F-13/F)

Figure No.	**Rev.**
2.1b	1

BXG

Copyright Reserved



LEGEND

- Noise Assessment Point
- Openable Window
- Fixed Window

	Prepared	Checked	Approved
Initial	Various	HC	HM
Date	20261023	20261023	20261023

Project Title

REDEVELOPMENT OF NO. 42 GRAMPIAN ROAD, KOWLOON, HONG KONG

NOISE IMPACT ASSESSMENT REPORT


Figure Title

Locations of Noise Assessment Points for Road Traffic Noise Impact Assessment (14/F-18/F)

Figure No.	**Rev.**
2.1c	1

FIGURE 3.1

LOCATION OF MAJOR FIXED NOISE SOURCES, REPRESENTATIVE NSRS AND NAPS FOR FIXED NOISE IMPACT ASSESSMENT



Copyright Reserved

LEGEND

- Site Boundary
- 300m Assessment Area
- Representative NSRs
- Fixed Noise Sources
- Representative NAPs

	Prepared	Checked	Approved
Initial	Various	HC	HM
Date	20261023	20261023	20261023

Project Title

REDEVELOPMENT OF NO. 42 GRAMPIAN ROAD, KOWLOON, HONG KONG

NOISE IMPACT ASSESSMENT REPORT


Figure Title

Locations of Major Fixed Noise Sources, Representative NSRs and NAPs for Fixed Noise Impact Assessment


Figure No.	**Rev.**
3.1	1

BXG


APPENDIX 1.1
MASTER LAYOUT PLAN




BASEMENT FLOOR PLAN (A4 1:100)




GROUND FLOOR PLAN (A4 1:100)



1ST FLOOR PLAN (A4 1:100)




2ND FLOOR PLAN (A4 1:100)




3RD FLOOR PLAN (A4 1:100)




4 FLOOR PLAN (A4 1:100)




5-18 FLOOR PLAN (A4 1:100)



ROOF FLOOR PLAN (A4 1:100)


B.L.
B.L.
80m.p.d RESTRICTION
80m.p.d RESTRICTION
LIFT MACHINE ROOM
1100
ROOF 78.175
4000
18/F 74.175
3150
17/F 71.025
3150
16/F 67.875
3150
15/F 64.725
3150
14/F 61.575
3150
13/F 58.425
3150
12/F 55.275
3150
11/F 52.125
3150
10/F 48.975
3150
9/F 45.825
3150
8/F 42.675
3150
7/F 39.525
3150
6/F 36.375
3150
5/F 33.225
3150
4/F 30.075
FLAT 1 MASTER BEDROOM
FLAT 2 LIVING ROOM & KITCHEN
FLAT 2 MASTER BEDROOM
FLAT ROOF 29.925
LANDSCAPED FACADE: GREEN WALL & PLANTERS
M/E PLANT ROOM
M/E PLANT ROOM
3000
3/F 27.075
M/E PLANT ROOM
CAR LIFT MACHINE ROOM
3000
2/F 24.075
CARPARK
3500
1/F 20.575
LANDSCAPE GARDEN AT STREET LEVEL (PRIVATE OPEN SPACE)
6m SETBACK
MEANS STREET LEVEL PAVEMENT 16.575
GRAMPIAN ROAD
CARPARK & LOBBY
CAR LIFT SHAFT
4000
G/F 16.575
CARPARK
3600
B/F 13.075
10.675
B.L.
No. 42 GRAMPIAN ROAD
B.L.
SECTION A-A (A3 1:100)



FRONT ELEVATION (A3 1:100)

APPENDIX 2.1
YEAR 2045 PEAK HOUR TRAFFIC FORECAST

By Fax
2528 6343

運輸署
Transport Department

本署檔案 Our Ref. : (00WCR) in 050-060-544-KR-G-005
來函檔號 Your Ref. : J7433/2
電 話 Tel. : 2399 2512
圖文傳真 Fax : 2397 8046
電 郵 Email :

12 May 2026

CKM Asia Limited
21st Floor, Methodist House
36 Hennessy Road, Wan Chai
Hong Kong
(Attn. Mr. Tommy LAW)

Dear Sir/Madam,

Section 16 Planning Application –
Proposed Minor Relaxation for "Residential" Use at 42 Grampian Road, Kowloon City (New Kowloon Inland Lot NO. 3536)

Traffic Forecast for Traffic Noise Impact Assessment


I refer to your captioned submission dated 16.4.2026.

I have no comment on the methodology of the traffic forecast from traffic engineering point of view provided that the traffic volume estimated in the forecast will only be used for conducting Noise Impact Assessment.

Yours faithfully,

(LI Hon-yeung, Simon)
for Commissioner for Transport

市區(九龍)及新界分區辦事處
Urban (Kln.) & NT Regional Office
九龍聯運街三十號旺角政府合署七樓及八樓
7th & 8th Floors, Mong Kok Government Offices, 30 Luen Wan Street, Kowloon.
圖文傳真 Fax No.: 2381 3799 (新界區) (NTRO) 2397 8046 (九龍市區) (U(K)RO)



Project Title	SECTION 16 PLANNING APPLICATION FOR THE COMPOSITE DEVELOPMENT AT 42 GRAMPIAN ROAD IN KOWLOON CITY, KOWLOON	J7433	Figure No. NIA1 / Revision A
Figure Title	LOCATION OF TRAFFIC DATA	Designed by L C H / Drawn by N C M / Checked by K C	Scale in A3 1 : 2500 / Date 14 NOV 2025

CKM Asia Limited
Traffic and Transportation Planning Consultants
21st Floor, Methodist House, 36 Hennessy Road
Wan Chai, Hong Kong
Tel : (852) 2520 5990 Fax : (852) 2528 6343
Email : mail@ckmasia.com.hk

T:\JOB\J7400-J7449\J7433\2025 11\Fig NIA1 RevA.dwg

TABLE 1 – PEAK HOUR TRAFFIC FLOW AND VEHICLE COMPOSITION

YEAR 2045 TRAFFIC FORECAST

Date: November 2025 **Job No.: J7433**

Link ID	Road Section	From Road	To Road	AM Peak Hour		
				Traffic Flows (veh/hr)	Vehicle Composition	
					LV	HV
L501	Grampian Road	Nga Tsin Wai Road	Dumbarton Road	300	86.9%	13.1%
L502	Grampian Road	Dumbarton Road	Nga Tsin Wai Road	100	78.4%	21.6%
L503	Grampian Road	Sau Chuk Yuen Road	Nga Tsin Wai Road	700	85.8%	14.2%
L504	Junction Road	Nga Tsin Wai Road	Carpenter Road	450	76.7%	23.3%
L505	Junction Road	Carpenter Road	Nga Tsin Wai Road	950	73.3%	26.7%
L506	Junction Road	Carpenter Road	Dumbarton Road	600	79.7%	20.3%
L507	Junction Road	Dumbarton Road	Carpenter Road	900	74.1%	25.9%
L508	Junction Road	Dumbarton Road	Tung Tau Tsuen Road	850	75.8%	24.2%
L509	Junction Road	Tung Tau Tsuen Road	Dumbarton Road	800	70.8%	29.2%
L510	Dumbarton Road	Grampian Road	Junction Road	550	83.4%	16.6%
L511	Dumbarton Road	Junction Road	Grampian Road	150	79.7%	20.3%
L512	Dumbarton Road	Inverness Road	Grampian Road	350	80.0%	20.0%
L513	Dumbarton Road	Grampian Road	Inverness Road	150	86.4%	13.6%
L514	Carpenter Road	Junction Road	Fuk Lo Tsun Road	300	82.8%	17.2%
L515	Carpenter Road	Fuk Lo Tsun Road	Junction Road	450	83.2%	16.8%
L516	Carpenter Road	Fuk Lo Tsun Road	Lion Rock Road	400	83.7%	16.3%
L517	Carpenter Road	Lion Rock Road	Fuk Lo Tsun Road	350	84.8%	15.2%
L518	Carpenter Road	Lion Rock Road	Hau Wong Road	250	84.6%	15.4%
L519	Carpenter Road	Hau Wong Road	Lion Rock Road	450	81.4%	18.6%
L520	Carpenter Road	Hau Wong Road	Nam Kok Road	500	80.8%	19.2%
L521	Carpenter Road	Nam Kok Road	Hau Wong Road	250	71.8%	28.2%
L522	Carpenter Road	Nga Tsin Long Road	Nam Kok Road	500	80.5%	19.5%
L523	Carpenter Road	Nam Kok Road	Nga Tsin Long Road	250	73.4%	26.6%
L524	Inverness Road	Nga Tsin Wai Road	Dumbarton Road	450	79.2%	20.8%
L525	Inverness Road	Dumbarton Road	Nga Tsin Wai Road	400	89.8%	10.2%
L526	Fuk Lo Tsun Road	Nga Tsin Wai Road	Carpenter Road	250	83.1%	16.9%
L527	Lion Rock Road	Carpenter Road	Nga Tsin Wai Road	300	80.4%	19.6%
L528	Hau Wong Road	Nga Tsin Wai Road	Carpenter Road	450	83.5%	16.5%
L529[(1)]	Nga Tsin Long Road	Carpenter Road	Nga Tsin Wai Road	-	-	-
L530	Nga Tsin Wai Road	Inverness Road	Grampian Road	400	80.0%	20.0%
L531	Nga Tsin Wai Road	Grampian Road	Inverness Road	700	79.0%	21.0%
L532	Nga Tsin Wai Road	Grampian Road	Junction Road	600	78.1%	21.9%
L533	Nga Tsin Wai Road	Junction Road	Grampian Road	400	81.0%	19.0%
L534	Nga Tsin Wai Road	Junction Road	Fuk Lo Tsun Road	750	79.4%	20.6%
L535	Nga Tsin Wai Road	Fuk Lo Tsun Road	Junction Road	350	76.7%	23.3%
L536	Nga Tsin Wai Road	Fuk Lo Tsun Road	Lion Rock Road	350	67.2%	32.8%
L537	Nga Tsin Wai Road	Lion Rock Road	Fuk Lo Tsun Road	450	76.8%	23.2%
L538	Nga Tsin Wai Road	Lion Rock Road	Hau Wong Road	400	68.2%	31.8%
L539	Nga Tsin Wai Road	Hau Wong Road	Lion Rock Road	450	73.9%	26.1%
L542	Tung Tau Tsuen Road	Junction Road	Tung Tsing Road	300	65.6%	34.4%
L543	Tung Tau Tsuen Road	Tung Tsing Road	Junction Road	300	61.0%	39.0%
L544	Junction Road	Tung Tau Tsuen Road	Inverness Road	700	76.7%	23.3%
L545	Junction Road	Inverness Road	Tung Tau Tsuen Road	700	72.5%	27.5%
L546	Nga Tsin Wai Road	College Road	Inverness Road	500	74.1%	25.9%
L547	Nga Tsin Wai Road	Inverness Road	College Road	700	80.8%	19.2%
L552	Junction Road	Prince Edward Road West	Nga Tsin Wai Road	650	82.1%	17.9%
L553	Junction Road	Nga Tsin Wai Road	Prince Edward Road West	950	73.7%	26.3%
L554	Fuk Lo Tsun Road	Nga Tsin Wai Road	Prince Edward Road West	300	92.4%	7.6%
L555	Lion Rock Road	Nga Tsin Wai Road	Prince Edward Road West	250	74.7%	25.3%
L560	Inverness Road	Dumbarton Road	Junction Road	300	84.0%	16.0%
L561	Inverness Road	Junction Road	Dumbarton Road	450	87.0%	13.0%

Note: "LV" includes motorcycle, private car and taxi

"HV" includes light / medium / heavy goods vehicle, public / private light bus, non-franchised bus and franchised bus

(1) The portion of Nga Tsin Long Road to be pedestrianised with reference to Urban Renewal Authority's Nga Tsin Wai Road / Carpenter Road Development Scheme (KC-017)

TABLE 1 – PEAK HOUR TRAFFIC FLOW AND VEHICLE COMPOSITION

YEAR 2045 TRAFFIC FORECAST

Date: November 2025 **Job No.: J7433**

Link ID	Road Section	From Road	To Road	PM Peak Hour		
				Traffic Flows (veh/hr)	Vehicle Composition	
					LV	HV
L501	Grampian Road	Nga Tsin Wai Road	Dumbarton Road	300	78.9%	21.1%
L502	Grampian Road	Dumbarton Road	Nga Tsin Wai Road	100	80.0%	20.0%
L503	Grampian Road	Sau Chuk Yuen Road	Nga Tsin Wai Road	550	82.4%	17.6%
L504	Junction Road	Nga Tsin Wai Road	Carpenter Road	550	74.6%	25.4%
L505	Junction Road	Carpenter Road	Nga Tsin Wai Road	800	77.0%	23.0%
L506	Junction Road	Carpenter Road	Dumbarton Road	550	75.8%	24.2%
L507	Junction Road	Dumbarton Road	Carpenter Road	650	74.5%	25.5%
L508	Junction Road	Dumbarton Road	Tung Tau Tsuen Road	700	72.5%	27.5%
L509	Junction Road	Tung Tau Tsuen Road	Dumbarton Road	650	71.4%	28.6%
L510	Dumbarton Road	Grampian Road	Junction Road	250	80.2%	19.8%
L511	Dumbarton Road	Junction Road	Grampian Road	100	79.1%	20.9%
L512	Dumbarton Road	Inverness Road	Grampian Road	100	87.0%	13.0%
L513	Dumbarton Road	Grampian Road	Inverness Road	150	83.3%	16.7%
L514	Carpenter Road	Junction Road	Fuk Lo Tsun Road	300	82.7%	17.3%
L515	Carpenter Road	Fuk Lo Tsun Road	Junction Road	450	85.6%	14.4%
L516	Carpenter Road	Fuk Lo Tsun Road	Lion Rock Road	400	84.5%	15.5%
L517	Carpenter Road	Lion Rock Road	Fuk Lo Tsun Road	350	82.0%	18.0%
L518	Carpenter Road	Lion Rock Road	Hau Wong Road	200	80.6%	19.4%
L519	Carpenter Road	Hau Wong Road	Lion Rock Road	500	82.0%	18.0%
L520	Carpenter Road	Hau Wong Road	Nam Kok Road	350	82.8%	17.2%
L521	Carpenter Road	Nam Kok Road	Hau Wong Road	300	74.9%	25.1%
L522	Carpenter Road	Nga Tsin Long Road	Nam Kok Road	300	82.6%	17.4%
L523	Carpenter Road	Nam Kok Road	Nga Tsin Long Road	300	74.4%	25.6%
L524	Inverness Road	Nga Tsin Wai Road	Dumbarton Road	200	73.1%	26.9%
L525	Inverness Road	Dumbarton Road	Nga Tsin Wai Road	250	87.3%	12.7%
L526	Fuk Lo Tsun Road	Nga Tsin Wai Road	Carpenter Road	200	93.4%	6.6%
L527	Lion Rock Road	Carpenter Road	Nga Tsin Wai Road	400	85.3%	14.7%
L528	Hau Wong Road	Nga Tsin Wai Road	Carpenter Road	400	89.0%	11.0%
L529[(1)]	Nga Tsin Long Road	Carpenter Road	Nga Tsin Wai Road	-	-	-
L530	Nga Tsin Wai Road	Inverness Road	Grampian Road	300	83.0%	17.0%
L531	Nga Tsin Wai Road	Grampian Road	Inverness Road	600	82.8%	17.2%
L532	Nga Tsin Wai Road	Grampian Road	Junction Road	500	80.6%	19.4%
L533	Nga Tsin Wai Road	Junction Road	Grampian Road	450	85.8%	14.2%
L534	Nga Tsin Wai Road	Junction Road	Fuk Lo Tsun Road	600	83.0%	17.0%
L535	Nga Tsin Wai Road	Fuk Lo Tsun Road	Junction Road	450	85.5%	14.5%
L536	Nga Tsin Wai Road	Fuk Lo Tsun Road	Lion Rock Road	300	73.1%	26.9%
L537	Nga Tsin Wai Road	Lion Rock Road	Fuk Lo Tsun Road	600	83.8%	16.2%
L538	Nga Tsin Wai Road	Lion Rock Road	Hau Wong Road	400	73.5%	26.5%
L539	Nga Tsin Wai Road	Hau Wong Road	Lion Rock Road	600	82.5%	17.5%
L542	Tung Tau Tsuen Road	Junction Road	Tung Tsing Road	250	64.8%	35.2%
L543	Tung Tau Tsuen Road	Tung Tsing Road	Junction Road	300	66.3%	33.7%
L544	Junction Road	Tung Tau Tsuen Road	Inverness Road	650	74.2%	25.8%
L545	Junction Road	Inverness Road	Tung Tau Tsuen Road	550	72.8%	27.2%
L546	Nga Tsin Wai Road	College Road	Inverness Road	400	78.3%	21.7%
L547	Nga Tsin Wai Road	Inverness Road	College Road	750	84.3%	15.7%
L552	Junction Road	Prince Edward Road West	Nga Tsin Wai Road	700	77.3%	22.7%
L553	Junction Road	Nga Tsin Wai Road	Prince Edward Road West	850	76.8%	23.2%
L554	Fuk Lo Tsun Road	Nga Tsin Wai Road	Prince Edward Road West	300	83.2%	16.8%
L555	Lion Rock Road	Nga Tsin Wai Road	Prince Edward Road West	300	83.9%	16.1%
L560	Inverness Road	Dumbarton Road	Junction Road	200	74.8%	25.2%
L561	Inverness Road	Junction Road	Dumbarton Road	200	86.8%	13.2%

Note: "LV" includes motorcycle, private car and taxi

"HV" includes light / medium / heavy goods vehicle, public / private light bus, non-franchised bus and franchised bus

(1) The portion of Nga Tsin Long Road to be pedestrianised with reference to Urban Renewal Authority's Nga Tsin Wai Road / Carpenter Road Development Scheme (KC-017)

APPENDIX 2.2
DETAILED RESULTS OF ROAD TRAFFIC NOISE ASSESSMENT

Predicted Road Traffic Noise Levels for 2045 (Base Case Scenario)

Floor	NAP ID		Description	Floor Height, mPD	Assessment Height, mPD	Noise Criteria, dB(A)	Unmitigated Noise Level, $L_{10\ (1\ hour)}$, dB(A)	Compliance
							AM	
4/F	4F_N01	4F_N01-4F-4/F	Flat - Bedroom	+30.1	+31.3	70	62	Yes
	4F_N02	4F_N02-4F-4/F	Flat - Living Room			70	62	Yes
	4F_N03	4F_N03-4F-4/F	Flat - Bedroom			70	62	Yes
	4F_N04	4F_N04-4F-4/F	Flat - Bedroom			70	61	Yes
	4F_N05	4F_N05-4F-4/F	Flat - Living Room			70	60	Yes
	4F_N06	4F_N06-4F-4/F	Flat - Bedroom			70	62	Yes
5/F	5F_N01	5F-13F_N01-5F-13F-5/F	Flat - Bedroom	+33.2	+34.4	70	67	Yes
	5F_N02	5F-13F_N02-5F-13F-5/F	Flat - Living Room			70	67	Yes
	5F_N03	5F-13F_N03-5F-13F-5/F	Flat - Bedroom			70	67	Yes
	5F_N04	5F-13F_N04-5F-13F-5/F	Flat - Bedroom			70	66	Yes
	5F_N05	5F-13F_N05-5F-13F-5/F	Flat - Living Room			70	65	Yes
	5F_N06	5F-13F_N06-5F-13F-5/F	Flat - Bedroom			70	67	Yes
6/F	6F_N01	5F-13F_N01-5F-13F-6/F	Flat - Bedroom	+36.4	+37.6	70	68	Yes
	6F_N02	5F-13F_N02-5F-13F-6/F	Flat - Living Room			70	68	Yes
	6F_N03	5F-13F_N03-5F-13F-6/F	Flat - Bedroom			70	68	Yes
	6F_N04	5F-13F_N04-5F-13F-6/F	Flat - Bedroom			70	68	Yes
	6F_N05	5F-13F_N05-5F-13F-6/F	Flat - Living Room			70	67	Yes
	6F_N06	5F-13F_N06-5F-13F-6/F	Flat - Bedroom			70	68	Yes
7/F	7F_N01	5F-13F_N01-5F-13F-7/F	Flat - Bedroom	+39.5	+40.7	70	69	Yes
	7F_N02	5F-13F_N02-5F-13F-7/F	Flat - Living Room			70	69	Yes
	7F_N03	5F-13F_N03-5F-13F-7/F	Flat - Bedroom			70	69	Yes
	7F_N04	5F-13F_N04-5F-13F-7/F	Flat - Bedroom			70	69	Yes
	7F_N05	5F-13F_N05-5F-13F-7/F	Flat - Living Room			70	68	Yes
	7F_N06	5F-13F_N06-5F-13F-7/F	Flat - Bedroom			70	68	Yes
8/F	8F_N01	5F-13F_N01-5F-13F-8/F	Flat - Bedroom	+42.7	+43.9	70	69	Yes
	8F_N02	5F-13F_N02-5F-13F-8/F	Flat - Living Room			70	69	Yes
	8F_N03	5F-13F_N03-5F-13F-8/F	Flat - Bedroom			70	69	Yes
	8F_N04	5F-13F_N04-5F-13F-8/F	Flat - Bedroom			70	69	Yes
	8F_N05	5F-13F_N05-5F-13F-8/F	Flat - Living Room			70	69	Yes
	8F_N06	5F-13F_N06-5F-13F-8/F	Flat - Bedroom			70	69	Yes
9/F	9F_N01	5F-13F_N01-5F-13F-9/F	Flat - Bedroom	+45.8	+47.0	70	69	Yes
	9F_N02	5F-13F_N02-5F-13F-9/F	Flat - Living Room			70	69	Yes
	9F_N03	5F-13F_N03-5F-13F-9/F	Flat - Bedroom			70	69	Yes
	9F_N04	5F-13F_N04-5F-13F-9/F	Flat - Bedroom			70	69	Yes
	9F_N05	5F-13F_N05-5F-13F-9/F	Flat - Living Room			70	69	Yes
	9F_N06	5F-13F_N06-5F-13F-9/F	Flat - Bedroom			70	69	Yes
10/F	10F_N01	5F-13F_N01-5F-13F-10/F	Flat - Bedroom	+49.0	+50.2	70	69	Yes
	10F_N02	5F-13F_N02-5F-13F-10/F	Flat - Living Room			70	69	Yes
	10F_N03	5F-13F_N03-5F-13F-10/F	Flat - Bedroom			70	69	Yes
	10F_N04	5F-13F_N04-5F-13F-10/F	Flat - Bedroom			70	69	Yes
	10F_N05	5F-13F_N05-5F-13F-10/F	Flat - Living Room			70	70	Yes
	10F_N06	5F-13F_N06-5F-13F-10/F	Flat - Bedroom			70	70	Yes
11/F	11F_N01	5F-13F_N01-5F-13F-11/F	Flat - Bedroom	+52.1	+53.3	70	69	Yes
	11F_N02	5F-13F_N02-5F-13F-11/F	Flat - Living Room			70	69	Yes
	11F_N03	5F-13F_N03-5F-13F-11/F	Flat - Bedroom			70	70	Yes
	11F_N04	5F-13F_N04-5F-13F-11/F	Flat - Bedroom			70	70	Yes
	11F_N05	5F-13F_N05-5F-13F-11/F	Flat - Living Room			70	70	Yes
	11F_N06	5F-13F_N06-5F-13F-11/F	Flat - Bedroom			70	70	Yes
12/F	12F_N01	5F-13F_N01-5F-13F-12/F	Flat - Bedroom	+55.3	+56.5	70	69	Yes
	12F_N02	5F-13F_N02-5F-13F-12/F	Flat - Living Room			70	68	Yes
	12F_N03	5F-13F_N03-5F-13F-12/F	Flat - Bedroom			70	70	Yes
	12F_N04	5F-13F_N04-5F-13F-12/F	Flat - Bedroom			70	70	Yes
	12F_N05	5F-13F_N05-5F-13F-12/F	Flat - Living Room			70	70	Yes
	12F_N06	5F-13F_N06-5F-13F-12/F	Flat - Bedroom			70	70	Yes
13/F	13F_N01	5F-13F_N01-5F-13F-13/F	Flat - Bedroom	+58.4	+59.6	70	69	Yes
	13F_N02	5F-13F_N02-5F-13F-13/F	Flat - Living Room			70	68	Yes
	13F_N03	5F-13F_N03-5F-13F-13/F	Flat - Bedroom			70	69	Yes
	13F_N04	5F-13F_N04-5F-13F-13/F	Flat - Bedroom			70	69	Yes
	13F_N05	5F-13F_N05-5F-13F-13/F	Flat - Living Room			70	70	Yes
	13F_N06	5F-13F_N06-5F-13F-13/F	Flat - Bedroom			70	70	Yes
14/F	14F_N01	14F-18F_N01-14F-18F-14/F	Flat - Bedroom	+61.6	+62.8	70	69	Yes
	14F_N02	14F-18F_N02-14F-18F-14/F	Flat - Living Room			70	68	Yes
	14F_N03	14F-18F_N03-14F-18F-14/F	Flat - Bedroom			70	69	Yes
	14F_N04	14F-18F_N04-14F-18F-14/F	Flat - Bedroom			70	69	Yes
	14F_N05	14F-18F_N05-14F-18F-14/F	Flat - Living Room			70	70	Yes
	14F_N06	14F-18F_N06-14F-18F-14/F	Flat - Bedroom			70	70	Yes

Predicted Road Traffic Noise Levels for 2045 (Base Case Scenario)

Floor	NAP ID		Description	Floor Height, mPD	Assessment Height, mPD	Noise Criteria, dB(A)	Unmitigated Noise Level, $L_{10\ (1\ hour)}$, dB(A)	Compliance
							AM	
15/F	15F_N01	14F-18F_N01-14F-18F-15/F	Flat - Bedroom	+64.7	+65.9	70	69	Yes
	15F_N02	14F-18F_N02-14F-18F-15/F	Flat - Living Room			70	68	Yes
	15F_N03	14F-18F_N03-14F-18F-15/F	Flat - Bedroom			70	69	Yes
	15F_N04	14F-18F_N04-14F-18F-15/F	Flat - Bedroom			70	69	Yes
	15F_N05	14F-18F_N05-14F-18F-15/F	Flat - Living Room			70	70	Yes
	15F_N06	14F-18F_N06-14F-18F-15/F	Flat - Bedroom			70	70	Yes
16/F	16F_N01	14F-18F_N01-14F-18F-16/F	Flat - Bedroom	+67.9	+69.1	70	69	Yes
	16F_N02	14F-18F_N02-14F-18F-16/F	Flat - Living Room			70	68	Yes
	16F_N03	14F-18F_N03-14F-18F-16/F	Flat - Bedroom			70	69	Yes
	16F_N04	14F-18F_N04-14F-18F-16/F	Flat - Bedroom			70	69	Yes
	16F_N05	14F-18F_N05-14F-18F-16/F	Flat - Living Room			70	70	Yes
	16F_N06	14F-18F_N06-14F-18F-16/F	Flat - Bedroom			70	70	Yes
17/F	17F_N01	14F-18F_N01-14F-18F-17/F	Flat - Bedroom	+71.0	+72.2	70	69	Yes
	17F_N02	14F-18F_N02-14F-18F-17/F	Flat - Living Room			70	68	Yes
	17F_N03	14F-18F_N03-14F-18F-17/F	Flat - Bedroom			70	69	Yes
	17F_N04	14F-18F_N04-14F-18F-17/F	Flat - Bedroom			70	69	Yes
	17F_N05	14F-18F_N05-14F-18F-17/F	Flat - Living Room			70	70	Yes
	17F_N06	14F-18F_N06-14F-18F-17/F	Flat - Bedroom			70	70	Yes
18/f	18F_N01	14F-18F_N01-14F-18F-18/F	Flat - Bedroom	+74.2	+75.4	70	69	Yes
	18F_N02	14F-18F_N02-14F-18F-18/F	Flat - Living Room			70	68	Yes
	18F_N03	14F-18F_N03-14F-18F-18/F	Flat - Bedroom			70	69	Yes
	18F_N04	14F-18F_N04-14F-18F-18/F	Flat - Bedroom			70	69	Yes
	18F_N05	14F-18F_N05-14F-18F-18/F	Flat - Living Room			70	70	Yes
	18F_N06	14F-18F_N06-14F-18F-18/F	Flat - Bedroom			70	70	Yes

Results Summary	
Total No. of NAPs	90
Total No. of NAPs with exceedance	0
Compliance Rate	100%

APPENDIX 3.1
CALCULATION FOR FIXED NOISE IMPACT ASSESSMENT

Title: Inventory of Major Fixed Noise Sources

Source Location	Source Description	Source ID	x-coordinate	y-coordinate	No. of Plant	SWL adopted in Fixed Noise Assessment, dB(A)	Remarks
Kowloon City Plaza	Air-cooled Chiller	S01	837398.4	821337.8	2	68.0	SWL reference to Planning Application No. A/K10/276 with similar equipemnt and project location
Pooi To Middle School	Air-cooled Chiller	S02a	837177.6	821196.8	2	83.0	
	AC Outdoor Unit	S02b	837188.2	821296	8	68.0	
Munsang College	AC Outdoor Unit	S03	837250.7	821515.9	19	68.0	
Swatow Christian Church Kowloon City	Air-cooled Chiller	S04	837225.3	821318.8	6	68.0	
Iu Shan School	AC Outdoor Unit	S05	837295.4	821241.5	4	68.0	
The Grandeur	AC Outdoor Unit	S06a	837234.5	821206.3	7	75.0	SWL reference to calatague of similar equipment attached in **Appendix 3.2**.
	AC Outdoor Unit	S06b	837233.3	821186.1	7	75.0	

Project:	Proposed Residential Care Home for the Elderly (RCHE) in Nam Sang Wai, Yuen Long
Title:	Assessment for Noise from Fixed Sources
Subtitle:	Calculation of SPL at Assessment Points
NSR ID:	5F-13F_N01
NSR x coord:	837285.9
NSR y coord:	821357.9
ASR	A

Noise Source ID	Description	Activities/Equipment	Operation		SWL, dB(A)		Horizontal Distance from NSR, m	Correction, dB(A)				Day-time Corrected Noise Level, Leq dB(A)	Night-time Corrected Noise Level, Leq dB(A)	Remark
			Daytime	Night-time	Daytime	Night-time		No. of Plant	Distance	Barrier	Façade			
S01	Kowloon City Plaza	Air-cooled Chiller	Y	Y	68.0	68.0	114	3	-49	0	3	25	25	Ngiht time operation is assumed as worst case scenario
S02a	Pooi To Middle School	Air-cooled Chiller	Y	Y	83.0	83.0	194	3	-54	0	3	35	35	
S02b		AC Outdoor Unit	Y	Y	68.0	68.0	116	9	-49	0	3	31	31	
S03	Munsang College	AC Outdoor Unit	Y	Y	68.0	68.0	162	13	-52	0	3	32	32	
S04	Swatow Christian Church Kowloon City	Air-cooled Chiller	Y	Y	68.0	68.0	72	8	-45	0	3	34	34	
S05	Iu Shan School	AC Outdoor Unit	Y	Y	68.0	68.0	117	6	-49	0	3	28	28	
S06a	The Grandeur	AC Outdoor Unit	Y	Y	75.0	75.0	160	8	-52	0	3	34	34	
S06b		AC Outdoor Unit	Y	Y	75.0	75.0	180	8	-53	0	3	33	33	
										Total SPL		42	42	
										Criteria ANL		60	50	
										Exceedance		-	-	

Project:	Proposed Residential Care Home for the Elderly (RCHE) in Nam Sang Wai, Yuen Long
Title:	Assessment for Noise from Fixed Sources
Subtitle:	Calculation of SPL at Assessment Points
NSR ID:	5F-13F_N03
NSR x coord:	837285.6
NSR y coord:	821350.3
ASR	A

Noise Source ID	Description	Activities/Equipment	Operation		SWL, dB(A)		Horizontal Distance from NSR, m	Correction, dB(A)				Day-time Corrected Noise Level, Leq dB(A)	Night-time Corrected Noise Level, Leq dB(A)	Remark
			Daytime	Night-time	Daytime	Night-time		No. of Plant	Distance	Barrier	Façade			
S01	Kowloon City Plaza	Air-cooled Chiller	Y	Y	68.0	68.0	113	3	-49	0	3	25	25	Ngiht time operation is assumed as worst case scenario
S02a	Pooi To Middle School	Air-cooled Chiller	Y	Y	83.0	83.0	188	3	-53	0	3	36	36	
S02b		AC Outdoor Unit	Y	Y	68.0	68.0	112	9	-49	0	3	31	31	
S03	Munsang College	AC Outdoor Unit	Y	Y	68.0	68.0	169	13	-53	0	3	31	31	
S04	Swatow Christian Church Kowloon City	Air-cooled Chiller	Y	Y	68.0	68.0	68	8	-45	0	3	34	34	
S05	Iu Shan School	AC Outdoor Unit	Y	Y	68.0	68.0	109	6	-49	0	3	28	28	
S06a	The Grandeur	AC Outdoor Unit	Y	Y	75.0	75.0	153	8	-52	0	3	35	35	
S06b		AC Outdoor Unit	Y	Y	75.0	75.0	172	8	-53	0	3	34	34	
										Total SPL		42	42	
										Criteria ANL		60	50	
										Exceedance		-	-	

Project:	Proposed Residential Care Home for the Elderly (RCHE) in Nam Sang Wai, Yuen Long
Title:	Assessment for Noise from Fixed Sources
Subtitle:	Calculation of SPL at Assessment Points
NSR ID:	5F-13F_N06
NSR x coord:	837295.1
NSR y coord:	821345.5
ASR	A


Noise Source ID	Description	Activities/Equipment	Operation		SWL, dB(A)		Horizontal Distance from NSR, m	Correction, dB(A)				Day-time Corrected Noise Level, Leq dB(A)	Night-time Corrected Noise Level, Leq dB(A)	Remark
			Daytime	Night-time	Daytime	Night-time		No. of Plant	Distance	Barrier	Façade			
S01	Kowloon City Plaza	Air-cooled Chiller	Y	Y	68.0	68.0	104	3	-48	0	3	26	26	Ngiht time operation is assumed as worst case scenario
S02a	Pooi To Middle School	Air-cooled Chiller	Y	Y	83.0	83.0	190	3	-54	0	3	35	35	
S02b		AC Outdoor Unit	Y	Y	68.0	68.0	118	9	-49	0	3	31	31	
S03	Munsang College	AC Outdoor Unit	Y	Y	68.0	68.0	176	13	-53	0	3	31	31	
S04	Swatow Christian Church Kowloon City	Air-cooled Chiller	Y	Y	68.0	68.0	75	8	-45	0	3	33	33	
S05	Iu Shan School	AC Outdoor Unit	Y	Y	68.0	68.0	104	6	-48	0	3	29	29	
S06a	The Grandeur	AC Outdoor Unit	Y	Y	75.0	75.0	152	8	-52	0	3	35	35	
S06b		AC Outdoor Unit	Y	Y	75.0	75.0	171	8	-53	0	3	34	34	
										Total SPL		42	42	
										Criteria ANL		60	50	
										Exceedance		-	-	

APPENDIX 3.2

REFERENCE CATALOGUE FOR SOUND POWER LEVEL ADOPTED OF AC OUTDOOR UNITS AT THE GRANDEUR

Single unit

Model : MMY-MAP1446FT6P-UL, MAP1686FT6P-UL, MAP1446FT9P-UL, MAP1686FT9P-UL



	a	b	c	d	e	g	h
≥	19.7"(500)	23.6"(600)	70.1"(1780)	63.8"(1620)	0.4"(10)	39.4"(1000)	31.5"(800)

No	Parts name	Remarks
①	Liquid pipe connection port	ϕA
②	Discharge gas pipe connection port	ϕB
③	Suction gas pipe connection port	ϕ1-1/8"(28.6)
④	Balance pipe connection port	ϕ3/8"(9.5)
⑤	Knockout hole for power wiring 1	ϕ0.9"(22.2)
⑥	Knockout hole for power wiring 2	ϕ1.7"(43.7)
⑦	Knockout hole for power wiring 2	ϕ1.9"(48)
⑧	Knockout hole for control wiring	ϕ1.1"(27)
⑨	Square hole (for freight handling)	4-2.4"×7.9"(4-60×200)
⑩	Square hole (for hanging)	4-1.6"×2.2"(4-40×55)

Model Name	A	B
MAP 1446 type	5/8"(15.9)	7/8"(22.2)
MAP 1686 type	3/4"(19.1)	7/8"(22.2)

System with Ducted indoor units

Model name				MMY-MAP1446FT6P-UL	MMY-MAP1686FT6P-UL
Power Supply	Nominal voltage		V/Ph/Hz	460 / 3 / 60	460 / 3 / 60
	Voltage range		V	414Minimum / 506 Maximum	414Minimum / 506 Maximum
Cooling	Nominal capacity (*1)		Btu/h	144000	168000
	Rated capacity (*1)		Btu/h	138000	160000
	Rated power consumption (*1)(*2)		kW	11.29	14.48
	Rated EER (*1)(*2)		(Btu/h)/W	12.2	11.1
Heating	Nominal capacity (*1)		Btu/h	162000	189000
	Rated capacity (*1)		Btu/h	154000	180000
	Rated power consumption (*1)(*2)		kW	12.02	15.38
	Rated COP (*1)(*2)		W/W	3.75	3.43
Dimension	Unit	Height	In	72.9	72.9
		Width	In	63.0	63.0
		Depth	In	30.7	30.7
	Packing	Height	In	76.3	76.3
		Width	In	65.8	65.8
		Depth	In	32.6	32.6
Weight	Unit		lbs	875.0	875.0
	Packing		lbs	917	917
Color				Silky shade (Munsell 1Y8.5/0.5)	Silky shade (Munsell 1Y8.5/0.5)
Compressor	Type			Hermetic twin rotary compressor	Hermetic twin rotary compressor
	Motor output		kW	5.4 x 2	6.5 x 2
Fan unit	Type			Propeller fan	Propeller fan
	Motor output		kW	1.0+1.0	1.0+1.0
	Air volume		cfm	10850	10850
Maximum external static pressure (*3)			In.WG	0.16	0.16
Heat exchanger				Finned tube	Finned tube
Refrigerant	Name			R410A	R410A
	Charged refrigerant amount (*4)		lbs	24.3	24.3
High-pressure switch			psi	OFF:420 ON:540	OFF:420 ON:540
Protective devices				(*5)	(*5)
Power supply wiring		MCA	A	23.4	29.7
		MOCP (*6)	A	30.0	35.0
Piping connections	Liquid	Type		Flare	Flare
		Diameter	In	5/8"	3/4"
	Suction Gas	Type		Brazing	Brazing
		Diameter	In	1-1/8"	1-1/8"
	Discharge Gas	Type		Flare	Flare
		Diameter	In	7/8"	7/8"
	Balance	Type		Flare	Flare
		Diameter	In	3/8"	3/8"
Indoor units	Maximum capacity of combined indoor units			50 to 150%(*7)	50 to 150%(*7)
	Maximum number of indoor units(*8)			25	30
Sound pressure level		Cooling	dB(A)	66.5	66.5
		Heating	dB(A)	66.5	67.0
Operation temperature range		Cooling	°FDB	14 to 122	14 to 122
		Heating	°FWB	-13 to 60	-13 to 60

Note

(*1) Rated conditions — Cooling : Indoor air temperature 80 F Dry Bulb / 67 F Wet Bulb , Outdoor air tempreture 95 F Dry Bulb.
Heating : Indoor air temperature 70 F Dry Bulb, Outdoor air tempreture 47 F Dry Bulb / 43 F Wet Bulb.
Equivalent piping length: 50 ft, Height difference: 0 ft

(*2) Value for only outdoor unit

(*3) Setting is necessary

(*4) The amount dose not consider extra piping length. Refrigerant must be added on site in accordance with the actual piping length.

(*5) Discharge temp. sensor / Suction temp. sensor / High-pressure sensor / Low-pressure sensor / PC board fuse

(*6) MOCP : Maximum Overcurrent Protection(Amps)

(*7) Permanent operation below 80% is not recommended.

(*8) It is 54 units in case central control is in system.

Assume SPL = 67 dB(A)@1m
SWL = 67 + 20*log(1) + 8 = 75 dB(A)

System with Non-ducted indoor units

Model name				MMY-MAP1446FT9P-UL	MMY-MAP1686FT9P-UL
Power Supply	Nominal voltage		V/Ph/Hz	208-230 / 3 / 60	208-230 / 3 / 60
	Voltage range		V	187Minimum / 253 Maximum	187Minimum / 253 Maximum
Cooling	Nominal capacity (*1)		Btu/h	144,000	168,000
	Rated capacity (*1)		Btu/h	138,000	160,000
	Rated power consumption (*1)(*2)		kW	11.03	14.55
	Rated EER (*1)(*2)		(Btu/h)/W	12.5	11.0
Heating	Nominal capacity (*1)		Btu/h	162,000	189,000
	Rated capacity (*1)		Btu/h	154,000	180,000
	Rated power consumption (*1)(*2)		kW	11.76	15.05
	Rated COP (*1)(*2)		W/W	3.84	3.51
Dimension	Unit	Height	In	72.9	72.9
		Width	In	63.0	63.0
		Depth	In	30.7	30.7
	Packing	Height	In	76.3	76.3
		Width	In	65.8	65.8
		Depth	In	32.6	32.6
Weight	Unit		lbs	882	882
	Packing		lbs	924	924
Color				Silky shade (Munsell 1Y8.5/0.5)	Silky shade (Munsell 1Y8.5/0.5)
Compressor	Type			Hermetic twin rotary compressor	Hermetic twin rotary compressor
	Motor output		kW	5.4 x 2	6.5 x 2
Fan unit	Type			Propeller fan	Propeller fan
	Motor output		kW	1.0+1.0	1.0+1.0
	Air volume		cfm	10850	10850
Maximum external static pressure (*3)			In.WG	0.16	0.16
Heat exchanger				Finned tube	Finned tube
Refrigerant	Name			R410A	R410A
	Charged refrigerant amount (*4)		lbs	24.3	24.3
High-pressure switch			psi	OFF:420 ON:540	OFF:420 ON:540
Protective devices				(*5)	(*5)
Power supply wiring		MCA	A	52.1	66.2
		MOCP (*6)	A	60.0	70.0
Piping connections	Liquid	Type		Flare	Flare
		Diameter	In	5/8"	3/4"
	Suction Gas	Type		Brazing	Brazing
		Diameter	In	1-1/8"	1-1/8"
	Discharge Gas	Type		Flare	Flare
		Diameter	In	7/8"	7/8"
	Balance	Type		Flare	Flare
		Diameter	In	3/8"	3/8"
Indoor units	Maximum capacity of combined indoor units			50 to 150%(*7)	50 to 150%(*7)
	Maximum number of indoor units(*8)			25	30
Sound pressure level		Cooling	dB(A)	66.5	66.5
		Heating	dB(A)	66.5	67.0
Operation temperature range		Cooling	°FDB	14 to 122	14 to 122
		Heating	°FWB	-13 to 60	-13 to 60

Note

(*1) Rated conditions Cooling : Indoor air temperature 80 F Dry Bulb / 67 F Wet Bulb , Outdoor air tempreture 95 F Dry Bulb.
Heating : Indoor air temperature 70 F Dry Bulb, Outdoor air tempreture 47 F Dry Bulb / 43 F Wet Bulb.
Equivalent piping length: 100 ft, Height difference: 0 ft

(*2) Value for only outdoor unit

(*3) Setting is necessary

(*4) The amount dose not consider extra piping length. Refrigerant must be added on site in accordance with the actual piping length.

(*5) Discharge temp. sensor / Suction temp. sensor / High-pressure sensor / Low-pressure sensor / PC board fuse

(*6) MOCP : Maximum Overcurrent Protection(Amps)

(*7) Permanent operation below 80% is not recommended.

(*8) It is 54 units in case central control is in system.