

Appendix F

Revised Sewerage Impact Assessment

Application for Permission Under Section 16 of the Town Planning Ordinance (Cap. 131) for Proposed Comprehensive Development including Flats, Retail and Community Facilities and Minor Relaxation of Plot Ratio and Building Height Restriction in "Comprehensive Development Area" Zone at Various Lots in S.D.4 and Adjoining Government Land, Kau Wa Keng, Kwai Chung

Sewerage Impact Assessment

Issue 3 | September 2025

This report takes into account the particular instructions and requirements of our client. It is not intended for and should not be relied upon by any third party and no responsibility is undertaken to any third party.

283274

Arup Hong Kong Limited Level 5 Festival Walk 80 Tat Chee Avenue Kowloon Tong Kowloon Hong Kong www.arup.com



Contents

			Page				
1	Introd	luction	1				
	1.1	Background	1				
	1.2	Purpose of this Report	1				
	1.3	Structure of this Report	1				
2	Propo	sed Development	3				
	2.1	Proposed Master Layout Plan	3				
3	Outlin	ne of Existing and Planned Sewerage System	4				
	3.1	Review of Existing Sewerage System	4				
	3.2	Review of Planned Sewerage System	5				
4	Assess	Assessment Methodology for Sewerage System					
	4.1	Assumptions and Parameters for Hydraulic Assessment	7				
	4.2	Design Flow for the Village Sewerage	9				
	4.3	Planning Assumptions and Parameters	10				
	4.4	Estimating of Sewage Flow from Existing Residential Buildings Along Lai King Hill Road	10				
5		ge Flow Projection, Potential Sewerage Impacts and					
	Mitiga	ation Measures	11				
	5.1	Assessment Scenarios and Corresponding Sewer Network	11				
	5.2	Estimation of Sewage Flow under Different Assessment Scenarios	13				
	5.3	Potential Sewerage Impacts and Mitigation Measures	14				
6	Concl	usion	16				

Application for Permission Under Section 16 of the Town Planning Ordinance (Cap. 131) for Proposed Comprehensive Development including Flats, Retail and Community Facilities and Minor Relaxation of Plot Ratio and Building Height Restriction in "Comprehensive Development Area" Zone at Various Lots in S.D.4 and Adjoining Government Land, Kau Wa Keng, Kwai Chung Sewerage Impact Assessment

Appendices

Appendix A

Master Layout Plan

Appendix B

Existing Sewerage Systems

Appendix C

Interface Projects

Appendix D

Layout of Baseline Sewer Network

Appendix E

Layout of Proposed Sewer Network

Appendix F

Population and Flow under Different Scenario

Appendix G

Calculation for Impact Assessment

1 Introduction

1.1 Background

- 1.1.1.1 Arup Hong Kong Limited was commissioned to conduct a Sewerage Impact Assessment (SIA) in support of the Section 16 Planning Application for Proposed Comprehensive Development including Flats, Retail and Community Facilities and Minor Relaxation of Plot Ratio and Building Height Restriction in "Comprehensive Development Area" Zone at Various Lots in S.D.4 and Adjoining Government Land, Kau Wa Keng, Kwai Chung (the Application Site).
- 1.1.1.2 The Application Site, with an area of about 48,313.167 m², is located at the Kau Wa Keng valley floor abutting Lai King Hill Road with high accessibility to public transport. It falls within the "CDA" zone on the Approved Kwai Chung Outline Zoning Plan (OZP) No. S/KC/32.

1.2 Purpose of this Report

1.2.1 The purpose of this Sewerage Impact Assessment (SIA) is to review the sewerage impact on the overall sewerage network based on preferred option and developments in the vicinity, assess whether there is adequate capacity for the planned development, and propose mitigation measures (if any).

1.3 Structure of this Report

- 1.3.1 This SIA report will include the following:
 - **Section 1 Introduction**, presents the project background, the purpose and structure of the report;
 - **Section 2 Project Description**, presents an outline description of the project;
 - Section 3 Outline of Existing and Planned Sewerage System, describes the existing and planned sewerage systems near the project area;
 - Section 4 Hydraulic Assessment Methodology for Sewerage System, present the sewerage system assessment methodologies;
 - Section 5 Sewage Flow Projection, Potential Sewerage Impacts and Mitigation Measures, contains the proposed sewage flow, potential sewerage impacts and corresponding mitigation measures;

| Issue 3 | September 2025 Page 1 of 16

Section 6 – **Conclusion**, provides a conclusion to this SIA report.

| Issue 3 | September 2025 Page 2 of 16

2 Proposed Development

2.1 Proposed Master Layout Plan

2.1.1 The Master Layout Plan is given in **Appendix A**. The Proposed Scheme will be developed by 4 phases, namely Phase 1A (P1A), Phase 1B (P1B), Remaining Phase A (RPA) and Remaining Phase B (RPB). For ease of reference, a table showing the key development parameters of the Proposed Scheme is shown in the table below.

Table 2.1 – Design Parameters

Development Parameters	P1A	P1B	RPA	RPB	Total
No. of Flats	1,981	1,476	1,158	2,437	7,052
Community Facilities (GFA)	Home Care Services for Frail Elderly Persons (513.8m²) School Social Work Office (650.2m²) Residential Care Home for the Elderly (RCHE) (100 places) (2,708m²)	Neighbourhood Elderly Centre (656m²) Residential Care Home Centre for the Elderly (100 Places) (2,708m²)	60-place Day Care Centre for the Elderly (716m²) Office Base of On-site Pre- school Rehabilitation Services (392m²) 120-place Day Care Centre for the Elderly (DE) (non kitchen based) (1,422m²)	60-place Special Child Care Centre (818.8m²) Residential Care Home Centre for the Elderly (150 Places) (3,826m²) 100-place Child Care Centre (1,060m²)	15,470.8m ²
Resident's Clubhouse GFA	Not more than 3,000.000 m ²	Not more than 2,420.000 m ²	Not more than 2,140.000 m ²	Not more than 3,500.000 m ²	Not more than 11,060 m ²
Retail GFA	2,912.323m ²	1,516.286m ²	1,437.357m ²	832.970m ²	6,698.936m ²

| Issue 3 | September 2025 Page 3 of 16

Outline of Existing and Planned Sewerage System

3.1 Review of Existing Sewerage System

- 3.1.1 The existing sewerage system in the vicinity of the proposed site location for the development options has been reproduced with reference to the GeoInfo Map¹ and presented in **Appendix B**. The areas surrounding the north turnaround part of Lai King Hill Road are served by existing 300mm gravity sewer along Lai King Hill Road.
- 3.1.2 Kau Wa Keng areas locate to the north of Lai King Hill Road, which include the study area of this project, are currently rural residential and cultivated areas with small village houses and squatters, and without any public sewerage system. The sewage generated from the local areas is either discharged to soakaway systems that could potentially pollute the ground water, or directly discharged to the drainage system.
- 3.1.3 The topography of Kau Wa Keng areas slopes down from the outer parts of the areas in the north, east and west, to the central part in the south. Surface runoff from the local areas is collected by 4 channels flowing through the central part, the 4 channels connect to downstream drainage system from underneath Lai King Hill Road.
- 3.1.4 There are 4 existing dry weather flow interceptors (DWFIs) locate at the downstream ends of the 4 channels to intercept dry weather flow (DWF) from the local areas, the feature nos. of the 4 DWFIs, from the west to the east, are SWD4014921, SDH4000981, SDH4000982 and SDH4000983 in the drainage record. The 4 DWFIs are hereafter called DWFI1 to 4 respectively for simplification. Since that the inverts of the 4 channels as well as the ground levels of the central part are lower than Lai King Hill Road and the existing 300mm gravity sewer underneath, the flow collected by the 4 DWFIs is conveyed to the existing 300mm gravity sewer by a 150mm rising main via Kau Wa Keng DWFI Sewage Pumping Station (KWKSPS).
- 3.1.5 The DWF is conveyed to the Cheung Sha Wan Sewage Pumping Station (CSWSPS) from Kau Wa Keng DWFI Sewage Pumping Station via existing 300mm sewer. The downstream facilities of sewage flow from the Cheung Sha Wan Sewage Pumping Station will be the Northwest Kowloon Preliminary Treatment Works before entering the Stonecutter Island Sewage Treatment Works. The design capacity of

.

¹ GeoInfo Map is a geospatial information service provided by the Hong Kong Special Administrative Region (HKSAR) Government to the general public.

the sewage pumping stations (SPSs) are summarized in in **Table 3.1** below.

Table 3.1 – Design Capacity of the Downstream Sewage Pumping Stations

Name of the Sewage Pumping Station	Design Capacity (m³/day)	Mean Flow (m³/day)	Spare Capacity (m³/day)	% Spare
Kau Wa Keng DWFI Sewage Pumping Station	1,152	1,056	96	8.4%
Water Boat Dock Sewage Pumping Station	57,888	32,603	25,285	43.7%
Cheung Sha Wan Sewage Pumping Station	456,863	342,915	113,948	24.9%

3.2 Review of Planned Sewerage System

3.2.1 According to the information that is publicly available to, there are three interface public sewerage projects regarding urban and village sewerage in Lai King Hill Road or Kau Wa Keng areas. The projects are summarized in **Table 3.2** below, the source of information and design drawings provided by works divisions of the corresponding projects are presented in **Appendix C**.

Table 3.2 – Summary of Interface Public Sewerage Projects near Study area

Project No.	Planned Works Relevant to this Study	Expected Time of Completion	Refer to	Interface Issue
PWP No. 4389DS	Upgrading the existing 300mm gravity sewer along Lai King Hill to Lai Wan Road.	End 2025 - Early 2026* (for Contract No. DC.2019/11)	Appendix C1	Downstream sewer of Phase 1A and Phase 1B
PWP No. 4358DS	Village sewerage in Kau Wa Keng Old Village	End 2025	Appendix C2	Overlap with the footprint of Remaining Phase A

| Issue 3 | September 2025 Page 5 of 16

Project No.	Planned Works Relevant to this Study	Expected Time of Completion	Refer to	Interface Issue
PWP No. 4391DS	Village sewerage in Kau Wa Keng San Tsuen	TBD [#]	Appendix C3	Overlap with the footprint of Remaining Phase A

^{*} Information provided on DSD website and confirmed by the RSS of DC/2019/11.

The proposed Drainage Improvement Works (DIW) under this project is preliminary. Further study is in progress while the said DIW is yet to be confirmed.

A plan showing the existing and planned sewerage infrastructures 3.2.2 overlaying with the proposed CDA development is given in Appendix D. It is illustrated that the sewage generated from the rural areas surrounding the study area in Kau Wa Keng, as well as Remaining Phases A and B of this study, will be served by the planned village sewerage under PWP Nos. 4358DS and 4391DS.

| Issue 3 | September 2025

4 Assessment Methodology for Sewerage System

4.1 Assumptions and Parameters for Hydraulic Assessment

Unit Flow Factors

- 4.1.1 The proposed CDA will include 14 residential buildings, clubhouse facilities and community facilities, therefore sewage flows would be generated: domestic and staff of clubhouse and community facilities. Sewage generated during backwash of filters for swimming pools will also be considered.
- 4.1.2 The population in village houses inside and/or in the upstream of the proposed CDA will be considered for estimation of existing sewage flow.
- 4.1.3 ADWF for the sewage sub-catchment areas is calculated based on the estimated population and the unit flow factors (UFFs) in accordance with the EPD's Guidelines for Estimating Sewage Flow for Sewage Infrastructure (GESF). The UFFs adopted in this SIA are shown in or Table 4.1 below. Since a domestic plot ratio of 6 and an assumed flat size of 40m² are adopted in the CDA, the UFF for Residential Private Housing (R2) is adopted for the domestic sewage flow in the CDA. For existing catchments along Lai King, Residential Private Housing (R1) and (R2) are adopted for lands defined as R(A) and R(B), respectively. There are 5 swimming pools in the proposed development, 2 swimming pools in P1A and one in rest of each phase. Information of these items and calculation of daily backwash flows are presented in Table 4.1a. Since the sewage from the CDA will be discharged to public sewers via a pumping system, the backwash flow will not directly contribute to the peak flow discharged to the public sewers.

Table 4.1 – Unit Flow Factors

Category	Unit	UFF (m³/day)
Domestic [1]		
Residential Private Housing (R1)	person	0.19
Residential Private Housing (R2)	person	0.27
Modern Village	person	0.27
Commercial [2]		
Community, Social and Personal Service	employee	0.28
Restaurants & Hotels	employee	1.58
(for F&B Services in Clubhouse)		

| Issue 3 | September 2025 Page 7 of 16

Notes:

- [1] Table T-1 of GESF
- [2] Table T-2 of GESF

Table 4.1a – Swimming Pools Backwash Flow

Item	Phase	Total Volume (m³)	Turnover Rate (hr)	Surface Loading Rate (m³/m²/hr)	Filter Area (m²)	Backwash Duration (min/day)	Backwash Flow Rate (m³/m²/hr)	Daily Backwash Flow (m³)
Two Swimming Pools in P1A	P1A	780	6	20	6.5	3	30	10
One Swimming Pool in P1B	R1B	600	6	20	5.0	3	30	8
One Swimming Pool in RPA	RPA	384	6	20	3.2	3	30	5
One Swimming Pool in RPB	RPB	384	6	20	3.2	3	30	5

Notes:

Peaking Factors

- 4.1.4 The peak flow for the corresponding section of sewer is used in the hydraulic assessment to examine the sewerage impact. The peak flow is calculated from multiplying the ADWF by the relative peaking factor.
- 4.1.5 The peaking factor is based on the cumulative contributing population. The contributing population is equal to the calculated total average flow divided by a factor of 0.27. The factor is taken as an average unit flow factor described in Section 12 of the GESF. As the cumulative contributing population increases, the peaking factor and the peak flow will decrease.
- 4.1.6 As a conservative approach, the peaking factors including stormwater allowance will be used for assessing the peak flow condition. The peaking factor is selected in accordance with **Table 4.2** below.

Table 4.2 – Peaking Factors

Population Range [1]	Peaking Factor (including stormwater allowance) [2]			
(a) For sewers				
< 1,000	8			

| Issue 3 | September 2025 Page 8 of 16

^[1] The actual surface loading rate, backwash duration and backwash flow rate are subject to supplier's information in detailed design.

Population Range [1]	Peaking Factor (including stormwater allowance) [2]			
1,000 - 5,000	6			
5,000 - 10,000	5			
10,000 - 50,000	4			
> 50,000	Max [7.3/N ^{0.15} , 2.4]			
(b) For sewage treatment stations (including storm	works, preliminary treatment works & pumping water allowance for SPS)			
< 10,000	4			
10,000 - 25,000	3.5			
25,000 - 50,000	3			
> 50,000	Max [3.9/N ^{0.065} , 2.4]			
Notes: [1] N is the contributing population in thousands: N = Calculated total average flow (m³/day) / 0.27 (m³/person/day) [2] Table T-5 of GESF				

Pipe Roughness

- 4.1.7 Colebrook-White Equation is used to estimate the hydraulic capacity. In this hydraulic assessment, the roughness coefficients (k_s) adopted representing the roughness of the inner surface are as follows:
 - $k_s = 1.5 \text{ mm}$ (for HDPE sewer in poor condition)

Catchment Inflow Factor

4.1.8 The catchment inflow factor (P_{CIF}) is extracted from the GESF to assess broadly the extent of the overall net excessive inflow situation of subcatchments. Since the sewage will be discharged to the sewerage network of North West Kowloon, a P_{CIF} of 1.30 is adopted for the rural and existing and planned sewerage catchments.

4.2 Design Flow for the Village Sewerage

- 4.2.1 The design flows for Kau Wa Keng Old Village and Kau Wa Keng San Tsuen are provided by project divisions of PWP Nos. 4358DS and 4391DS. The design flow for Kau Wa Keng Old Village is 1115.74m³/day with population of 1,964, and the design flow for Kau Wa Keng San Tsuen is 418.9m³/day based on a population of 971.
- 4.2.2 House counting method is used to estimate the sewage flow from the villages after developing of the CDA. Numbers of houses covered by the planned village sewerage are counted according to the design drawings provided by the project divisions of the village sewerage (refer to **Appendix C2 and C3**). Sewage flows from the parts of

| Issue 3 | September 2025 Page 9 of 16

villages outside the proposed development are estimated based on the corresponding house numbers on a prorate basis.

4.3 Planning Assumptions and Parameters

- 4.3.1 According to the proposed development scheme, a domestic plot ratio of 6 and a non-domestic plot ratio of 0.5 are applied to different phases of the CDA. A person per flat (PPF) ratio of 2.7 is adopted with reference to the PPF of the Kwai Chung District as reported in the 2021 Population By-census by the Census and Statistics Department.
- 4.3.2 For the proposed community services facilities, numbers of employees are based on the notional staffing establishment provided by Social Welfare Department (refer to website address: https://www.swd.gov.hk/en/ngo/subventions/suballoc/subvention/nses/).

4.4 Estimating of Sewage Flow from Existing Residential Buildings Along Lai King Hill Road

- 4.4.1 The sewage flow from existing residential buildings along Lai King Hill Road is provided, which include Lai Yan Court, Happy Villa, Wah Fung Garden, Lai Chi Kok Bay Garden, Greenwood Villas and other residential buildings in Lai King Hill Road and Chung Shan Terrace. The population is based on 2021 Population By-census by the Census and Statistics Department.
- 4.4.2 Population growth is considered. According to "2019 based Territorial Population and Employment Data Matrix" (TPEDM) available on PlanD's website, there will be a decrease in population from Year 2026 to 2031 in the entire Kowloon. Therefore, population projection in Kwai Chung is adopted in this study for conservative purpose. According to TPEDM, five-year population growth rate is 1.235% according to the projected pollutions in Year 2026 and 2031. Assuming 1.235% to be the average five-year growth rate and the growth rate from Year 2026 to 2041 is 3.751%. A growth rate of 5% is adopted in the calculation of this assessment for conservative purpose.

| Issue 3 | September 2025 Page 10 of 16

5 Sewage Flow Projection, Potential Sewerage Impacts and Mitigation Measures

5.1 Assessment Scenarios and Corresponding Sewer Network

5.1.1 Three development scenarios that are considered in this assessment are listed in Table 5.1 below. Scenario 1 representing the original planned condition is baseline scenario, in which the CDA development does not exist, and all the sewage is generated from existing villages and collected by existing DWFI or the planned village sewerage (the DWFIs could be demolished after provision of the village sewerage). Scenario 2 (phase 1 development scenario) is an intermediate scenario, in which only phases P1A and P1B of the CDA have been developed. Scenario 3 is the ultimate condition with the fully developed CDA, in which the CDA is fully developed with part of the original villages being transferred to the proposed CDA, the sewage generated from the remaining of the villages will be conveyed to the public sewer network via diverted village sewerage. The existing and planned sewer network in the first scenario is shown Appendix D. The proposed conditions and corresponding sewerage diversion in the second and third scenarios are shown in Appendix E1 and E2.

Table 5.1 – Development Scenarios in this Assessment

		Sou	irce of Sewa		
No	Description	Kau Wa Keng Old Village	Kau Wa Keng San Tsuen	CDA	Sewer Network
1	Baseline	Entire Village	Entire Village	None	Existing DWFI/ Planned Village Sewerage
2	Phase 1 Development* (Intake year 2032)	Entire Village	Entire Village	Phases P1A and P1B	Planned Village Sewerage and Sewers for Phase 1 Development
3	Fully Developed CDA (Intake year 2032)	Village outside the Study Area	Village outside the Study Area	Entire CDA	Proposed Diversion to the Planned Village Sewerage and Sewers for CDA Development

^{*} The intake year of the village sewerage will be further verified in later stages.

| Issue 3 | September 2025 Page 11 of 16

- 5.1.2 In Scenario 2, the planned village sewerage will not be affected by the proposed phase 1 development. The sewage generated inside the phase 1 development will be collected by a separated sewer network (detailed network to be available in the design stage) which conveys the sewage to a proposed SPS for the CDA, the sewage will then be discharged to existing sewer manhole No. FMH4009609 via existing and proposed rising mains. The proposed SPS will cover an area of around 78m². The applicant will be responsible for the construction, operation and maintenance of the proposed SPS, rising mains, discharge sump and the connecting pipe. The planned village sewerage will be outside the fence wall of the phase 1 development and the maintenance authority of the government will have free access from outside the CDA to carry out maintenance works. A cantilevered structure of the Block 3 will be on top of a small section of the village sewerage for Kau Wa Keng San Tsuen and corresponding land will be acquired by the Applicant. The land around the planned village sewerage will become drainage reserved and DSD will have free access. The existing DWFI SDH4000981 will be demolished and re-provided. The re-provided DWFI will be located in the in the downstream of the proposed drainage system that collects stormwater from the site and an upstream catchment outside the site. The re-provided DWFI is to collect DWF only from the upstream catchment outside the site as no dry weather flow from the new development is expected. The DWF intercepted by the re-provided DWFI will be discharged to KWKSPS.
- 5.1.3 In Scenario 3, the sewage generated in the remaining parts of the villages will be diverted along the north and west boundary of the CDA, a new 225mm sewer will be provided to covey the sewage from remaining village houses outside the CDA to an existing sewer manhole No. FMH4009599. The sewage generated in the fully developed CDA will be discharged to the SPS and then existing sewer manhole No. FMH4009609 via proposed rising mains. The village sewerage diversion will be implemented by the future developer(s) of respective development phases on their own cost, the diverted village sewerage will be subsequently handed over to DSD. The proposed village sewerage diversion will be carried out prior to the proposed demolition of planned sewer. The planned village sewerage and corresponding diversion will be outside the fence wall of the CDA, and the maintenance authority of the government will have free access from outside the CDA to carry out maintenance works. A drainage reserve along the proposed sewerage diversion as shown in Appendix E2 will be provided for construction the planned village sewerage if the completion of the proposed development is before the completion of

| Issue 3 | September 2025 Page 12 of 16

the planned village sewerage. The existing DWFI SDH4000980 will be demolished and re-provided. This DWFI is located in an existing channel within the site boundary of Phase RPA Development. The existing channel will be demolished and a new box culvert will be re-provided along the site boundary and the re-provided DWFI will be constructed in the downstream of the box culvert. The DWF intercepted by the re-provided DWFI will be discharged to the diverted village sewer that connects to KWKSPS.

5.1.4 The re-provision of DWFI Nos. SDH4000980 and SDH4000981 will be implemented by the Applicant and no adverse sewerage impact is anticipated due to demolishment and re-provision of DWFIs as all DWFI would be retained or re-provided so that all potential DWF from the original catchments will be intercepted, and there is no additional catchment for the DWFIs so no additional DWF will be collected.

5.2 Estimation of Sewage Flow under Different Assessment Scenarios

Calculation of the population and corresponding ADWF in different assessment scenarios are provided in **Appendix F**. **Table 5.2** below gives the key information required for impact assessment. The total ADWF considering the proposed development is 5,176m³/day and 7,986m³/day in Scenario 2 and 3 respectively.

Table 5.2 – Summary of ADWF in Different Assessment Scenarios

		ADWF from Different Sources (m³/day)				Peak Flow
Scenario No.	Discharge Point	Kau Wa Keng Old Village	Kau Wa Keng San Tsuen	CDA	Total ADWF (m³/day)	for the Proposed SPS (m ³ /s)
1	FMH4009607 from KWKSPS	1,116	419	0	1,535	0
2	FMH4009609 from KWKSPS and the proposed SPS	1,116	419	3,642	5,176	0.148
3	FMH4009609 from KWKSPS and the proposed SPS	228	393	7,364	<mark>7,986</mark>	0.256

5.2.2 Catchment inflow factor (P_{CIF}) of 1.30 and peaking factors including stormwater allowance are adopted in the calculation for the proposed

| Issue 3 | September 2025 Page 13 of 16

SPS. The design capacity of the proposed SPS is 7,364 m³/day. For KWKSPS, since it is an existing facility, the maximum pump rate (average design ADWF with peaking factor of 4) is the peak flow discharged to downstream sewer network.

5.3 Potential Sewerage Impacts and Mitigation Measures

- 5.3.1 Impact assessments have been done for the following potential impacts to the existing sewerage system:
 - Potential impact to sewers to the downstream of manhole No. FMH4009599 due to the proposed diversion of village sewerage in Scenario 3 for village sewerage diversion;
 - Potential impact to sewers to the downstream of manhole No. FMH4009607 due to sewage generated from the proposed CDA;
 - Potential impact to the downstream of manhole No. FMH4009445 due to the upstream flow.

Detailed calculation has been included in **Appendix G**.

- In Scenario 3, the peak sewage flow discharged to sewer manhole No. FMH4009599 will be 0.029m³/s after the village sewerage diversion, which is larger than the capacity of downstream gravity sewer. Therefore, it is proposed to upgrade the existing sewer between FMH4009599 and the KWKSPS to 300mm, proposed upgrading works will be constructed by the Applicant at their own cost and subsequently handed over to DSD for future maintenance.
- 5.3.3 The additional peak sewage flow discharged from the proposed SPS to sewer manhole No. FMH4009609 in Scenario 2 and 3 will be 0.148m³/s and 0.256m³/s, respectively. According to the latest information of Contract No. DC/2019/11 (refer to information of PWP No. 4389DS in Appendix C1), the sewer in the downstream of sewer manhole No. FMH4009607 will be upgraded to a 675mm sewer by early 2026, which is cater for the peak sewage flow from existing KWKSPS, existing residential buildings along Lai King Hill Road and the proposed development via the proposed SPS and rising main. In case of programme mismatch between the interfacing project, proposed sewerage upgrading works between manhole Nos. FMH4009607 and FMH4009444 will be constructed by the Applicant at their own cost and subsequently handed over to DSD for future maintenance.
- 5.3.4 The proposed SPS rising mains, discharge sump and the connecting sewer between the discharge sump and manhole FMH4009607 will be constructed and maintained by the Applicant at their own cost. The

| Issue 3 | September 2025 Page 14 of 16

Application for Permission Under Section 16 of the Town Planning Ordinance (Cap. 131) for Proposed Comprehensive Development including Flats, Retail and Community Facilities and Minor Relaxation of Plot Ratio and Building Height Restriction in "Comprehensive Development Area" Zone at Various Lots in S.D.4 and Adjoining Government Land, Kau Wa Keng, Kwai Chung Sewerage Impact Assessment

capacity of the proposed SPS is 7,364m³/day. Layout of the proposed SPS is shown on **Appendix E1**.

| Issue 3 | September 2025 Page 15 of 16


Conclusion 6

- 6.1.1 A SIA study has been undertaken for the proposed development.
- The estimated total ADWF generated from the proposed development 6.1.2 is approximately 7,983 m³/day.
- 6.1.3 It has been identified that there is no adverse impact to the downstream SPSs due to the proposed development and associated sewerage diversion, upgrading works to the existing sewer between Kau Wa Keng San Tsuen and KWKSPS should be carried out to mitigate potential impacts due to the village sewerage diversion works. The proposed CDA has no adverse impact on the downstream sewer after considering the planned sewer upgrading works under PWP No. 4389DS to be completed by early 2026.
- The applicant will be responsible for the construction, operation and 6.1.4 maintenance of the proposed SPS, rising mains, discharge sump and the connecting pipes.

| Issue 3 | September 2025

Appendix A

Master Layout Plan




Application for Permission Under Section 16 of the Town Planning Ordinance (Cap. 131) for Proposed Comprehensive Development including Flats, Retail and Community Facilities and Minor Relaxation of Plot Ratio and Building Height Restriction in "Comprehensive Development Area" Zone at Various Lots in S.D.4 and Adjoining Government Land, Kau Wa Keng, Kwai Chung Sewerage Impact Assessment

Appendix B

Existing Sewerage Systems

Appendix B - Existing Drainage & Sewerage Systems



Appendix C

Interface Projects

Status of PWP No. 4389DS according to DSD's website

★ Home > Tender Notices and Our Projects > All Projects



PWP No. 4389DS

Upgrading of West Kowloon and Tsuen Wan Sewerage – Phase 2

Project Scope: Upgrading of existing sewerage system in West Kowloon and

Tsuen Wan

Major Improvements and To improve the existing sewerage system in West Kowloon

and Tsuen Wan to cater for developments and to improve

≺ Back

quality of receiving waters.

Consultants: Atkins China Limited

Contractor: DC/2019/11 - Kum Shing (K.F.) Construction Company

Limited

DC/2019/12 - Shun Yuen Construction Company Limited

DC/2020/01 - Welcome Construction Company Limited

Contract No.: DC/2019/11, DC/2019/12, DC/2020/01

Project Commencement 20 July 2020

Dato:

Benefits:

Project Completion Date: Mid 2026

Project estimate: About \$2,300 million

Controlling Division: Harbour Area Treatment Scheme Division


Type: Sewerage and sewage treatment

District: Kowloon City; Sham Shui Po; Yau Tsim Mong; Kwai Tsing;

Tsuen Wan

Status: On-going

Other Information: Project Layout Plan (TW) roject Layout Plan (WK)





g.	
ăì.	

MANHOLE

REFERENCE

MANHOLE SCHEDULE (TSUEN WAN AREA)

GROUND

INVER

PIPE

MANHOLE

MA25

MA26

4.79

3.86

G1

1.820

1.700

750

225

750

OC

EXT.

ОС

TYPE LEVEL LEVEL LEVEL SIZE (mn NUMBER MATERIAL MANHOLE NO. MATERIAL (mPD) (mPD) (mPD) GROUTING D1 5.21 OD355 PE MC2 MC1 4.000 5.27 3.850 OD355 PE MC1 OD355 PE MC3 MC2 D1 3.850 Class B MC3 D1 5.19 3.820 OD355 PΕ MC2 3.780 OD450 PE MC4 Class B 225 EXT. EMH4006933 D1 5.19 3.740 OD450 3.740 PE MC4 PE MC3 OD450 MC5 Class B 5.13 3.640 PE MC4 OD450 PE FMH4007131 MC5 D1 OD450 3.640 Class B EXT. MH 5.12 EXT. 4.700 OD280 PE FMH4006902 Class B FMH4006902 FXT MH 5.88 4 000 OD280 PE MC6 CHUNG AREAD MANHOLE/SCHEDULE/LKWAI OUTLET PIPE INLET PIPE **APPROX** MANHOLE MANHOLE GROUND BEDDING INVFRT INVERT REFERENCE PIPE PIPE TOMANHOLE LEVEL SIZE (mm) MATERIAL LEVEL SIZE (mm) LEVEL NUMBER MATERIAL MANHOLE NO. NO (mPD) (mPD) (mPD) E1 375 EXT. FMH4022463 OD450 MC7 MC6 11.8 Class A 9.920 MC7 12.58 OD450 PE MC6 OD450 MC8 9.000 9.000 375 EXT. FMH4022482 375 EXT. MC8A MC8 F1 12.58 8.950 OD450 PE MC7 OD450 MC8A Class A MC8A E1 8.81 6.910 OD450 PE MC8 375 EXT. FMH4006969 375 EXT. MC7 225 EXT. FMH4006988 300 EXT. FMH4006986 MC9A F1 + BD 20.8 225 EXT. FMH4088220 17.500 OD450 PE MC9B GROUTING FMH4023100 225 EXT. MC9B F1 20.6 17.160 OD450 PE MC9A 17.160 OD450 PE MC9C Class A EXT. FMH4023100 225 MC9C F1 20.49 17.000 OD450 PΕ MC9B 17.000 OD450 PE FMH4023102 Class A FMH4023102 EXT. MH 20.35 16,740 OD450 PE MC9C FMH4023103 MA10 E1 4.5 150 EXT. FMH4020078 3.290 OD560 OC MA17 TYPE I MA11 D1 375 EXT. FMH4020067 3.500 675 OC MA12 TYPE I MA12 E1 3.280 675 ОС MA11 675 MA13 3.280 OC Class B 350 EXT. MA13 E1 3.195 675 OC MA12 3.195 675 OC MA14 GROUTING MA14 E1 3.050 675 OC MA13 3.050 675 OC MA15 GROUTING 450 EXT. FMH4020079 E1 2.989 675 OC MA14 2.989 675 MA16 MA15 OC Class B MA16 E1 2.894 675 OC MA15 675 MA17 Class B MA17 E1 + BD 4.84 3.590 OD560 OC MA10 2.880 675 OC MA18 Class B 2.880 675 ОС MA16 MA18 E1 4 89 2 650 675 OC MA17 2.650 675 OC MA19 Class B 675 MA19 E1 4.79 2.510 675 OC MA18 2.510 OC MA20 Class B MA20 4.77 2.480 675 OC MA19 2.480 750 OC MA21 Class B 150 EXT. FMH4020077 MA21 4.69 2.370 750 OC MA20 2.370 750 OC MA22 Class B MA22 MA21 750 MA23 4.56 2.230 750 OC 2.230 OC Class B MA23 4.46 2.090 750 OC MA22 2.090 750 OC MA24 Class B 750 MA24 4.627 1.960 OC MA23 1.960 750 OC MA25 Class B

MA24

FMH4022729

MA25

1.820

1.700

750

750

OC

MA26

MA27

Class B

OUTLET PIPE

PIPE

TOMANHOLE

INVERT

FROM

BEDDING

•	NOT SCAL		LET PIPE	OUT		INLET PIPE				APPROX		ANHOLE
	BEDDING TYPE	TOMANHOLE NO.	PIPE MATERIAL	SIZE (mm)	INVERT LEVEL (m PD)	FROM MANHOLE NO.	PIPE MATERIAL	SIZE (mm)	INVERT LEVEL (mPD)	GROUND LEVEL (mPD)	MANHOLE TYPE	FERENCE IUMBER
	Class B	MA28	OC	750	1.500	MA26	OC	750	1.500	4.15	Н	MA27
	Class A	MA29	OC	750	1.370	MA27	OC	750	1.370	4.5	Н	MA28
						FMH4022735	EXT.	375	-			
	GROUTING	MA30	ОС	900	1.250	MA28	ОС	750	1.250	5.132	I	MA29
	GROUTING	MA31	OC	900	1.180	MA29 FMH4019828	OC EXT.	900 450	1.180	5.5	L	MA30
						FMH4019804	EXT.	375	-			
	Class A	MA32	OC	900	1.160	MA30	OC	900	1.160	5.16	I	MA31
	Class A	MA33	OC	900	1.080	MA31	ОС	900	1.080	5.247	I	MA32
	Class A	MA34	OC	900	1.010	MA32	OC	900	1.010	5.41	L	MA33
						FMH4022722	EXT.	300	-			
	Class A	MA35	ОС	900	0.880	MA33 FMH4022696	OC EXT.	900 375	0.880	5.23	L	MA34
	Class A	MA36	OC	900	0.840	MA34	OC	900	0.840	5.28	L	MA35
	GROUTING	MA43	OC	900	0.780	MA35	OC	900	0.790	6.36	SP3+BD	MA36
	- GROUTING	FMH4022698	EXT.	600	0.780	FMH4022715	EXT.	225	3.180	0.30	252+RD	WASO
						FMH4022710	EXT.	300	3.340			
	GROUTING -	FMH4022703 FMH4022703	OC EXT.	675 675	0.420	MA36 FMH4022701	OC EXT.	900	0.420	6.225	SP3	MA43
		FMH4022704					OC OC		0.370	7.6	EXT. MH	IH4022703
	-	FIVITI4UZZ/U4	-	-	-	MA43 MA43	EXT.	675 675	0.370	1.0	EAL MH	n4022703
	GROUTING	MB2	PE	OD280	30.430	FMH4009638	EXT.	150	-	31.73	D1	MB1
	GROUTING	MB3	PE	OD280	30.135	MB1	PE	OD280	30.135	31.42	D1	MB2
	GROUTING	MB4	PE	OD280	30.042	MB2	PE	OD280	30.042	31.21	D1	MB3
	-	FMH4009643	EXT.	150	-	MB3	PE	OD280	29.783	30.64	C1	MB4
	GROUTING	MB6	PE	OD560	39.440	FMH4009419	EXT.	300	-	41.44	E1	MB5
	GROUTING	MB7	PE	OD560	37.440	MB5	PE	OD560	37.440	39.44	E1	1B6
	LEAKAGE	MDO	DE	ODECO	25 400	MDe	DE	ODEGO	25 400	27.40	E1 DD	MD7
	COLLECTION	MB8	PE	OD560	35.490	MB6 FMH4009658	PE EXT.	OD560 225	35.490	37.49	E1 + BD	MB7
	LEAKAGE COLLECTION	MB9	PE	OD560	34.540	MB7	PE	OD560	34.540	36.54	E1	MB8
		IVIDS	FE	OD300	J4.J4U	IVID/	FE	OD300	J4.J4U	50.54	EI	INIDO
	LEAKAGE COLLECTION	MB10	PE	OD560	31.645	MB8	PE	OD560	31.645	33.65	E1	MB9
	LEAKAGE COLLECTION	MB11	PE	OD560	29.090	MB9	PE	OD560	29.090	31.09	E1	MB10
	LEAKAGE											
	COLLECTION	MB12	PE	OD560	26.910	MB10	PE	OD560	26.910	28.91	E1	/IB11
	LEAKAGE COLLECTION	MB13	PE	OD560	24.300	MB11	PE	OD560	24.300	26.3	E1	MB12
	LEAKAGE COLLECTION	MB14	PE	OD560	21.800	MB12	PE	OD560	21.800	23.8	E1	MB13
	LEAKAGE											-
	COLLECTION	MB15	PE	OD560	18.600	MB13	PE	OD560	18.600	20.6	E1	MB14
	LEAKAGE COLLECTION	MB16	PE	OD560	16.270	MB14	PE	OD560	16.270	18.27	E1	MB15
		FMH4009431	EXT.	300	-							
	-	FMH4009432	EXT.	300	-	MB15 FMH4009610	PE EXT.	OD560 300	13.540	15.92	E1	MB16
	TYPE I	MB17A	OC	600	4.500	-	EXT.	150	-	5.97	D1	MB17
	TYPE I	MB18	OC	600	4.390	MB17	OC	600	4.390	5.97	E1	MB17A

- THIS DRAWING SHALL BE READ IN CONJUNCTION WITH DRAWING NO. 5130661-DC1911-1000 TO 1037.
- 2. FOR BEDDING TYPE:
- b) CLASS B : CLASS B BEDDING DETAILS REFER TO DSD STANDARD DRAWING NO. DS1048.
- c) TYPE I: TYPE I CONCRETE SURROUND
 DETAILS REFER TO DSD STANDARD DRAWING NO. DS1049.
- d) LEAKAGE COLLECTION: LEAKAGE COLLECTION SYSTEM DETAILS REFER TO DRAWING 5130661-DC1911-2102.
- DETAILS OF MANHOLES AND COVERS REFER TO DSD STANDARD DRAWINGS UNLESS OTHERWISE SPECIFIED.
- 4. DETAILS OF SPECIAL MANHOLES REFER TO DRAWING NOS. 5130661-DC1911-2001 TO 2005.

LEGEND AND ABBREVIATION:

SPECIAL MANHOLE TYPE 5

BACKDROP TYPE 3

EXISTING SEWERAGE PRECAST CONCRETE POLYETHYLENE

SPECIAL MANHOLE TYPE 2 SPECIAL MANHOLE TYPE 3 SPECIAL MANHOLE TYPE 4

- JAN 20 ISSUE FOR TENDER XJY WKML DF By Chk'd App'd Rev. Date

TENDER

Member of the SNC-Lavalin Group



渠務署 Drainage Services Department

顧問工程管理部 Consultants Management Division

CONTRACT NO. DC/2019/11 UPGRADING OF WEST KOWLOON AND

TSUEN WAN SEWERAGE -PHASE 2A

MANHOLE SCHEDULE (SHEET 3)

7	Scale	Designed	Drawn	Checked	Authorised					
4	N:509.	XJY	AC	WKML	DF					
+	Orlginal Size A1	Date JAN 2020	JAN 2020	Date JAN 2020	JAN 2020					
_	Drawing Number				Revision					
	51	5130661-DC1911-1103								

MANHOLE SCHEDULE (KWAI CHUNG AREA)

		APPROX		INI	ET PIPE						
MANHOLE REFERENCE NUMBER	MANHOLE TYPE	1	INVERT LEVEL (mPD)		DIDE	FROM MANHOLE NO.	INVERT LEVEL (m PD)		PIPE PIPE MATERIAL	TOMANHOLE NO.	BEDDING TYPE
MB19	E1	5.98	4.290	600	oc	MB18	4.290	675	OC	MB20	Class B
			-	300	EXT.	FMH4009566					
MB20	E1	5.94	4.240	675	ОС	MB19	4.240	675	OC	MB21	Class B
MB21	E1	5.78	4.010	675	ос	MB20	4.010	675	oc	MB22	Class B
MB22	E1	5.65	3.810	675	ОС	MB21	3.810	675	ОС	MB23	Class B
MB23	E1	5.47	3.650	675	ос	MB22	3.650	675	ОС	MB24	Class B
			-	150	EXT.	-					
MB24	E1	5.4	3.510	675	ОС	MB23	3.510	675	ОС	MB25	Class B
MB25	E1	5.34	3.330	675	OC	MB24	3.330	675	OC	MB26	Class B
MB26	E1 + BD	5.34	3.210	675	ОС	MB25	3.210	675	OC	MB27	GROUTING
			3.900	225	EXT.	FMH4009597					
MB27	E1	5.62	3.090	675	ОС	MB26	3.090	675	ОС	MB28	Class B
MB28	E1	5.62	3.030	675	ос	MB27	3.030	675	ОС	MB29	Class B
		5.02	0,000				0,000				0.000 2
MB29	E1	5.22	2.860	675	ОС	MB28	2.860	675	ОС	MB30	Class B
MB30	E1	4.97	2.730	675	ОС	MB29	2.730	675	ОС	MB31	Class B
Man			0.500	075		14500	0.450	075			00015010
MB31	E1	4.7	2.580	675	oc	MB30	2.450	675	OC	MB32	GROUTING
MB32	E1	4.84	2.350	675	ОС	MB31	2.350	OD560	PE	FMH4009443	Class B
							-	375	EXT.	FMH4009444	-
FMH4009443	EXT. MH	4.84	2.320	OD560	PE	MB32	-	600	EXT.	FMH4009444	-
			-	600	EXT.	FMH4009589					
			-	500	EXT.	FMH4009442					

MANHOLE SCHEDULE (SHAM SHU! PO AREA)

MANHOLE		APPROX		INL	ET PIPE				OUTLET PIPE		
REFERENCE NUMBER	MANHOLE TYPE	GROUND LEVEL (mPD)	INVERT LEVEL (mPD)	SIZE (mm)	PIPE MATERIAL	FROM MANHOLE NO.	INVERT LEVEL (mPD)	SIZE (mm)	PIPE MATERIAL	TOMANHOLE NO.	BEDDING TYPE
MF38	E1	9.81	-	-	-	-	8.000	OD355	PE	MF39	Class E
MF39	F1 + BD	10	6.900	OD355	PE	MF38	6.900	OD355	PE	MF42	Class A
			8.740	150	EXT.	FMH4010169					
			-	150	EXT.	FMH4010172					
			8.740	150	EXT.	FMH4010173					
MF40	F1 + BD	9.57	7.500	300	EXT.	FMH4010176	6.030	525	OC	MF41	Class I
			6.030	450	EXT.	FMH4010166					
MF41	F1	9.65	5.970	525	ОС	MF40	5.970	525	OC	MF42	Class /
			6.300	300	EXT.	-					
MF42	1	9.95	6.100	OD355	PE	MF39	5.700	525	OC	FMH4010148	Class
			5.700	525	ОС	MF41					
			5.700	225	EXT.	-					
FMH4010148	EXT. MH	10.31	5.430	525	ОС	MF42	-	-	-	FMH4010149	-
MF01	C1	6.07	5.160	150	EXT.	FMH4010270	5.160	OD355	PE	MF02	Class /
			5.160	150	EXT.	FMH4010320					
MF02	D1	6.15	4.930	OD355	PE	MF01	4.930	OD355	PE	MF03	Class
			5.140	150	EXT.	-					

DO NOT SCALE NOTES:

	1 - 10 - 20 -	
	1. THIS DRAWING SHALL BE READ IN CONJUNCTION W	HT)
1 I	DDAWING NO. 5130661-DC1011-1000 TO 1037	

2. FOR BEDDING TYPE:

a) CLASS A: CLASS A (REINFORCED) BEDDING DETAILS REFER TO DSD STANDARD DRAIWNG NO. DS1048.

b) CLASS B : CLASS B BEDDING
DETAILS REFER TO DSD STANDARD DRAWING NO. DS1048.

c) TYPE I: TYPE I CONCRETE SURROUND DETAILS REFER TO DSD STANDARD DRAWING NO. DS1049.

d) LEAKAGE COLLECTION : LEAKAGE COLLECTION SYSTEM DETAILS REFER TO DRAWING 5130661-DC1911-2102.

3. DETAILS OF MANHOLES AND COVERS REFER TO DSD STANDARD DRAWINGS UNLESS OTHERWISE SPECIFIED.

4. DETAILS OF SPECIAL MANHOLES REFER TO DRAWING NOS. 5130661-DC1911-2001 TO 2005.

LEGEND AND ABBREVIATION :

Εx	t	EXISTIN	G SEWERA	GE
OC		PRECAST	CONCRETE	
PE		POL YE TH	YLENE	
SP	1	SPECIAL	MANHOLE	TYPE 1
SP	2	SPECIAL	MANHOLE	TYPE 2
SP	3	SPECIAL	MANHOLE	TYPE 3
SP	4	SPECIAL	MANHOLE	TYPE 4
SP	5	SPECIAL	MANHOL F	TYPE 5

BACKDROP TYPE 3

Rev.	Date	Description	Ву	Chk'd	App'd
-	JAN 20	ISSUE FOR TENDER	XJY	WKML	DF
			Xm.	سسا	b

TENDER

Member of the SNC-Lavalin Group



渠務署 集務署 Drainage Services Department

顧問工程管理部 Consultants Management Division

CONTRACT NO. DC/2019/11 UPGRADING OF WEST KOWLOON AND TSUEN WAN SEWERAGE -PHASE 2A

MANHOLE SCHEDULE (SHEET 4)

	Scale	Designed	Drawn	Checked	Authorised					
7	NI: 508).	XJY	AC	WKML	DF					
	Original Size A1	JAN 2020	JAN 2020	JAN 2020	JAN 2020					
	Drawing Number				Revision					
	51	5130661-DC1911-1104								

		APPROX		INI	ET PIPE			1	OUTLET PIPE		
MANHOLE REFERENCE	MANHOLE	GROUND	INVERT			FROM	INVERT			TOMANHOLE	BEDDING
NUMBER	TYPE	(mPD)	LEVEL (mPD)	SIZE (mm)	PIPE MATERIAL	MANHOLE NO.	LEVEL (mPD)	SIZE (mm)	PIPE MATERIAL	NO.	TYPE
MF03	D1	6.25	4.790	OD355	PE	MF02	4.790	OD355	PE	MF04	Class B
			5.790 5.150	225 150	EXT.	-					
MF04	D1	6.13	4.720	OD355	PE	MF03	4.720	OD355	PE	MF05	Class P
WF04	DI	0.13	4.720	150	EXT.	-	4.720	ODSSS	PE	MIFUS	Class B
MEGE	D1	6.12	4.600	OD355	DE	MEOA	4.690	ODSEE	PE	MEGG	Class D
MF05	D1	6.12	4.680 5.220	150	PE EXT.	MF04 -	4.680 4.650	OD355 300	EXT.	MF06 MF06	Class B
MF06	E1	6.24	4.640	OD255	PE	MF05	4.640	ODSEE	PE	ME07	Class P
WFOO	E1	0.24	4.640	OD355 150	EXT.	-	4.630	OD355 300	EXT.	MF07 MF07	Class B
			4.630	300	EXT.	MF05					
MF07	E1	6.24	4.600	OD355	PE	MF06	4.600	OD355	PE	MF08	Class B
			4.630	300	EXT.	MF06	4.630	300	EXT.	MF08	-
MF08	E1	6.25	4.170	OD355	PE	MF07	4.170	OD355	PE	MF09	Class B
			-	300	EXT.	MF07	-	300	EXT.	MF09	-
MF10	C1	6.13	-	-	-	-	5.290	OD355	PE	MF11	Class A
MF11	D1	6.2	5.100	OD355	PE	MF10	5.100	OD355	PE	MF12	Class A
MF12	D1	6.19	5.040 5.060	OD355 150	PE EXT.	MF11 -	5.040	OD355	PE	MF13	Class A
MF13	D1	6.2	4.950	OD355 150	PE EXT.	MF12 -	4.950	OD355	PE	MF14	Class B
MF14	E1	6.24	4.670	OD355	PE	MF13	4.670	OD355	PE	MF15	Class B
MF15	E1	6.25	4.648	OD355	PE	MF14	4.648	OD355	PE	MF16	Class B
			-	150 150	EXT.	-					
			-	150	EXT.	-					
MF16	E1	6.28	4.581	OD355	PE	MF15	4.581	OD355	PE	MF17	Class B
			-	150	EXT.	-					
MF17	E1	6.28	4.539	OD355	PE	MF16	4.539	OD355	PE	MF18	Class B
14540		2.22	4 470	00055	5-	14547	4.470	00055		14540	
MF18	E1	6.26	4.470	OD355	PE	MF17	4.470	OD355	PE	MF19	Class B
MF19	E1	6.27	4.430	OD355	PE	MF18	4.430	OD355	PE	MF20	Class B
			-	150	EXT.	-					
MF20	E1	6.27	4.247	OD355	PE	MF19	4.247	OD355	PE	MF09	Class B
MF09	E1	6.27	3.950	OD355	PE	MF08	3.930	450	EXT.	FMH4010274	-
			4.100	OD355	PE	MF20					
MF33	E1	7.31	-	-	-	-	4.940	OD560	PE	MF34	Class B
MF34	E1	7.36	4.840	OD560	PE	MF33	4.840	OD560	PE	MF35	Class B
mi o4		7.00	6.160	150	EXT.	-	4.040	CECCO		WII 00	Oldoo B
MF35	E1	7.36	4.780	OD560	PE	MF34	4.780	OD560	PE	MF62	Class B
			5.910	150	EXT.	-					
MF21	E1	6.18	-	150	EXT.	FMH4064080	4.380	OD560	PE	MF22	Class B
MF22	E1	6.24	4.120	OD560	PE	MF21	4.120	OD560	PE	MF23	Class B
MF23	E1	6.24	4.000	OD560	PE	MF22	4.000	OD560	PE	MF24	Class B
MF24	E1	6.24	3.873	OD560	PE	MF23	3.873	OD560	PE	MF25	Class B
			4.390	150	EXT.	-					
MF25	E1	6.205	3.800	OD560	PE	MF24	3.800	OD560	PE	MF26	Class B
MF26	E1	6.2	3.728	OD560	PE	MF25	3.728	OD560	PE	MF70	Class D
WIFZO	EI	0.2	3.120	OD000	FE	WIFZO	5.120	OD300	FE	IVIETU	Class B
MF27	E1	6.21	4.650 4.100	150 150	EXT.	- FMH4062347	4.070	OD560	PE	MF28	Class B
			4.580	150	EXT.	-					
MF28	E1	6.18	3.625	OD560	PE	MF27	3.625	OD560	PE	FMH4010234	Class B
		5.10					5.520	35000			J.000 D
FMH4010234	EXT. MH	6.12	3.500	OD560	PE	MF28	-	-	-	FMH4010235	-
MF29	D1	6	4.920	150	EXT.	FMH4054447	4.800	OD560	PE	MF30	Class A



Drainage Hotline 2300 1110 📳 📁 enter search keyword(s)

About Us

Information Corner

Tender Notices and Our Projects

Core Business

Sewage Services Charging Scheme

Technical **Documents**

Service Enquiries

|≡×


Drainage Services Department



What's New



☆ Home > Information Corner > What's New



DSD awarded Contract No. DC/2019/11 "Upgrading of West Kowloon and Tsuen Wan Sewerage – Phase 2A"

31 July 2020

The Drainage Services Department (DSD) signed a works contract of about \$257 million with Kum Shing (K.F.) Construction Company Limited on 31 July 2020. The works include construction of about 14 kilometres of gravity sewers; provision of internal lining at 6 existing sewers; construction of 2 new dry weather flow interceptors and ancillary works. This 65-month works contract commenced on 20 July 2020.

工務計劃項目第 4358DS 號 老圍、川龍及九華徑舊村污水收集系統(部分) 新界葵青九華徑舊村鄉村污水收集系統

工程項目簡介

工程計劃的背景及效益

1. 現時仍有不少村屋或食肆的污水及生活廢水未經妥善處理便直接或間接地排放進溪澗或河道之內,對區內環境造成環境污染(如<u>附件一:</u>「化糞池所產生的污染問題」)。 為了減少這些污染以改善鄰近環境的衛生及符合有關污染管制法例的要求,政府現正計劃在沙頭角、打鼓嶺、荃灣及葵青等一帶地區的鄉村內建造公共污水收集系統。詳情可參閱渠務署印製的附件二:「鄉村污水收集系統計劃」單張。

當工程完成後,村內所產生的污水將會經由公共污水收集系統排放至 污水處理廠集中處理,以取代村內現有的化糞池系統和減少村民長期 維修化糞池的需要。 更重要是可以改善村內及附近地區的水質,提 升村民的生活質素和環境衛生。

工程計劃的範圍

 工程計劃範圍包括為位於沙頭角、打鼓嶺、荃灣及葵青等一帶地區的 鄉村建造污水收集系統。當中位於葵青區的鄉村包括:

九華徑舊村

3. 工務計劃項目第 4358DS 號將會為九華徑舊村鋪設約 1.6公里長的污水 渠。工程範圍及初步設計請參閱<u>附件三</u>。

環境影響及相應的舒減措施

4. 我們將會就本工程計劃制定適當的環境影響紓緩措施,以紓減施工期間及當有關設施啟用後對環境的影響。

徵收土地

5. 我們在規劃及設計有關污水收集系統時,會將有關的污水渠建於現有 鄉村通道之下及政府土地範圍內,避免徵收私人土地。擬建工程將不 會涉及徵收私人土地及清拆現有房屋。

村屋的污水接駁安排

6. 有關的公共污水渠及主要沙井將由渠務署負責建造及維修保養,而村民則須要自行建造及保養各自物業的終端沙井及接駁渠。 現附上附件四:「村屋接駁污水渠的示意圖」、環境保護署印製的附件五:「接駁污水渠計劃」中英文版單張及渠務署印製的附件六:「終端沙井的規格」以供參考。

排污費用

7. 排污費用將會在村屋/物業成功接駁至公共污水收集系統後開始收取。 根據現時的污水處理服務收費,住宅用戶每立方米用水須繳交 2.92 元 排污費,而每個住宅用戶每 4 個月一期的首 12 立方米用水,是免收排 污費的。 排污費用將會在將來作出調整。 排污收費的詳情可參考 渠務署印製的附件七:「排污收費」單張及附件八:「住宅用水排污費 與水費參考表」。

鄉村污水渠的接駁與維修資助

8. 終端沙井及接駁渠的建造費用,會視乎個別情况有所不同,包括村屋大小、地勢環境、村民與各自聘用的工程承包商的商討等。 在工程進行期間,工程人員必會先到有關鄉村,盡量安排預留的接駁點貼近村屋邊界,方便村民接駁,以期減低日後的接駁費用。至於個別經濟有困難的村民,可以考慮申請由政府透過香港房屋協會提供的家居維修免息貸款計劃或有需要人士維修自住物業津貼計劃。 有關計劃已獲批准涵蓋村渠接駁在內的排污裝置更換維修工程。 詳情可參閱「鄉村污水渠的接駁與維修資助」小冊子。

未來路向

9. 我們計劃於 2021 年年中根據《水污染管制(排污設備)規例》(第 358AL章)第 26 條引用《道路(工程、使用及補償)條例》(第 370 章)把九華徑舊村工程計劃的詳情刊登於憲報。

預計進度


10. 我們初步計劃在 2022 年年底為九華徑舊村開展工程,並預計於 2025 年年底完成。

諮詢意見

11. 請各委員就上述工程提出意見,並支持上述工程計劃,使工程可以盡快如期展開。

渠務署

2021年3月





KAU WA KENG MANHOLE SCHEDULE FOR BRANCH 1

		COVER LEVEL	INL	ΕT		OUTLET		PIPE		
MANHOLE NO.	MANHOLE TYPE	(mPD)	INVERT LEVEL (mPD)	PIPE SIZE (mm) DN	INVERT LEVEL (mPD)	PIPE SIZE (mm) DN	TO MANHOLE	MATERIAL	TYPE OF BEDDING	REMARKS
KWK0101	C1	13.00	12.00	250.00	11.96	250.00	KWK0102	PE	TYPE B BEDDING	_
KWK0102	D1	12.76	11.66	250.00	11.60	250.00	KWK0103	PE	TYPE B BEDDING	_
K WK 0103	C1	12.38	11.38	250.00	11.34	250.00	KWK0104	PE	TYPE B BEDDING	-
KWK0104	C1	12.11	11.11	250.00	11.08	250.00	KWK0105	PE	TYPE B BEDDING	_
KWK0105	C1	11.90	10.90	250.00	10.85	250.00	KWK0106	PE	TYPE B BEDDING	_
K WK 0106	C1	11.65	10.65	250.00	10.60	250.00	KWK0107	PE	TYPE B BEDDING	-
KWK0107	C1	11.46	10.46	250.00	10.38	250.00	KWK0108	PE	TYPE B BEDDING	-
K WK 0108	D1	11.14	9.94	250.00	9.89	250.00	KWK0109	PE	TYPE B BEDDING	-
KWK0109	BACKDROP T3	10.64	7.54	250.00	7.45	250.00	KWK0110	PE	TYPE B BEDDING	WITH BACKDROP
KWK0110	BACKDROP T3	8.18	6.38	250.00	6.34	250.00	K WK O 1 1 1	PE	TYPE B BEDDING	WITH BACKDROP
K WK O 1 1 1	D1	7.16	6.06	250.00	6.01	250.00	KWK0112	PE	TYPE B BEDDING	-
KWK0112	C1	6.76	6.01	250.00	5.98	250.00	KWK0113	PE	TYPE B BEDDING	-
K WK O113	C1	6.73	5.98	250.00	5.94	250.00	KWK0114	PE	TYPE B BEDDING	_
K WK O 1 1 4	C1	6.68	5.94	250.00	5.85	250.00	KWK0115	PE	TYPE B BEDDING	_
KWK0115	C1	6.58	5.85	250.00	5.81	250.00	KWK0116	PE	TYPE B BEDDING	-
KWK0116	C1	6.54	5.81	250.00	5.78	250.00	KWK0117	PE	TYPE B BEDDING	-
KWK0117	C1	6.50	5.78	250.00	5.74	250.00	KWK0118	PE	TYPE B BEDDING	-
K WK O 1 1 8	C1	6.46	5.74 NE	250.00	5.70	250.00	KWK0401	PE	TYPE B BEDDING	_

KAU WA KENG MANHOLE SCHEDULE FOR BRANCH 2

		COVER LEVEL	INLI	ΞΤ		OUTLET		PIPE		
MANHOLE NO.	MANHOLE TYPE	(mPD)	INVERT LEVEL (mPD)	PIPE SIZE (mm) DN	INVERT LEVEL (mPD)	PIPE SIZE (mm) DN	TO MANHOLE	MATERIAL	TYPE OF BEDDING	REMARKS
KWK0201	D1	11.00	9.80	250.00	9.76	250.00	KWK0202	PE	TYPE B BEDDING	_
KWK0202	D1	10.49	9.35	250.00	9.33	250.00	KWK0203	PE	TYPE B BEDDING	_
KWK0203	BACKDROP T3	10.27	8.67	250.00	8.60	250.00	KWK0204	PE	TYPE B BEDDING	WITH BACKDROP
KWK0204	C 1	9.37	8.37	250.00	8.35	250.00	KWK0205	PE	TYPE B BEDDING	_
KWK0205	D1	9.07	7.87	250.00	7.83	250.00	KWK0206	PE	TYPE B BEDDING	_
KWK0206	C 1	8.62	7.62	250.00	7.59	250.00	KWK0207	PE	TYPE B BEDDING	_
KWK0207	C 1	8.40	7.40	250.00	7.35	250.00	KWK0208	PE	TYPE B BEDDING	_
KWK0208	BACKDROP T3	8.09	4.79 S	250.00	4.74	250.00	KWK0501	PE	TYPE B BEDDING	WITH BACKDROP

KAU WA KENG MANHOLE SCHEDULE FOR BRANCH 3

			COVER LEVEL	INLE	T		OUTLET		PIPE		
MA	NHOLE NO.	MANHOLE TYPE	COVER LEVEL (mPD)	INVERT LEVEL (mPD)	PIPE SIZE (mm) DN	INVERT LEVEL (mPD)	PIPE SIZE (mm) DN	TO MANHOLE		TYPE OF BEDDING	REMARKS
	KWK0301	D1	7.77	6.32	250.00	6.21	250.00	KWK0302	PE	TYPE B BEDDING	_
	KWK0302	D1	7.51	6.06	250.00	5.89	250.00	K WK 0303	PE	TYPE B BEDDING	_
	KWK0303	D1	7.31	5.86 W	250.00	5.56	250.00	K WK 0404	PE	TYPE B BEDDING	_

KAU WA KENG MANHOLE SCHEDULE FOR BRANCH 4

		COVER LEVEL	INL	ΕT		OUTLET		PIPE		
MANHOLE NO.	MANHOLE TYPE	(mPD)	INVERT LEVEL (mPD)	PIPE SIZE (mm) DN	INVERT LEVEL (mPD)	PIPE SIZE (mm) DN	TO MANHOLE	MATERIAL	TYPE OF BEDDING	REMARKS
KWK0401	C 1	6.42	5.69	250.00	5.64	250.00	KWK0402	PE	TYPE B BEDDING	_
KWK0402	C 1	6.37	5.47	250.00	5.43	250.00	KWK0403	PE	TYPE B BEDDING	_
KWK0403	C1	6.32	5.32	250.00	5.29	250.00	KWK0404	PE	TYPE B BEDDING	_
KWK0404	C1	6.28	5.28	250.00	5.24	250.00	KWK0405	PE	TYPE B BEDDING	_
KWK0405	C1	6.15	5.24	250.00	5.21	250.00	KWK0406	PE	TYPE B BEDDING	_
KWK0406	C1	6.07	5.21	250.00	5.19	250.00	KWK0407	PE	TYPE B BEDDING	-
KWK0407	C1	6.00	5.19	250.00	5.17	250.00	KWK0408	PE	TYPE B BEDDING	_
KWK0408	C1	5.94	4.94	250.00	4.91	250.00	KWK0409	PE	TYPE B BEDDING	_
KWK0409	C1	5.83	4.91	250.00	4.88	250.00	KWK0410	PE	TYPE B BEDDING	-
KWK0410	C1	5.73	4.88 SE	250.00	4.82	250.00	KWK0501	PE	TYPE B BEDDING	_

KAU WA KENG MANHOLE SCHEDULE FOR BRANCH 5

		COVER LEVEL	INLE	ΕT		OUTLET		PIPE		
MANHOLE NO.	MANHOLE TYPE	(mPD)	INVERT LEVEL (mPD)	PIPE SIZE (mm) DN	INVERT LEVEL (mPD)	PIPE SIZE (mm) DN	TO MANHOLE	MATERIAL	TYPE OF BEDDING	REMARKS
KWK0501	C1	5.57	4.57	250.00	4.48	250.00	KWK0502	PE	TYPE B BEDDING	_
KWK0502	C1	5.47	4.48	250.00	4.40	250.00	K WK 0503	PE	TYPE B BEDDING	_
KWK0503	C1	5.37	4.40	250.00	4.25	250.00	KWK0504	PE	TYPE B BEDDING	_
K WK 0504	C1	5.19	4.19	250.00	4.05	250.00	K WK 0505	PE	TYPE B BEDDING	-
K WK 0505	C1	5.01	4.05	250.00	3.99	250.00	KWK0506	PE	TYPE B BEDDING	-
K WK 0506	C1	4.94	3.99	250.00	3.87	250.00	K WK 0507	PE	TYPE B BEDDING	-
K WK 0507	C1	4.78	3.78	250.00	3.64	250.00	K WK 0508	PE	TYPE B BEDDING	-
K WK 0508	C1	4.60	3.64	250.00	3.56	250.00	K WK 0509	PE	TYPE B BEDDING	_
K WK 0509	C1	4.50	3.50	250.00	3.38	250.00	KWK0510	PE	TYPE B BEDDING	-
KWK0510	C1	4.32	3.38	250.00	3.25	250.00	KWK0511	PE	TYPE B BEDDING	-
K WK 0511	C1	4.13	3.13	250.00	3.04	250.00	KWK0512	PE	TYPE B BEDDING	_
KWK0512	C1	4.00	3.04	250.00	2.85	250.00	K WK 0513	PE	TYPE B BEDDING	_
K WK 0513	D1	3.90	2.85	250.00	2.76	250.00	K WK 0514	PE	TYPE B BEDDING	_
K WK 0514	D1	3.86	2.76	250.00	2.66	250.00	K WK 0515	PE	TYPE B BEDDING	-
KWK0515	D1	3.80	2.66	250.00	2.56	250.00	KWK0516	PE	TYPE B BEDDING	-
K WK 0516	D1	3.75	2.56	250.00	2.45	250.00	K WK 0517	PE	TYPE B BEDDING	_
K WK 0517	D1	3.69	2.45	250.00	2.42	250.00	KWK0518	PE	TYPE B BEDDING	_
KWK0518	D1	3.68	2.42	250.00	2.35	250.00	KWK0519	PE	TYPE B BEDDING	-
KWK0519	D1	3.64	2.35	250.00	2.01	250.00	KWK0520	PE	TYPE B BEDDING	_
KWK0520	D1	3.47	2.01	250.00	1.81	250.00	KWK0521	PE	TYPE B BEDDING	-
KWK0521	E 1	3.36	1.81	250.00	1.68	250.00	EXISTING	PE	TYPE B BEDDING	_

KAU WA KENG MANHOLE SCHEDULE FOR BRANCH 6

		COVER LEVEL	INLE	ΞT		OUTLET		PIPE		
MANHOLE NO.	MANHOLE TYPE	(mPD)	INVERT LEVEL (mPD)	PIPE SIZE (mm) DN	INVERT LEVEL (mPD)	PIPE SIZE (mm) DN	TO MANHOLE	MATERIAL	TYPE OF BEDDING	REMARKS
KWK0601	E1	10.50	8.70	250.00	8.65	250.00	KWK0602	PE	TYPE B BEDDING	_
K WK 0602	BACKDROP T3	9.38	7.98	250.00	7.95	250.00	KWK0603	PE	TYPE B BEDDING	WITH BACKDROP
KWK0603	BACKDROP T3	8.74	7.14	250.00	7.10	250.00	KWK0604	PE	TYPE B BEDDING	WITH BACKDROP
K WK 0604	BACKDROP T3	7.85	5.75 SW	250.00	5.69	250.00	KWK0401	PE	TYPE B BEDDING	WITH BACKDROP

KAU WA KENG MANHOLE SCHEDULE FOR BRANCH 7

		COVER LEVEL	INL	ΞT		OUTLET		PIPE		
MANHOLE NO.	MANHOLE TYPE	(mPD)	INVERT LEVEL (mPD)	PIPE SIZE (mm) DN	INVERT LEVEL (mPD)	PIPE SIZE (mm) DN	TO MANHOLE	MATERIAL	TYPE OF BEDDING	REMARKS
KWK0701	C1	10.50	9.50	250.00	9.47	250.00	KWK0702	PE	TYPE B BEDDING	_
KWK0702	C1	10.40	9.47	250.00	9.43	250.00	KWK0703	PE	TYPE B BEDDING	_
KWK0703	C1	10.28	9.43	250.00	9.40	250.00	KWK0704	PE	TYPE B BEDDING	_
K WK 0704	C1	10.16	9.40 E	250.00	9.35	250.00	KWK0202	PE	TYPE B BEDDING	-

KAU WA KENG MANHOLE SCHEDULE FOR BRANCH 8

		COVER LEVEL		INLE			OUTLET		PIPE		
MANHOLE NO.	MANHOLE TYPE	(mPD)	INVERT LEV (mPD)	VEL	PIPE SIZE (mm) DN	INVERT LEVEL (mPD)	PIPE SIZE (mm) DN	TO MANHOLE	MATERIAL	TYPE OF BEDDING	REMARKS
K WK 0801	E1	11.10	9.50	W	250.00	9.48	250.00	KWK0203	PE	TYPE B BEDDING	_

KAU WA KENG MANHOLE SCHEDULE FOR BRANCH 9

		COVER LEVEL	INL	ΕT		OUTLET		DIDE		
MANHOLE NO.	MANHOLE TYPE	(mPD)	INVERT LEVEL (mPD)	PIPE SIZE (mm) DN	INVERT LEVEL (mPD)	PIPE SIZE (mm) DN	TO MANHOLE	PIPE MATERIAL	TYPE OF BEDDING	REMARKS
KWK0901	C1	9.45	8.65	250.00	8.61	250.00	KWK0902	PE	TYPE B BEDDING	_
KWK0902	C 1	9.41	8.61 SE	250.00	8.57	250.00	KWK0204	PE	TYPE B BEDDING	_

KAU WA KENG MANHOLE SCHEDULE FOR BRANCH 10

		COVER LEVEL	INLE	T		OUTLET		DIDE		
MANHOLE NO.	MANHOLE TYPE	(mPD)	INVERT LEVEL (mPD)	PIPE SIZE (mm) DN	INVERT LEVEL (mPD)	PIPE SIZE (mm) DN	TO MANHOLE	PIPE MATERIAL	TYPE OF BEDDING	REMARKS
K WK 1001	C1	9.50	8.60	250.00	8.57	250.00	K WK 1002	PE	TYPE B BEDDING	-
K WK 1002	C1	9.29	8.29	250.00	8.25	250.00	K WK 1003	PE	TYPE B BEDDING	_
K WK 1003	D1	9.04	7.94 SE	250.00	7.87	250.00	KWK0206	PE	TYPE B BEDDING	-

KAU WA KENG MANHOLE SCHEDULE FOR BRANCH 11

		COVER LEVEL	INLE	ΕT		OUTLET		DIDE		
MANHOLE NO.	MANHOLE TYPE	(mPD)	INVERT LEVEL (mPD)	PIPE SIZE (mm) DN	INVERT LEVEL (mPD)	PIPE SIZE (mm) DN	TO MANHOLE	PIPE MATERIAL	TYPE OF BEDDING	REMARKS
K WK 1101	E 1	11.20	9.40	250.00	9.36	250.00	KWK1102	PE	TYPE B BEDDING	_
KWK1102	BACKDROP T3	10.22	8.62	250.00	8.58	250.00	KWK1103	PE	TYPE B BEDDING	WITH BACKDROP
K WK 1103	BACKDROP T3	9.36	7.86 NW	250.00	7.83	250.00	KWK0206	PE	TYPE B BEDDING	WITH BACKDROP

KAU WA KENG MANHOLE SCHEDULE FOR BRANCH 12

		COVER LEVEL	INL	ΞT		OUTLET		PIPE		
MANHOLE NO.	MANHOLE TYPE	(mPD)	INVERT LEVEL (mPD)	PIPE SIZE (mm) DN	INVERT LEVEL (mPD)	PIPE SIZE (mm) DN	TO MANHOLE	MATERIAL	TYPE OF BEDDING	REMARKS
KWK1201	C1	10.20	8.65	250.00	8.61	250.00	KWK0902	PE	TYPE B BEDDING	_
KWK1202	BACKDROP T3	9.51	8.61 N	250.00	8.57	250.00	KWK0204	PE	TYPE B BEDDING	WITH BACKDROP

KAU WA KENG MANHOLE SCHEDULE FOR BRANCH 13

MANUOLE NO		COVER LEVEL	INLET			OUTLET		PIPE			
MANHOLE NO.	ANHOLE NO. MANHOLE TYPE		INVERT LEVEL (mPD)	PIPE SIZE (mm) DN	INVERT LEVEL (mPD)	PIPE SIZE (mm) DN	TO MANHOLE	MATERIAL	TYPE OF BEDDING	REMARKS	
KWK1301	E1	10.52	8.12	250.00	8.08	250.00	KWK1302	PE	TYPE B BEDDING	_	
K WK 1302	BACKDROP T3	8.88	6.78	250.00	6.75	250.00	K WK 1303	PE	TYPE B BEDDING	WITH BACKDROP	
K WK 1303	BACKDROP T3	7.49	4.69 W	250.00	4.64	250.00	KWK0502	PE	TYPE B BEDDING	WITH BACKDROP	

KAU WA KENG MANHOLE SCHEDULE FOR BRANCH 14

MANHOLE NO. MANH		COVER LEVEL	INLET			OUTLET		PIPE		
	MANHOLE TYPE	(mPD)	INVERT LEVE (mPD)	L PIPE SIZE (mm) DN	INVERT LEVEL (mPD)	PIPE SIZE (mm) DN	TO MANHOLE	MATERIAL	TYPE OF BEDDING	REMARKS
KWK1401	D1	6.00	4.60	E 250.00	4.54	250.00	KWK0503	PE	TYPE B BEDDING	_

KAU WA KENG MANHOLE SCHEDULE FOR BRANCH 15

		MANHOLE TYPE COVER LEVEL	INLET			OUTLET		PIPE	TYPE OF BEDDING	REMARKS
MANHOLE NO. MANHOLE TYPE	(mPD)	INVERT LEVEL (mPD)	PIPE SIZE (mm) DN	INVERT LEVEL (mPD)	PIPE SIZE (mm) DN	TO MANHOLE	PIPE MATERIAL			
KWK1501	D1	6.00	4.54	250.00	4.52	250.00	KWK1502	PE	TYPE B BEDDING	_
KWK1502	D1	5.73	4.43 SE	250.00	4.39	250.00	KWK0504	PE	TYPE B BEDDING	-

© Copyright by Binnies Hong Kong Limited

NOTES:

- 1. ALL LEVELS ARE METERS ABOVE P.D.H.K.
- 2. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS OTHERWISE SPECIFIED.
- 3. PE DENOTES POLYETHYLENE.
- 4. B DENOTES CLASS B BEDDING IN ACCORDANCE WITH DSD STANDARD DRAWING NO. DS1048.
- 5. THIS DRAWING SHALL BE READ IN CONJUNCTION WITH DRG. NO. 382813/BIN/KWK/SR/001.

Revision Date Description Initial

Designed Checked Drawn Checked
Initial SYW CT SZ CC

Date 04/22 04/22 04/22 04/22

Approved

Contract no.

DC/2022/06

Contract title

VILLAGE SEWERAGE IN MUK WU, LO WAI, CHUEN LUNG AND KAU WA KENG OLD VILLAGE

Drawing title

KAU WA KENG OLD VILLAGE -PROPOSED MANHOLE SCHEDULE

Drawing no.

382813/BIN/KWK/SR/002

Scale

N.T.S. 香港特别行政區政府渠務署

Revision





工程計劃項目編號 4391DS 九龍西部及荃灣鄉村污水收集系統一第 2 期

1. 目的

本文件目的是簡介工程計劃項目編號 4391DS「九龍西部及荃灣鄉村污水 收集系統一第 2 期」(下稱「工程」),當中包括葵青區九華徑新村及長坑 路怡菁山莊下游建造新污水渠,並就有關工程諮詢各委員的意見,希望委 員支持進行此項工程。

2. 背景資料

環境保護署於 2010 年完成《西九龍及荃灣污水收集整體計劃檢討》,檢討建議在九龍西部及荃灣區內某些未有公共污水收集系統的鄉村/地區,提供鄉村污水收集系統,將所產生的污水收集並輸送至污水處理廠處理,以改善鄉村/地區內的衛生狀況和下游水體的水質。

整項鄉村污水收集系統工程共分兩期進行。 第 1 期工程已於 2020 年開展,預期於 2023 年年底完成。 就第 2 期工程我們亦已於 2017 年 6 月諮詢荃灣鄉事委員會, 並獲得支持。 我們正就第 2 期工程進行規劃及設計。

3. 工程範圍

整個項目第 2 期工程包括在荃灣區七個鄉村/地區(即橫龍、新村、三疊潭、和宜合、上葵涌、芙蓉山、漢民寮屋區)、葵青區兩個鄉村/地區(即九華徑新村、長坑路怡菁山莊下游)及深水埗區青山公路段建造總共約 9 公里長的新污水渠,將相關鄉村/地區所產生的污水收集並輸送至現有的污水系統。

當中我們擬於葵青區內九華徑新村建造長約 1.4 公里長的污水渠,及於長坑路怡菁山莊下游建造約 1.2 公里長的污水渠。 有關葵青區的擬議工程的位置平面圖載於**附件一**。

4. 施工計劃

我們會為本工程完成法定程序後,啟動申請撥款程序,一旦獲立法會批准撥款,我們預計整項第2期工程需時約6年完成建造工程。

5. 環境及交通影響評估

5.1 環境影響評估

我們對本工程已進行初步環境評審,所得結論是工程在建造時對環境所造成的影響輕微。 在施工期間,我們會實施相應的環境緩解措施,以儘量減低工程對環境帶來的影響。

為減低噪音對附近居民的影響,我們會在有需要的地方實施以下緩解措施:

- 使用流動隔音屏障:
- 使用配有滅音裝備的機械;及
- 適當地計劃工序,例如安排只在非繁忙時段進行噪音較大如 開掘路面等工作。

為減少挖土工序及處理填土物料所產生的泥塵,我們會在施工期間實施以下緩解措施:

- 經常在工地內灑水以減少在空氣中飄浮的塵埃; 及
- 用帆布覆蓋在運送途中或儲存的泥土。

整體而言,我們會妥善實施上述的環境緩解措施,並在施工期間進行密切的監察及工地巡察,相信工程對環境的影響將會很輕微。

5.2 交通影響評估

在施工期間,我們會提供足夠的臨時行車路及行人徑,以維持交通 暢順。施工區域會被小心分隔,確保道路使用者安全。 在非施工期 間時,已開掘的路面會被妥善覆蓋以維持交通正常運作。 而工程完 成後,我們會重鋪因本工程而受影響的現有車道及行人通道,確保 行車及行人通道回復正常。 工程進行期間,承建商會成立交通管理 聯絡小組,並會向附近居民提供聯絡電話,以保持緊密聯繫及在有 需要時處理有關工程的查詢和投訴。

6. 徵收土地

為了減低對居民的影響,本工程會儘量減少徵收私人土地。 在規劃及設計 污水系統走綫時,我們已儘量將擬建的污水系統建造於政府土地範圍內。 但因受到地形及環境的限制,在無可避免的情況下,我們亦有需要徵收部 分私人土地以建造完整的污水系統。

於長坑路至青山公路工程將不涉及私人土地。 至於九華徑新村,在過往與 荃灣區鄉事委員會及九華徑新村村代表諮詢時,我們已提供初步污水渠走 綫圖讓相關人士參考,並與村代表進行實地視察。 於 2021 年 1 月,我們 就土地徵用方案再向地政處諮詢意見,在可行的情況下已作出相應修改。 我們會繼續諮詢村代表、村民及地政處,不時檢視情況及因應實際需要而 對污水渠走綫作出修正,在可行的情況下儘量配合各方面的需要。

7. 公眾參與

施工前,我們再會諮詢受影響的市民,提供有關工程的資料,並與他們商 討有關的施工安排,以減低對公眾帶來的影響。


施工期間,我們會設立熱線電話,方便市民查詢,並收集公眾對本工程的意見。


8. 諮詢


歡迎各委員就本諮詢文件提出意見。在獲得委員的支持後,我們會盡快完成工程的詳細設計及開展工程。

渠務署

2021年4月








	٦	
	\dashv	
"	\dashv	
netre	╛	
Σ		
	٦	

MANHOLE	SCHEDULE								0 1 1		
		Approx		Inl	et Pipe				Outlet P	ipe	
Manhole Number	MH type	Ground Level (mPD)	Invert Level (mPD)	Size (mm)	Pipe Material	From manhol e no.	Invert Level (mPD)	Size (mm)	Pipe Material	To manhole no.	Bedding Type
WK1.1.1	El	17.4	-	-	-	-	15.65	225	HDPE	WK1.1.2	Class B
WK1.1.2	E1	17.3	15.58	225	HDPE	WK1.1.1	15.58	225	HDPE	WK1.1.3	Class B
WK1.1.3	D1	17	15.52	225	HDPE	WK1.1.2	15.52	225	HDPE	WK1.1.4	Class B
WK1.1.4	El	17.5	15.84 15.29	225 225	HDPE HDPE	WK1.4.2 WK1.1.3	15.29	225	HDPE	WK1.1.5	Class B
WK1.1.5	D1	9	8.10	225	HDPE	WK1.1.4	7.80	225	HDPE	WK1.1.6	Class B
WK1.1.6	C1	8.5	7.55	225	HDPE	WK1.1.5	7.55	225	HDPE	WK1.1.7	Class B
WK1.1.7	D1	7.85	6.89	225 225	HDPE HDPE	WK1.7.13 WK1.1.6	6.83	225	HDPE	WK1.1.8	Class B
WK1.1.8	E1	7.8	6.77	225	HDPE	WK1.14.2	6.26	225	HDPE	WK1.1.9	Class B
WK1.1.8	EI	7.8	6.26	225	HDPE	WK1.14.2 WK1.1.7	6.26	225	HDPE	WK1.1.9	Class B
WK1.1.9	E1	7.55	6.09 5.82	225 225	HDPE HDPE	WK1.15.1 WK1.1.8	5.82	225	HDPE	WK1.1.10	Class B
WK1.1.10	El	7.5	5.99 6.26 5.69	225 225 225 225 225	HDPE HDPE HDPE	WK1.17.1 WK1.16.1 WK1.6.18 WK1.1.9	5.69	225	HDPE	WK1.1.11	Class B
WK1.1.11	C1	6.3	5.44	225	HDPE	WK1.1.10	5.44	225	HDPE	WK1.1.12	Class B
WK1.1.12	D1	6	4.79	225	HDPE	WK1.19.3	4.79	225	HDPE	WK1.1.13	Class B
WK1.1.13	E1	5.9	4.87 4.31 4.72	225 225 225	HDPE HDPE HDPE	WK1.1.11 WK1.22.2 WK1.1.12	4.31	225	HDPE	WK1.1.14	Class B
WK1.1.14	D1	5.75	4.44	225		WK1.1.12	4.27	225	HDPE	WW 1 1 15	Class P
WK1.1.14	DI	3.73	4.44	225	HDPE HDPE	WK1.24.9 WK1.1.13	4.27	223	HDFE	WK1.1.15	Class B
WK1.1.15	E1	5.6	4.00 4.25	225 225	HDPE HDPE	WK1.25.2 WK1.1.14	4.00	225	HDPE	WK1.1.16	Class B
WK1.1.16	E1	5.5	3.97	225	HDPE	WK1.1.15	3.97	225	HDPE	WK1.1.17	Class B
WK1.1.17	D1	5.1	4.02 3.92	225 225	HDPE HDPE	WK1.26.1 WK1.1.16	3.92	225	HDPE	WK1.1.18	Class B
WK1.1.18	D1	5	4.05 3.88	225 225	HDPE HDPE	WK1.27.1 WK1.1.17	3.88	225	HDPE	WK1.1.19	Class B
WK1.1.19	D1	4.9	3.67	225	HDPE	WK1.28.3	3.67	225	HDPE	WK1.1.20	Class B
WK1.1.20	D1	5	3.82	225	HDPE HDPE	WK1.1.18 WK1.30.3	3.62	225	HDPE	WK1.1.21	Class B
WK1.1.21	D1	4.6	3.62	225	HDPE HDPE	WK1.1.19 WK1.1.20	3.54	225	HDPE	WK1.1.22	Class B
WK1.1.22	C1	4.4	3.46	225	HDPE	WK1.1.21	3.46	225	HDPE	WK1.1.23	Class B
WK1.1.23	C1	4	3.11	225 225	HDPE HDPE	WK1.31.6 WK1.1.22	3.10	225	HDPE	WK1.1.24	Class B
WK1.1.24	E1	5	3.07	225	HDPE	WK1.1.23	3.07	225	HDPE	WK1.1.25	Class B
WK1.1.25	E1	4.9	3.05	225	HDPE	WK1.1.24	3.05	225	HDPE	WK1.1.26	Class B
WK1.1.26	D1	4	2.98	225	HDPE	WK1.1.25	2.98	225	HDPE	WK1.1.27	Class B
WK1.1.27	D1	4	2.66 2.77	225 225	HDPE HDPE	WK1.34.11 WK1.1.26	2.66	225	HDPE	FMH4009599	Class B
WK1.4.1	E1	24	-	-	-	-	22.35	225	HDPE	WK1.4.2	Class B
WK1.4.2	E1	22	20.34	225	HDPE	WK1.4.1	20.34	225	HDPE	WK1.1.4	Class B
WK1.4.2	D1	30	-	-	-		28.55	225	HDPE	WK1.6.2	Class B
WK1.6.2	E1	30	28.33	225	HDPE	WK1.6.1	28.33	225	HDPE	WK1.6.3	Class B
WK1.6.3	E1	30	28.26	225	HDPE	WK1.6.2	28.26	225	HDPE	WK1.6.4	Class B
WK1.6.4	E1	30	27.97	225	HDPE	WK1.6.3	27.97	225	HDPE	WK1.6.5	Class B

				Inlet Pipe Outlet Pipe					DO NOT Outlet Pipe				
Manhole Number	MH type	Approx Ground Level (mPD)	Invert Level (mPD)	Size (mm)	Pipe Material	From manhol e no.	Invert Level (mPD)	Size (mm)	Pipe Material	To manhole no.	Bedding Type		
WK1.6.5	El	30	27.89	225	HDPE	WK1.6.4	27.89	225	HDPE	WK1.6.6	Class B		
WK1.6.6	D1	27	26.15	225	HDPE	WK1.6.5	25.85	225	HDPE	WK1.6.7	Class B		
WK1.6.7	E1	27	25.79	225	HDPE	WK1.6.6	25.49	225	HDPE	WK1.6.8	Class B		
WK1.6.8	D1	21.5	20.51	225	HDPE	WK1.6.7	20.21	225	HDPE	WK1.6.9	Class B		
WK1.6.9	E1	20	18.76	225	HDPE	WK1.6.8	18.46	225	HDPE	WK1.6.10	Class B		
WK1.6.10	El	19.9	18.34	225	HDPE	WK1.6.9	18.04	225	HDPE	WK1.6.11	Class B		
WK1.6.11	D1	17	15.99	225	HDPE	WK1.6.10	15.69	225	HDPE	WK1.6.12	Class B		
WK1.6.12	D1	15.5	14.60	225	HDPE	WK1.6.11	14.30	225	HDPE	WK1.6.13	Class B		
WK1.6.13	D1	13.42	12.49	225	HDPE	WK1.6.12	12.09	225	HDPE	WK1.6.14	Class B		
WK1.6.14	D1	12.56	11.59	225	HDPE	WK1.6.13	11.19	225	HDPE	WK1.6.15	Class B		
WK1.6.15	E1	10.88	9.77	225	HDPE	WK1.6.14	9.37	225	HDPE	WK1.6.16	Class B		
WK1.6.16	D1	8.96	8.05	225	HDPE	WK1.6.15	7.65	225	HDPE	WK1.6.17	Class B		
WK1.6.17	E1	8.47	7.39	225	HDPE	WK1.6.16	6.89	225	HDPE	WK1.6.18	Class B		
WK1.6.18	C1	7.39	6.50	225	HDPE	WK1.6.17	6.50	225	HDPE	WK1.1.10	Class B		
WK1.7.1	C1	27.55	-	-	-	-	26.70	225	HDPE	WK1.7.2	Class B		
WK1.7.2	C1	27.5	26.54	225	HDPE	WK1.7.1	26.54	225	HDPE	WK1.7.3	Class B		
WK1.7.3	D1	27.65	26.25	225	HDPE	WK1.7.2	26.25	225	HDPE	WK1.7.4	Class B		
WK1.7.4	F1	28.82	26.06 26.00	225 225	HDPE HDPE	WK1.8.1 WK1.7.3	25.50	225	HDPE	WK1.7.6	Class B		
WK1.7.6	E1	23.45	21.49 21.98	225 225	HDPE HDPE	WK1.9.1 WK1.7.4	21.49	225	HDPE	WK1.7.9	Class B		
WK1.7.9	D1	17.6	16.45 16.60	225 225	HDPE HDPE	WK1.10.1 WK1.7.6	16.43	225	HDPE	WK1.7.10	Class B		
			16.43	225	HDPE	WK1.11.3							
WK1.7.10	D1	17.5	16.35	225	HDPE	WK1.7.9	16.35	225	HDPE	WK1.7.11	Class B		
WK1.7.11	C1	11.6	10.64	225	HDPE	WK1.7.10	10.64	225	HDPE	WK1.7.12	Class B		
WK1.7.12	D1	11.7	10.73 10.51 10.84	225 225 225	HDPE HDPE HDPE	WK1.12.1 WK1.7.11 WK1.13.1	10.51	225	HDPE	WK1.7.13	Class B		
WK1.7.13	D1	11.7	10.41	225	HDPE	WK1.7.12	10.41	225	HDPE	WK1.1.7	Class B		
WK1.8.1	D1	27.5	-	-	-	-	26.25	225	HDPE	WK1.7.4	Class B		
WK1.9.1	C1	22.4	-	-	-	-	21.55	225	HDPE	WK1.7.6	Class B		
WK1.10.1	C1	17.5	-	-	-	-	16.65	225	HDPE	WK1.7.9	Class B		
WK1.11.1	D1	18.3	-	-	-	-	17.15	225	HDPE	WK1.11.2	Class B		
WK1.11.2	D1	18.33	16.89	225	HDPE	WK1.11.1	16.89	225	HDPE	WK1.11.3	Class B		
WK1.11.3	C1	17.55	16.55	225	HDPE	WK1.11.2	16.55	225	HDPE	WK1.7.9	Class B		
WK1.12.1	C1	11.64	-	-	-	-	10.78	225	HDPE	WK1.7.12	Class B		
WK1.13.1	C1	11.8	-	-	-	-	10.94	225	HDPE	WK1.7.12	Class B		
WK1.14.1	D1	12	-	-	-	-	10.55	225	HDPE	WK1.14.2	Class B		
WK1.14.1	D1	11.26	10.23	225	HDPE	WK1.14.1	10.23	225	HDPE	WK1.14.2	Class B		
WK1.14.2	D1	11.5	-	-	- IIDI'E	- WK1.14.1	10.23	225	HDPE	WK1.1.8	Class B		
WK1.15.1	Dl	7.5	-	-	-	-	6.05	225	HDPE	WK1.1.9	Class B		
WK1.16.1	D1	8		<u> </u>			6.55		HDPE	WK1.1.10	Class B		
			-	_	-	-		225					
WK1.18.1 WK1.19.1	C1 D1	9.26	-	-	-	-	7.59 8.01	225	HDPE	WK1.19.3 WK1.19.2	Class B Class B		

DO NOT SCALE NOTES:

- 1. FOR BEDDING TYPE: a) CLASS B : CLASS BEDDING DETAILS REFER TO DSD STANDARD DRAWING NO. DS104B.
- b) TYPE 1: TYPE I CONCRETE SURROUNG DETAILS REFER TO DSD STANDARD DRAWING NO. DS1049.
- 2. DETAILS OF MANHOLES AND COVERS REFER TO DSD STANDARD DRAWINGS UNLESS OTHERWISE SPCICIED.



DESIGN

Member of the SNC-Lavalin Group



淨化海港計劃部

Harbour Area Treatment Scheme Division

CE25/2013 (DS)
WEST KOWLOON AND TSUEN WAN
VILLAGE SEWERAGE AND NORTH
DISTRICT SEWERAGE - INVESTIGATION,
DESIGN AND CONSTRUCTION

MANHOLE SCHEDULE -KAU WA KENG SAN TSUEN (SHEET 1)


T	Scale	Designed	Drawn	Checked	Authorised
+	1:500	SS	AC	LLL	KP
	Original Size	Date APR 2022			
	Drawing Number	Revision			
	512	-			

MANHOLE SCHEDULE											
		Approx		Inl	et Pipe				Outlet P	ipe 	
Manhole Number	MH type	Ground Level (mPD)	Invert Level (mPD)	Size (mm)	Pipe Material	From manhol e no.	Invert Level (mPD)	Size (mm)	Pipe Material	To manhole no.	Bedding Type
WK1.19.2	D1	9	7.61	225	HDPE	WK1.19.1	7.61	225	HDPE	WK1.19.3	Class B
WK1.19.3	C1	5.7	4.82 4.82	225 225	HDPE HDPE	WK1.18.1 WK1.19.2	4.82	225	HDPE	WK1.1.12	Class B
WK1.21.1	D1	8	-	-	-	-	6.75	225	HDPE	WK1.22.2	Class B
WK1.22.1	D1	5.8	-	-	-	-	4.55	225	HDPE	WK1.22.2	Class B
WK1.22.2	D1	5.8	4.80 4.48	225 225	HDPE HDPE	WK1.21.1 WK1.22.1	4.48	225	HDPE	WK1.1.13	Class B
WK1.23.1	D1	12.22	-	-	-	-	10.97	225	HDPE	WK1.24.6	Class B
WK1.24.1	E1	24	-	-	-	-	22.35	225	HDPE	WK1.24.2	Class B
WK1.24.2	D1	23.5	22.25	225	HDPE	WK1.24.1	22.25	225	HDPE	WK1.24.3	Class B
WK1.24.3	D1	23.25	21.94	225	HDPE	WK1.24.2	21.94	225	HDPE	WK1.24.4	Class B
WK1.24.4	D1	17.86	16.74	225	HDPE	WK1.24.3	16.74	225	HDPE	WK1.24.5	Class B
WK1.24.5	D1	16	14.88	225	HDPE	WK1.24.4	14.88	225	HDPE	WK1.24.6	Class B
WK1.24.6	D1	11.7	10.81	225	HDPE	WK1.23.1	10.57	225	HDPE	WK1.24.7	Class B
WK1.24.7	D1	10.15	9.02	225	HDPE HDPE	WK1.24.5 WK1.24.6	9.02	225	HDPE	WK1.24.8	Class B
WK1.24.8	D1	10	8.86	225	HDPE	WK1.24.7	8.86	225	HDPE	WK1.24.9	Class B
WK1.24.9	D1	5.65	4.46	225	HDPE	WK1.24.8	4.46	225	HDPE	WK1.1.14	Class B
WK1.25.1	C1	5	-	-	-	-	4.14	225	HDPE	WK1.25.2	Class B
WK1.25.2	C1	5	4.09	225	HDPE	WK1.25.1	4.09	225	HDPE	WK1.1.15	Class B
WK1.26.1	C1	8.2	-	-	-	-	7.34	225	HDPE	WK1.1.17	Class B
WK1.27.1	D1	5.45	-	-	-	-	4.10	225	HDPE	WK1.1.18	Class B
WK1.28.1	C1	4.7	-	-	-	-	3.85	225	HDPE	WK1.28.2	Class B
WK1.28.2	C1	4.7	3.80	225	HDPE	WK1.28.1	3.80	225	HDPE	WK1.28.3	Class B
WK1.28.3	C1	4.77	3.77	225	HDPE	WK1.28.2	3.77	225	HDPE	WK1.1.19	Class B
WK1.29.1	C1	8	-	-	-	-	7.14	225	HDPE	WK1.29.2	Class B
WK1.29.2	E1	9	7.09	225	HDPE	WK1.29.1	7.09	225	HDPE	WK1.29.3	Class B
WK1.29.3	E1	9.88	7.05	225	HDPE	WK1.29.2	7.05	225	HDPE	WK1.29.4	Class B
WK1.29.4	E1	9.88	7.04	225	HDPE	WK1.29.3	7.04	225	HDPE	WK1.30.3	Class B
WK1.30.1	E1	13	-	-	-	-	11.25	225	HDPE	WK1.30.1a	Class B
WK1.30.1a	D1	12	11.09	225	HDPE	WK1.30.1	10.69	225	HDPE	WK1.30.2	Class B
WK1.30.2	C1	10.5	9.56	225	HDPE	WK1.30.1a	9.56	225	HDPE	WK1.30.3	Class B
WK1.30.3	C1	8	7.02 7.15	225 225	HDPE HDPE	WK1.29.4 WK1.30.2	7.02	225	HDPE	WK1.1.20	Class B
WK1.31.1	C1	12	-	-	-	-	11.14	225	HDPE	WK1.31.2	Class B
WK1.31.2	C1	12	11.13	225	HDPE	WK1.31.1	11.13	225	HDPE	WK1.31.3	Class B
WK1.31.3	C1	9	8.14	225	HDPE	WK1.31.2	8.14	225	HDPE	WK1.31.4	Class B
WK1.31.4	C1	6	5.12	225	HDPE	WK1.31.3	5.12	225	HDPE	WK1.31.5	Class B
WK1.31.5	C1	5	4.15	225	HDPE	WK1.31.4	4.15	225	HDPE	WK1.31.6	Class B
WK1.31.6	E1	5.9	4.13	225	HDPE	WK1.31.5	1.13	225	HDPE	WK1.1.23	Class B
WK1.33.1	C1	13.5	-	-	-	-	12.64	225	HDPE	WK1.34.4	Class B
WK1.34.1	E1	14.47	-	-	-	-	12.42	225	HDPE	WK1.34.2	Class B
WK1.34.2	E1	13.5	12.59 11.85	225 225	HDPE HDPE	WK1.37.6 WK1.34.1	11.55	225	HDPE	WK1.34.3	Class B

				Inl	et Pipe		Outlet Pipe				
Manhole Number	MH type	Approx Ground Level (mPD)	Invert Level (mPD)	Size (mm)	Pipe Material	From manhol e no.	Invert Level (mPD)	Size (mm)	Pipe Material	To manhole no.	Bedding Type
WK1.34.3	C1	11	10.13	225	HDPE	WK1.34.2	10.13	225	HDPE	WK1.34.4	Class B
WK1.34.4	D1	7.18	6.19 6.13	225 225	HDPE HDPE	WK1.33.1 WK1.34.3	6.13	225	HDPE	WK1.34.5	Class B
WIIZ1 24.5	D1	7	6.12	225	HDPE	WK1.35.4	5.74	225	HDDE	WW.1 24.6	Cl. P.
WK1.34.5	D1	7	5.94	225	HDPE	WK1.34.4	5.74	225	HDPE	WK1.34.6	Class B
WK1.34.6	E1	7	5.54 4.93	225	HDPE	WK1.34.5	5.24	225	HDPE	WK1.34.7	Class B
WK1.34.7 WK1.34.8	E1	6.5	4.93	225	HDPE HDPE	WK1.34.6 WK1.34.7	4.63	225	HDPE	WK1.34.8 WK1.34.9	Class B
WK1.34.9	E1	5.18	3.91	225	HDPE	WK1.34.8	3.61	225	HDPE	WK1.34.10	Class B
WK1.34.10	D1	4.5	3.51	225	HDPE	WK1.34.9	3.21	225	HDPE	WK1.34.11	Class B
WK1.34.11	D1	3.97	3.09	225	HDPE	WK1.34.10	2.79	225	HDPE	WK1.1.27	Class B
WK1.35.1	C1	7.18	-	-	-	-	6.32	225	HDPE	WK1.35.2	Class B
WK1.35.2	E1	8.2	6.28	225	HDPE	WK1.35.1	6.28	225	HDPE	WK1.35.3	Class B
WK1.35.3	E1	8	6.24	225	HDPE	WK1.35.2	6.24	225	HDPE	WK1.35.4	Class B
WK1.35.4	E1	7.94	6.21	225	HDPE	WK1.35.3	6.21	225	HDPE	WK1.34.4	Class B
WK1.36.1	E1	17.44	-	-	-	-	15.49	225	HDPE	WK1.36.2	Class B
WK1.36.2	El	16.5	15.37	225	HDPE	WK1.36.1	14.87	225	HDPE	WK1.37.4	Class B
WK1.37.1	E1	16.1	-	-	-	-	14.35	225	HDPE	WK1.37.2	Class B
WK1.37.2	E1	16.1	14.22	225	HDPE	WK1.37.1	14.22	225	HDPE	WK1.37.3	Class B
WK1.37.3	El	15.65	14.04	225	HDPE	WK1.37.2	14.04	225	HDPE	WK1.37.4	Class B
WK1.37.4	E1	16.1	14.55 13.96	225 225	HDPE HDPE	WK1.36.2 WK1.37.3	13.96	225	HDPE	WK1.37.6	Class B
WK1.37.6	El	15	13.05	225	HDPE	WK1.37.4	13.05	225	HDPE	WK1.34.2	Class B

DO NOT SCALE NOTES:

- FOR BEDDING TYPE:
 a) CLASS B: CLASS BEDDING
 DETAILS REFER TO DSD STANDARD DRAWING NO. DS104B.
- b) TYPE I : TYPE I CONCRETE SURROUNG DETAILS REFER TO DSD STANDARD DRAWING NO. DS1049.
- DETAILS OF MANHOLES AND COVERS REFER TO DSD STANDARD DRAWINGS UNLESS OTHERWISE SPCICIED.



DESIGN

Member of the SNC-Lavalin Group



淨化海港計劃部

Harbour Area Treatment Scheme Division

CE25/2013 (DS)
WEST KOWLOON AND TSUEN WAN
VILLAGE SEWERAGE AND NORTH
DISTRICT SEWERAGE - INVESTIGATION,
DESIGN AND CONSTRUCTION

MANHOLE SCHEDULE -KAU WA KENG SAN TSUEN (SHEET 2)

Original Size Date Date Date Date Date Date Date A1 APR 2022 APR 2022 APR 2022 APR 2022 APR 2022	Scale	Designed	Drawn	Checked	Authorised
	1:500	SS	AC	LLL	KP
					Date APR 2022

Appendix D

Layout of Baseline Sewer Network Appendix D Site boundary of 4391DS Proposed village sewerage in Kau Wa Keng San Tsuen under PWP No. 4391DS. Site boundary of 4358DS Proposed village sewerage in Kau Wa Keng Old Village under PWP No. 4358DS. Proposed sewer upgrading works along Lei King Hill Road under PWP No. 4389DS. Legend **Existing DWFI Existing Sewer Manhole Existing Sewer** Phase of the Proposed CDA Development Boundary of Village Swerage Project Planned Public Sewerage Works (Trunk Only)

Appendix E

Layout of Proposed Sewer Network

Appendix E2 - Scenario 3 (Fully Developed CDA) Proposed 225mm sewer Legend DWFI No. SDH4000980 to be reprovided Proposed CDA **Existing KWKSPS Existing Sewer Manhole** DWFI No. SDH4000981 to be reprovided **Existing Sewer Exisitng DWFI** Existing DWFI to be Demolished DWFI to be Re-provided Buildings in CDA Existing sewer manhole No. FMH4009607 ××× Planned Sewer to be Demolished Planned Sewer to be Retained Proposed Village Sewerage Diversion Existing sewer manhole No. FMH4009599 Proposed SPS for the CDA

Appendix F

Population and Flow under Different Scenario

Appendix F - Estimation of Population and Sewage Flow of the under different Scenarios

Part 1 - Population and Sewage in Villages and CDA Development

Villages

Name of Village	Section	No. of Village House	Projected Population ⁽¹⁾	Estimated Population by Section ⁽²⁾	Projected ADWF ⁽³⁾ (m3/day)	Projected ADWF ⁽²⁾ in Scenario 1&2 (m3/day)	Projected ADWF in Scenario 3 (m3/day)
Kau Wa Keng Old	Inside CDA Development	144	1964	1,563	1115.74	888	0
Village	Outside CDA Development	37	1904	401	1113.74	228	228
Kau Wa Keng San	Inside CDA Development	7	971	60	418.90	26	0
Tsuen	Outside CDA Development	107	9/1	911	418.90	393	393
		•	•	•	Total	1535	621

⁽¹⁾ Data from design population under PWP No. 4358DS and 4391DS.

⁽²⁾ Prorata values according to number of houses.

⁽³⁾ Data from design flow under PWP No. 4358DS and 4391DS.

CDA Development

Phase	Site Area ⁽¹⁾ (m ²)	Туре	No. of Flats ⁽²⁾	Occupancy Rate ⁽³⁾	Population ⁽⁴⁾	UFF (m³/ person/ day)	Projected ADWF (m³/day), with P _{CIF} =1.3
1A	13,577.3	Residential	1,981	2.7	5,348.7	0.27	1,877
	513.8	Home Care Services for Frail Elderly Persons (HCS)	-	-	15.2	0.28	6
	650.2	School Social Work Office	-	-	41.0	0.28	15
	2,708.0	Residential Care Home Centre for the Elderly (RCHE) (100 Places) - resident	-	-	100.0	0.19	25
		Residential Care Home Centre for the Elderly (RCHE) (100 Places) - staff	-	-	9.3	0.28	3
	300.0	Clubhouse - F&B	-	5.1	15	1.58	31
	2,700.0	Clubhouse - Other Staff	-	3.3	89	0.28	32
	685.6	Retail - F&B	-	5.1	35	1.58	72
	1,599.7	Retail - Other Staff	-	3.3	53	0.28	19
	650.0	Backwash flow for swimming	-	-	-	-	10
	10,111.8	Residential	1,476	2.7	3,985	0.27	1,399
	656.0	Neighbourhood Elderly Centre (NEC)	-	-	11.25	0.28	4
	2,708.0	Residential Care Home Centre for the Elderly (RCHE) (100 Places) - resident	-	-	100.0	0.19	25
1B		Residential Care Home Centre for the Elderly (RCHE) (100 Places) - staff	-	-	9.3	0.28	3
	242.0	Clubhouse - F&B	-	5.1	12	1.58	25
	2,178.0	Clubhouse - Other Staff	-	3.3	72	0.28	26
	454.9	Retail - F&B	-	5.1	23	1.58	48
	1,061.4	Retail - Other Staff	-	3.3	35	0.28	13
	500.0	Backwash flow for swimming pool P1B	-	-	-	-	8

	7,934.7	Residential	1,158	2.7	3,127	0.27	1,097
	716.0	60-place Day Care Centre for the Elderly	-	-	22.507	0.28	8
	392.0	Office Base of On-site Pre- school Rehabilitation Services (OPRS)	-	-	17	0.28	6
RPA	1,422.0	120-place Day Care Centre for the Elderly	-	-	45.014	0.28	16
	214.0	Clubhouse - F&B	-	5.1	11	1.58	22
	1,926.0	Clubhouse - Other Staff	-	3.3	64	0.28	23
	431.2	Retail - F&B	-	5.1	22	1.58	45
•	1,006.1	Retail - Other Staff	-	3.3	33	0.28	12
	320.0	Backwash flow for swimming pool RPA	-	-	-	-	5
	16,689.3	Residential	2,437	2.7	6,580	0.27	2,310
	818.8	60-place Special Child Care Centre (SCCC)	-	-	27.2	0.28	10
	3,826.0	Residential Care Home Centre for the Elderly (RCHE) (150 Places) - resident	-	-	150.0	0.19	37
RPB		Residential Care Home Centre for the Elderly (RCHE) (150 Places) - staff	-		13.5	0.28	5
KPB	1.060.0	Child Care Centre (100 places) - Children/ Student	-	-	100.0	0.04	5
	1,060.0	Child Care Centre (100 places) - Staff (5)	-	-	20.0	0.28	7
	350.0	Clubhouse - F&B	-	5.1	18	1.58	37
	3,150.0	Clubhouse - Other Staff	-	3.3	104	0.28	38
	249.9	Retail - F&B	-	5.1	13	1.58	26
	583.1	Retail - Other Staff	-	3.3	19	0.28	7
-	320.0	Backwash flow for swimming pool RPB	-	-	-	-	5
		-		Total	19,875	-	7,364

⁽¹⁾ GFA for school and clubhouse

⁽²⁾ For calculation of the flat no., please refer to Supporting Planing Statement

⁽³⁾ The unit is no. of residents per flat and no. of clubhouse employee per 100m^2 GFA, the occupacy rate for clubhouse refer to Commercial and Industrial Floor Space Utilization Survey by PlanD

⁽⁴⁾ Notional staffing for the proposed welfare facilities according to the establishment from SWD website.

⁽⁵⁾ The children/ staff ratio is assumed to be 5:1 conservatively to inlude child care supervisor, child care worker, child care aide, clerical assisstant and cook/workman.

Part 2 - Calculation of Flows from Kau Wah Keng

Scenario	Discharge Point	ADWF from Kau Wa Keng Old Village	Different Sou Kau Wa Keng San Tsuen	CDA	Total ADWF (m³/day)	Contributing Population	Peaking Factor for Sewer ⁽¹⁾	Peaking Factor for SPS ⁽²⁾	Peak Flow for Sewer (m ³ /s)	Peak Flow for SPS (m³/s)
1. Baseline	FMH4009607 from KWKSPS	1116	419	0	1535	5,684	-	4	-	0.071
2. Phase 1 Development	FMH4009607 from KWKSPS (Village Only)	1116	419	0	1535	5,684	-	4	-	0.071
	FMH4009609 from the proposed SPS (CDA Only)	0	0	3,642	3,642	13,488	-	3.5	1	0.148
	FMH4009609 (Total Flow)	1116	419	3,642	5,176	-	-	1	ı	-
	FMH4009607 from FMH4009599 and KWKSPS (Village Only)	228	393	0	621	2,301	6	4	0.043	0.029
3. Fully Developed CDA	FMH4009609 from the proposed SPS (CDA Only)	0	0	7,364	7,364	27,275	-	3.0	1	0.256
	FMH4009609 (Total Flow)	228	393	7,364	7,986	-	-	-	-	-

⁽¹⁾ The calculation is only for the sewerage impact to sewer manhole No. FMH4009599 due to village sewerage diversion

Additional ADWF = 3,642 m³/day in Scenario 2, and 7,364 m³/day in Scenario 3.

Additional Peak Flow to Downstream Sewers = 0.148 m³/s in Scenario 2, and 0.256 m³/s in Scenario 3.

Regardless of the flow from DWFI and village sewerage, the sewage flow discharged to the downsteam sewer network is controlled by the design capacity of KWKSPS. Therefore, the additional flow in this assessment will be the sewage from the proposed development and will not consider the sewage flow reduction in the villages due to the devlopment.

Design Capacity of the Proposed SPS=7,364 m³/dayDesign Pump Rate of the Proposed SPS=0.256 m³/sDesign Diameter of the Proposed Sewage Rising Mains*=450 mm

⁽²⁾ Since the sewage from the village sewerage and the CDA are discharged to seperated SPS, the peak flow are estimated seperately.

^{*} Assumed flow velocity 1.3 - 2 m/s

Part 3 - Calculation of Other Flows Discharged to Lai King Hill Road (based on 2021 Population By-Census from CentaMap)

Building Group No.	Total Population	Name of Estate/Building	Zoning in OZP	Projected Population	UFF (m³/ person/ day)	Projected ADWF (m³/day), with P _{CIF} =1.3	Contributing Population	Peaking Factor for Sewer	Peak Flow for Sewer (m ³ /s)
KT0197	5601	Lai Yan Court	R(A)	5,881	0.19	1,453			
KT0200	2657	Happy Villa, Wah Fung Garden, Greenwood Villas and buildings No. 7-22 of Chung Shan Terrace (assume equivalent to Lai Chi Kok Bay Garden)	R(B)	2,790	0.27	979	9,007	5	0.141

^{(1) 5%} growth rate is applied to the residentail population

Appendix G

Calculation for Impact Assessment

Appendix G - Calculation for Potential Sewerage Impacts

Manning Equation is used to estimate the performace of the existing/planned sewers

$$\overline{V} = -\sqrt{32gRS_f} \log \left[\frac{k_s}{14.8R} + \frac{1.255v}{R\sqrt{32gRS_f}} \right]$$
 where R (hydraulic radius) = A/P_f ks (Roughness coefficient) = S_s (friction gradient) = serve

ks (Roughness coefficient) = 1.5mm for HDPE sewers in poor condition;

 S_f (friction gradient) = sewer gradient for normal flows.

is kinematic viscosity of water = 1.01e-6 at 1atm and 20° C

Part 1 - Impact Assessment for Sewers to the Downstream of Manhole No. FMH4009599

Existing Sewers

US MH No.	DS MH No.	Pipe Length (m)	Pipe Diameter (mm)	US IL (mPD)	DS IL (mPD)	Pipe Gradient	Radius R		Full Bore Capacity (m³/s)	Cumulative Peak Flow (m ³ /s)	% Full Bore Capacity	Remarks
FMH4009599	FMH4009600	29.22	225	1.71	1.42	0.0099	0.05625	1.143	0.0455	0.043	95%	Unavadina
FMH4009600	FMH4009601	31.62	225	1.42	1.18	0.0076	0.05625	0.999	0.0397	0.043	109%	Upgrading works
FMH4009601	FMH4009602	4.11	225	1.18	1.14	0.0097	0.05625	1.132	0.0450	0.043	96%	
FMH4009602	FMH4009605	8.28	300	1.14	1.1	0.0048	0.075	0.962	0.0680	0.043	63%	required

Proposed upgrading works

Proposed upgrad	illig works											
US MH No.	DS MH No.	Pipe Length (m)	Pipe Diameter (mm)	US IL (mPD)	DS IL (mPD)	Pipe Gradient	Radius R		Full Bore Capacity (m³/s)	Cumulative Peak Flow (m³/s)	% Full Bore Capacity	Remarks
FMH4009599	FMH4009600	29.22	300	1.71	1.42	0.0099	0.075	1.382	0.0977	0.043	44%	No adverse impact
FMH4009600	FMH4009601	31.62	300	1.42	1.18	0.0076	0.075	1.208	0.0854	0.043	51%	No adverse impact
FMH4009601	FMH4009602	4.11	300	1.18	1.14	0.0097	0.075	1.368	0.0967	0.043	45%	No adverse impact
FMH4009602	FMH4009605	8.28	300	1.14	1.1	0.0048	0.075	0.962	0.0680	0.043	63%	No adverse impact

Part 2 - Impact Assessment for Sewers to the Downstream of Manhole No. FMH4009607

Proposed Upgrading Works under 4389DS (Manhole Schedule refer to Appendix C1)

US MH No. (4389DS Refernce No.)	DS MH No. (4389DS Refernce No.)	Pipe Length (m)	Pipe Diameter (mm) [#]	US Invert^ (mPD)	DS Invert^ (mPD)	Gradient	Hydaulic Radius R (m)	Full Bore Velocity (m/s)	Full Bore Capacity (m³/s)	Additonal Peak Flow from CDA (m³/s)	Flow from Other Catchments (m³/s)*	Note for Flow from Other Catchments	Total Peak Flow (m ³ /s)	% Full Bore Capacity
FMH4009607 (MB17)	FMH4009608 (MB17A)	9.90	600	4.500	4.390	0.011	0.15	2.288	0.647	0.256	0.053	KWKSPS	0.309	48%
FMH4009608 (MB17A)	FMH4009609 (MB18)	3.97	600	4.390	4.350	0.010	0.15	2.178	0.616	0.256	0.053	/	0.309	50%
FMH4009609 (MB18)	FMH4009567 (MB19)	4.42	600	4.350	4.290	0.014	0.15	2.529	0.715	0.256	0.053	/	0.309	43%
FMH4009567 (MB19)	FMH4009568 (MB20)	5.83	675	4.290	4.240	0.009	0.16875	2.166	0.775	0.256	0.194	Building Group No. KT0197, KT0200	0.450	58%
FMH4009568 (MB20)	FMH4009569 (MB21)	29.30	675	4.240	4.010	0.008	0.16875	2.072	0.741	0.256	0.194	/	0.450	61%
FMH4009569 (MB21)	FMH4009570 (MB22)	29.00	675	4.010	3.810	0.007	0.16875	1.942	0.695	0.256	0.194	/	0.450	65%
FMH4009570 (MB22)	FMH4009571 (MB23)	30.30	675	3.810	3.650	0.005	0.16875	1.698	0.608	0.256	0.194	/	0.450	74%
FMH4009571 (MB23)	MB24	29.02	675	3.650	3.510	0.005	0.16875	1.623	0.581	0.256	0.194	/	0.450	77%
MB24	FMH4009573 (MB25)	35.01	675	3.510	3.330	0.005	0.16875	1.676	0.600	0.256	0.194	/	0.450	75%
FMH4009573 (MB25)	FMH4009575 (MB26)	25.50	675	3.330	3.210	0.005	0.16875	1.603	0.574	0.256	0.194	/	0.450	78%
FMH4009575 (MB26)	FMH4009576 (MB27)	29.95	675	3.210	3.090	0.004	0.16875	1.479	0.529	0.256	0.194	/	0.450	85%
FMH4009576 (MB27)	FMH4009577 (MB28)	14.73	675	3.090	3.030	0.004	0.16875	1.491	0.534	0.256	0.194	/	0.450	84%
FMH4009577 (MB28)	FMH4009578 (MB29)	48.30	675	3.030	2.860	0.004	0.16875	1.386	0.496	0.256	0.194	/	0.450	91%
FMH4009578 (MB29)	FMH4009579 (MB30)	37.08	675	2.860	2.730	0.004	0.16875	1.383	0.495	0.256	0.194	/	0.450	91%
FMH4009579 (MB30)	FMH4009580 (MB31)	42.23	675	2.730	2.580	0.004	0.16875	1.392	0.498	0.256	0.194	/	0.450	90%
FMH4009580 (MB31)	FMH4009581 (MB32)	34.35	675	2.580	2.350	0.007	0.16875	1.913	0.685	0.256	0.194	/	0.450	66%

^{*}For upstream of manhole FMH4009567, design flow of KWKSPS is adopted. The pump rate is assumed to be four times of the average flow under ADWF. Design capacity of KWKSPS is 1,152m³/day (provided by DSD).

[^]According to the manhole schedule on the latest design drawings.

[#] The proposed upgrading works will be undertaken by the applicant in case of project mismatch of PWP 4389DS.

Part 3 - Impact Assessment for Sewers to the Downstream of Manhole No. FMH4009445

US MH No.	DS MH No.	Pipe Length (m)	Pipe Diameter (mm) [#]	US Invert^ (mPD)	DS Invert^ (mPD)	Gradient	Hydaulic Radius R (m)	Full Bore Velocity (m/s)	Full Bore Capacity (m ³ /s)	Flow from Upstream* (m³/s)	% Full Bore Capacity
FMH4009442	FMH4009443	23.28	500	2.550	2.210	0.015	0.125	2.335	0.458	Considered full bore	/
FMH4009589	FMH4009443	43.54	600	2.250	2.210	0.001	0.15	0.654	0.185	Considered full bore	/
FMH4054163	FMH4009444	12.10	150	/	/	0.005	0.0375	0.618	0.011	Considered full bore	/
FMH4009444	FMH4009445	55.33	1500	1.650	1.630	1.005	0.375	38.806	68.576	1.104	2%

*For upstream of manhole FMH4009444, the inlet flow is from one DN150 pipe discharge from FMH4054163, one DN500 pipe from FMH4009442, one DN600 pipe from FMH4009589 and one DN675 pipe from FMH4009580. It is considered full bore flow from the DN150, DN600 and DN500. The sewerage plan can be referred as below.

