



- inside CA zone**
- Item 1a: 93m(L) x 1m(W) x 1.2m(D)
 - Item 5: 1m(L) x 1m(W) x 1.8m(D) x7.2m(H)
 - Item 8: 1m(L) x 1m(W) x 1.8m(D) x7.2m(H)
 - Item 12: 1m(L) x 1m(W) x 1.8m(D) x7.2m(H)
 - Item 16: 1m(L) x 1m(W) x 1.8m(D) x7.2m(H)
 - Item 3: 1m(L) x 1m(W) x 1.2m(D)
 - Item 4: 1m(L) x 1m(W) x 1.2m(D)
 - Item 6: 1m(L) x 1m(W) x 1.2m(D)
 - Item 7: 1m(L) x 1m(W) x 1.2m(D)
 - Item 9: 1m(L) x 1m(W) x 1.2m(D)
 - Item 10: 1m(L) x 1m(W) x 1.2m(D)
 - Item 11: 1m(L) x 1m(W) x 1.2m(D)
 - Item 13: 1m(L) x 1m(W) x 1.2m(D)
 - Item 14: 1m(L) x 1m(W) x 1.2m(D)
 - Item 15: 1m(L) x 1m(W) x 1.2m(D)
- S16 will be applied**

- outside CA zone**
- Item 1b: 15m(L) x 1m(W) x 1.2m(D)
 - Item 2: 10m(L) x 1m(W) x 1.2m(D)
 - Item 17: 1m(L) x 1m(W) x 1.2m(D)
 - Item 18: 1m(L) x 1m(W) x 1.2m(D)
 - Item 19: 1m(L) x 1m(W) x 1.8m(D) x7.2m(H)
- S16 will be not applied**



TITLE : LV CABLE LAYING, POLE & STAY ERECTION
 AT NAM WAI
 NEAR LOT618SA LOT 619
 SAI KUNG

MAP NO : 11NE05B

LEGEND

- PROPOSED TRENCH FOR LAYING / RECOVERING CABLE
- PROPOSED TRENCH FOR LAYING DUCTS
- PROPOSED CABLE THROUGH EXISTING DUCTS
- EXISTING PILLAR
- PROPOSED PILLAR 1.6M x 0.6M x 0.75M / CUTOUT BOX
- EXCAVATION FOR JOINTING / REPAIRING / INSPECTION CABLE
- EXISTING OVERHEAD LINE & POLE
- PROPOSED 11KV, LV, OHL, OF STEEL / WOODEN POLE
- OVERHEAD LINE & POLE TO BE REMOVED
- PROPOSED TREE TRIMMING / CUTTING
- EXISTING POLE MOUNTED TRANSFORMER
- PROPOSED POLE MOUNTED TRANSFORMER
- PROPOSED STAY / STAY POLE
- PROPOSED 3.6M(L) x 3.32M(W) x 2.7M(H) HV PILLAR

DRAWN : H.Y. WONG		E/O NO :	
CHECKED : W.Y. KWAN		REGION : WE	O.C. : SK
DATE : 23-10-2024		PROJECT REF. : SK2024-0049	
SCALE : 1:1000		PLAN REF. : WESK2024-0049-01H	

Map data reproduced with permission of the Director of Lands. (C) Hong Kong Information Classification: PROPRIETARY