


## Appendix 6

---

### Tree Survey



T1

## Existing Trees within the Application Site

## **T1 - T6 *Ficus microcarpa* (All proposed to be felled)**

**For details, please refer to Tree Assessment Schedule**

Legend:

- • — Application Site (Area: about 2,287m<sup>2</sup>)
- ■ ■ Warehouse with Ancillary Facilities (Height: not exceeding 13m)
- ■ ■ Loading/Unloading Spaces for Light Goods Vehicles (3 nos.) (3.5m x 7m)
- ■ ■ Private Car Parking Spaces for Staff/Visitors (4 nos.) (2.5m x 5m)

## Existing Trees within the Application Site

Figure 6

Scale 1:1000



## 羅迅測計師行

Lawson David & Sung

**Lawson David & Sons**  
SURVEYORS LIMITED  
Property Consultants • Planning • Valuers • Auctioneers


## Photographic Record of Tree Survey




T1



T2



T3



T4



T5



T6

**Tree Survey**

**Project Title: Lot 2447 S.A RP in D.D. 130**

**Date of survey: 5-12-2025**

**Surveyed by: C K Lau Surveyors Limited**

**Tree Assessment Schedule**

Tree No.	Photo No.	Species		Measurements			Location		Top of soil level above root collar (mPD)	Amenity Values	Form	Health	Structural Condition	Suitability for Transplanting		# Conservation Status	Additional Remarks
		Botanical Name	Chinese Name	Height (m)	Trunk DBH (mm)	Crown Spread (m)	Northing	Easting		(High(H)/ Medium(M) /Low(L))	Good(G)/ Average(A)/ Poor(P)		(High(H)/ Medium(M) /Low(L))	*	Remarks		
T1	T1	<i>Ficus microcarpa</i>	細葉榕	7	350	5	817581.988	831464.121	22.7	L	P	A	A	L	a b	Nil	Hangers, wound on trunk, codominant stems
T2	T2	<i>Ficus microcarpa</i>	細葉榕	9	500	8	817589.690	831459.084	22.8	L	A	A	A	L	a b c d	Nil	Codominant stems
T3	T3	<i>Ficus microcarpa</i>	細葉榕	8	520	6	817591.595	831456.419	22.9	L	A	A	A	L	a b	Nil	Codominant stems
T4	T4	<i>Ficus microcarpa</i>	細葉榕	12	400	10	817596.444	831447.656	23.2	L	A	A	A	L	a b c d	Nil	Codominant stems
T5	T5	<i>Ficus microcarpa</i>	細葉榕	12	420	10	817598.031	831443.229	23.4	L	P	A	A	L	a b c d	Nil	Crooked, wound on trunk
T6	T6	<i>Ficus microcarpa</i>	細葉榕	12	350	10	817591.005	831430.752	24.4	L	P	P	P	L	a b c d	Nil	Restricted root, Significant diebacks, crooked, epicormics

**\* Remarks for suitability for transplanting**

- a) low amenity value;
- b) irrecoverable form after transplanting (e.g. if substantial crown and root pruning are necessary to facilitate the transplanting)
- c) low survival rate after transplanting;
- d) very large size (unless the feasibility to transplant has been considered financially reasonable and technically feasible during the feasibility stage);
- e) with evidence of over-maturity and onset of senescence;
- f) with poor health, structure or form (e.g. imbalanced form, leaning, with major cavity/cracks/splits);
- g) undesirable species (e.g. *Leucaena leucocephala* which is an invasive exotic tree), or
- h) on steep slope.
- i) trees grown under poor conditions which have limited the formation of proper root ball necessary for transplanting

**#Conservation status**

- (A) The Protection of Endangered Species of Animals and Plants Ordinance (Cap.586)
- (B) Forests and Countryside Ordinance (Cap. 96)
- (C) Rare and Precious Plants of Hong Kong
- (D) IUCN Red List of Threatened Species