Appendix A

Revised Air Quality Impact Review

Prepared for


Ten Choice Development Limited

Prepared by

Ramboll Hong Kong Limited

SECTION 16 PLANNING APPLICATION FOR PROPOSED SOCIAL WELFARE FACILITY (RESIDENTIAL CARE HOME FOR THE ELDERLY) IN "RESIDENTIAL (GROUP C)" ZONE AT PALM SPRINGS PLAZA (SHOP NOS. G1-G3 & G5-G8), YUEN LONG, NEW TERRITORIES

AIR QUALITY IMPACT REVIEW

Date	**11 November 2026**
Prepared by	**Tony Ling** **Environmental Consultant**
Signed	
Approved by	**Tony Cheng** **Senior Manager**
Signed	
Project Reference	**SHKPS-EHEI00**
Document No.	**R10252_v1.2**

No part of this document may be reproduced or transmitted, in any form or by any means electronic, mechanical, photographic, recording or otherwise, or stored in a retrieval system of any nature without the written permission of Ramboll Hong Kong Ltd, application for which shall be made to Ramboll Hong Kong Ltd, [redacted].

Disclaimer: This report is made on behalf of Ramboll Hong Kong Ltd. No individual is personally liable in connection with the preparation of this report. By receiving this report and acting on it, the client or any third party relying on it accepts that no individual is personally liable in contract, tort or breach of statutory duty (including negligence).

Ramboll Hong Kong Limited

[redacted]

[redacted]

CHAPTERS

Page

1. INTRODUCTION 2
1.1 Background and Objectives 2
1.2 Project Location and Description 2
1.3 Air Quality Environment Appraisal 2
2. OPERATIONAL PHASE REVIEW 2
2.1 Scope of Work 2
2.2 Relevant Legislations, Standards and Guidelines 2
2.3 Potential Impacts on the Proposed RCHE – Operation Phase 4
2.4 Potential Impacts from the Proposed RCHE – Operation Phase 5
2.5 Conclusion 6
3. CONSTRUCTION PHASE REVIEW 8
3.1 Scope of Work 8
3.2 Relevant Legislations, Standards and Guidelines 8
3.3 Surrounding Air Sensitive Receivers 8
3.4 Review of the Construction Phase Impact 8
4. OVERALL CONCLUSION 11
4.1 Overall Summary 11

FIGURES

Figure 1.1 Location of Application Premises and its Environs
Figure 1.2 Layout of the Proposed RCHE
Figure 2.1 200m and 500m Assessment Area from the Proposed RCHE
Figure 2.2 Buffer Distance from the Road Kerb of Palm Springs Boulevard
Figure 3.1 Location of Nearest Air Sensitive Uses

APPENDICES

Appendix 1.1 Approved General Building Plan

1. INTRODUCTION

1.1 Background and Objectives

1.1.1 This planning statement is submitted to the Town Planning Board (the Board) under Section 16 of the Town Planning Ordinance to seek permission for proposed Social Welfare Facility (Residential Care Home for the Elderly) use (hereafter referred to as "the Proposed RCHE") at Palm Springs Plaza (Shop Nos. G1-G3 & G5-G8), Yuen Long, New Territories (hereafter referred to as "the Application Premises"). Ramboll Hong Kong Limited (the Consultant) has been commissioned by the Applicant to conduct this Air Quality Impact Review.

1.2 Project Location and Description

1.2.1 The Palm Springs Plaza is located at the middle of the Palm Springs.

1.2.2 **Figure 1.1** shows the location and the environs of the Palm Springs Plaza.

1.2.3 The approved general building plan of the plaza can be found in **Appendix 1.1**.

1.2.4 The applicant proposes to convert an area of around 974m^2 on the G/F of Palm Springs Plaza (Shop Nos. G1-G3 & G5-G8) to the Proposed RCHE, which will provide 90 private bed spaces. The layout of the Proposed RCHE is shown in **Figure 1.2**.

1.3 Air Quality Environment Appraisal

1.3.1 The Palm Springs Plaza is located at the middle of the Palm Springs and surrounded by residential houses. The Proposed RCHE is located at the western part of the ground floor of the plaza, i.e. there is no major construction activities involving. The construction would involve alternation and addition works of the ground floor of the plaza.

1.3.2 The major air quality source affecting the proposed RCHE is the Palm Springs Boulevard, which is a local road. The major roads in the area, such as the Castle Peak Road and San Tin Highway are located about 380m away from the proposed RCHE with clusters of residential blocks located in between.

1.3.3 The Palm Springs is supported by an on-site sewage treatment plant with internal drains connecting premises to it. The location of the on-site sewage treatment plant is at the northwestern end of the Palm Springs with a separation from the Palm Springs Plaza of around 530m with residential houses located in between.

1.3.4 Section 2 reviews whether the Proposed RCHE will be subject to any adverse air quality impact.

1.3.5 Section 3 reviews the potential construction impact to the surroundings.

2. OPERATIONAL PHASE REVIEW

2.1 Scope of Work

2.1.1 The aim of this study is to review the potential air quality impact associated with the operation of the proposed RCHE use on the G/F of Palm Springs Plaza (Shop Nos. G1-G3 & G5-G8). Mitigation measures may be required if any adverse impact is identified.

2.2 Relevant Legislations, Standards and Guidelines

2.2.1 The following legislation and regulations provide the standards and guidelines for evaluation of air quality and odour impacts and the type of works that are subject to air pollution and odour control:

- Air Pollution Control Ordinance (APCO) (Cap. 311) and the Air Quality Objectives (AQO)
- Air Pollution Control (Construction Dust) Regulation
- Recommended Pollution Control Clauses for Construction Contracts
- Control of Air Pollution in Car Parks (ProPECC PN 2/96)
- Hong Kong Planning Standards and Guidelines (HKPSG)
- Criteria for Evaluating Air Quality Impact (Annex 4 of the EIAO-TM)

Air Pollution Control Ordinance (CAP 311)

2.2.2 To achieve as soon as reasonably practicable and to maintain thereafter to safeguard the health of the community, a set of Air Quality Objectives (AQOs) is established under the Air Pollution Control Ordinance (Cap. 311). The current set of AQOs that came into effect on 11 April 2025 is presented in **Table 2.1**.

Table 2.1 Current Hong Kong Air Quality Objectives (AQOs)

Pollutants	Average Time	Standard [i] (µg/m3)	No. of exceedances allowed
SO_2	10-min	500	3
	24-Hour	40	3
RSP (PM_{10}) [ii]	24-Hour	75	9
	Annual	30	NA
FSP ($PM_{2.5}$) [iii]	24-Hour	37.5	18
	Annual	15	NA
NO_2	1-Hour	200	18
	24-Hour	120	9
	Annual	40	NA
Ozone (O_3)	8-Hour	160	9
	Peak Season	100	NA
Carbon Monoxide (CO)	1-Hour	30,000	0
	8-Hour	10,000	0
	24-Hour	4,000	0
Lead (Pb)	Annual	0.5	NA

Notes:

[i] All measurements of the concentration of gaseous air pollutants, i.e. sulphur dioxide, nitrogen dioxide, ozone and carbon monoxide, are to be adjusted to a reference temperature of 293 Kelvin and a reference pressure of 101.325 kilopascal.

[ii] Respirable suspended particulates mean suspended particles in air with a nominal aerodynamic diameter of 10 μm or less.

[iii] Fine suspended particulates mean suspended particles in air with a nominal aerodynamic diameter of 2.5 μm or less.

Air Pollution Control (Non-road Mobile Machinery) (Emission) Regulation

2.2.3 The Air Pollution Control (Non-road Mobile Machinery) (Emission) Regulation, which aims to control emissions from non-road mobile machinery (NRMMs) to improve air quality, became effective on 1 June 2015. NRMMs include non-road vehicles, as well as mobile machines and equipment (regulated machines) such as crawler cranes, excavators and air compressors.

2.2.4 Under the regulation, regulated machines have to comply with the Stage IIIA emission standards of the European Union (EU). It also requires all regulated machines sold or leased for use in Hong Kong to bear an approval or exemption label issued to them by the EPD, started from 1 September 2015. It restricts specified activities and locations including construction sites, designated waste disposal facilities and specified processes to use only NRMMs that bear an approval or exemption label issued to them by the EPD, with effect from 1 December 2015.

Hong Kong Planning Standards and Guidelines (HKPSG)

2.2.5 Potential air quality impacts associated with the surrounding road carriageways and chimney emission from industrial stack shall be evaluated in accordance with the guidelines set out in the HKPSG.

2.2.6 Table 3.1 of Chapter 9 of the HKPSG provides the broad guidelines for locating open spaces close to potentially polluting uses, viz. road traffic. The recommended buffer distances are reproduced in **Table 2.2**.

Table 2.2 Recommended Minimum Buffer Distance from Roads

Pollution Source	Parameter	Buffer Distance	Permitted Uses
Road and Highways	Type of Road		
	Trunk Road and Primary Distributor	> 20 m	Active and passive recreation uses
		3 – 20 m	Passive recreational uses
		< 3 m	Amenity areas
	District Distributor	> 10 m	Active and passive recreational uses
		< 10 m	Passive recreational uses
	Local Distributor	> 5 m	Active and passive recreational uses
		< 5 m	Passive recreational uses
	Under Flyovers	-	Passive recreational uses

Source:HKPSG Chapter 9 Table 3.1: Guidelines on Usage of Open Space Site

2.2.7 Table 3.1 of Chapter 9 of the HKPSG also provides the broad guidelines for locating open spaces close to potentially polluting uses, viz. industrial chimneys emissions. The recommended buffer distances are reproduced in **Table 2.3**.

Table 2.3 Recommended Minimum Buffer Distance from Industrial Chimneys

Pollution Source	Parameter	Buffer Distance	Permitted Uses
Industrial Areas	Difference in Height between Industrial Chimney Exit and the Site		
	< 20 m	> 200 m	Active and passive recreation uses
		5 – 200 m	Passive recreational uses
	20 m – 30 m (*)	> 100 m	Active and passive recreational uses
		5 – 100 m	Passive recreational uses
	30 m – 40 m	> 50 m	Active and passive recreational uses
		5 – 50 m	Passive recreational uses
	> 40 m	10 m	Active & Passive recreational uses

Notes:

(i) In situations where the height of chimneys is not known, use the set of guidelines marked with an asterisk for preliminary planning purpose and refine as and when more information is available.

(ii) The buffer distance is the horizontal, shortest distance from the boundary of the industrial lot, the position of existing chimneys or the edge of road kerb, to the boundary of open space sites.

(iii) The guidelines are generally applicable to major industrial areas but NOT individual large industrial establishment which are likely to be significant air pollution sources. Consult EPD when planning open spaces close to such establishments.

(iv) Amenity areas are permitted in any situation.

Source:HKPSG Chapter 9 Table 3.1: Guidelines on Usage of Open Space Site

2.3 Potential Impacts on the Proposed RCHE – Operation Phase

Review on Industrial Emission Impact

2.3.1 The buffer distance of 200m from the Application Premises is shown in **Figure 2.1**. Site survey was conducted in Jun 2026 to verify the presence of chimneys. There were no chimney or industrial activities identified within the 500m assessment area of the proposed RCHE. The buffer distance requirement under the Hong Kong Planning Standards and Guidelines (HKPSG) listed in Table 2.3 above could be met, no adverse air quality impact from the chimney/industrial emission source is anticipated.

Review on Vehicular Emission Impact

2.3.2 The Palm Springs Plaza is located at the middle of the Palm Springs which is surrounded by residential houses. The major roads of the area (Castle Peak Road and San Tin Highway) are located far away from the plaza (~380m) and are separated by clusters of houses in between.

2.3.3 The Application Site is mainly bounded by the Palm Springs Boulevard to the south and the Sunflower Path to the north. The road classification of the nearby road network provided by project traffic consultant is shown in **Figure 2.2**.

2.3.4 The Sunflower Path is an internal road of Palm Springs with gate bar at the entrance for restriction of access. This road mainly serves 10 detached houses and the existing open carpark for the Palm Springs Plaza only. Although the building layout of Palm Springs Plaza imposes physical constraints on the proposed RCHE for maintaining sufficient buffer distance from Sunflower Path, there would be very limited number of private cars travelling along this internal road. As such, this internal road is not anticipated to induce any adverse air quality impact on the Proposed RCHE.

2.3.5 There is an open carpark for the Palm Springs Plaza to the west of the air sensitive receivers of the Proposed RCHE. This ancillary carpark is a charged carpark with private car parking spaces for the Palm Springs Plaza. As such, only the visitors to the Palm Springs Plaza will use this carpark. With such limited usage, it is anticipated that this ancillary carpark would not induce any adverse air quality impact on the air sensitive receivers of the Proposed RCHE.

2.3.6 The western section of the Palm Springs Boulevard that falls within the same private lot of Palm Springs Plaza is the internal road of Palm Springs. The traffic is considered limited since it is mainly induced by the private cars of the residents of detached houses. Also, the separation from the air sensitive use of the Proposed RCHE is around 10m to the Palm Springs Boulevard. Therefore, a minimum separation distance of >5m setback for local distributor under the HKPSG in **Table 2.2** can be fulfilled. As shown in **Figure 2.2**, the setback from the road kerb of Palm Springs Boulevard is around 10m which is well above the HKPSG recommended buffer distance for vehicular emission. With limited traffic travelling on this internal road and with sufficient buffer distance, it is anticipated that this internal road would not induce any adverse air quality impact on the air sensitive receivers of the Proposed RCHE.

2.3.7 In view of above, the proposed RCHE would not be subject to adverse air quality impacts.

Review on Odour Impact

2.3.8 According to site survey carried in Jun 2026, there is no odour emission source within 500m assessment area from the proposed RCHE. The location of the on-site sewage treatment plant for Palm Springs is at the northwestern end of the Palm Springs with the separation from the Palm Springs Plaza is around 530m with residential houses located in between, such that the buffer distance requirement of 200m under Chapter 9 of HKPSG can be fulfilled. Therefore, no adverse odour impact is anticipated. Location of the Palm Springs On-Site Sewage Treatment Plant is also shown in **Figure 2.1**.

2.4 Potential Impacts from the Proposed RCHE – Operation Phase

Review on Potential Air Quality Impact from Oily Fume and Cooking Odour

2.4.1 Kitchen will be provided within the proposed RCHE. Exhaust hoods and appropriate Air Pollution Control Equipment and grease trap will be provided and the air change rate for the kitchen area will be designed according to the standard of kitchen as stipulated in Building Department's Practice Note for Authorized Persons (PNAP). Potential odour emissions will be minimised as far as practicable. The following considerations recommended in EPD's Control of Oil Fume and Cooking Odour from Restaurant and Food Business shall be taken into account in the detailed design when positioning the exhaust outlets:

- Locate the outlet at such a place where the ventilation is good and the emissions from them can be adequately dispersed without hindrance
- Provide sufficient separation distance from any sensitive receptor in the vicinity so that the emissions will not cause, or contribute to, an odour nuisance or other type of air pollution to the public
- Ensure the emissions from the exhaust system will be directed vertically upwards, unless it can be demonstrated by an environmental professional that other direction is more advantageous in preventing emissions from causing air pollution problems

- Ensure that emissions from the exhaust system will not be restricted nor deflected by, for example, the use of plates or caps

2.5 Conclusion

2.5.1 In view of above, the proposed RCHE would not be subject to any adverse air quality impacts during the operation.

3. CONSTRUCTION PHASE REVIEW

3.1 Scope of Work

3.1.1 The aim of this study is to review the potential air quality impact associated with the construction of the proposed RCHE use on the G/F of Palm Springs Plaza (Shop Nos. G1-G3 & G5-G8) upon the surrounding air sensitive use. Mitigation measures may be required if any adverse impact is identified. The construction works for the proposed RCHE involves decoration and renovation works only.

3.2 Relevant Legislations, Standards and Guidelines

3.2.1 The following legislation and regulations provide the standards and guidelines for evaluation of air quality and odour impacts and the type of works that are subject to air pollution and odour control:

- Air Pollution Control Ordinance (APCO) (Cap. 311) and the Air Quality Objectives (AQO)
- Recommended Pollution Control Clauses for Construction Contracts

Air Pollution Control (Construction Dust) Regulation

3.2.2 Made under Section 43 of the APCO, this Regulation defines notifiable and regulatory works for achieving the purpose of dust control for a number of activities. The Regulation requires that any notifiable work shall give advance notice to EPD, and the Contractors shall ensure that the notifiable and regulatory works are carried out in accordance with the Schedule of the Regulation. Dust control and suppression measures are also provided in the Schedule.

3.2.3 The proposed construction works for the proposed Project involve alternation and addition works within the premises. Therefore, piling works nor excavation works would not be required. Dusty material handling is likely be the potential sources of fugitive dust emissions as detailed under Parts I to IV of the Schedule on Dust Control Requirements.

Air Pollution Control (Fuel Restriction) Regulations

3.2.4 The Air Pollution Control (Fuel Restriction) Regulations was enacted in 1990 to impose legal control on the type of fuels allowed for use and their sulphur contents in commercial and industrial processes to reduce sulphur dioxide (SO2) emissions. In June 2008, the Regulation was amended to tighten the control requirements of liquid fuels. On 1 April 2025, the sulphur content of liquid fuel is further tightened to 0.001% by weight.

3.3 Surrounding Air Sensitive Receivers

3.3.1 Figure 3.1 shows the nearest surrounding air sensitive uses. The nearest air sensitive uses is the House no. 11 of Palm Springs north of the proposed RCHE.

3.4 Review of the Construction Phase Impact

3.4.1 The proposed RCHE is located at the western end of the ground floor of the Palm Springs Plaza, i.e. the project is located at indoor area of the plaza. The Proposed RCHE only involves alteration and addition (A&A) works to the ground floor of the Palm Springs Plaza. All the works will be carried out indoor, and the works would involve mainly the decoration or renovation works. Therefore, it is anticipated that no major construction works or dusty works will be involved and there would be any significant dusty construction works to be carried out.

3.4.2 A&A works are classified as excluded works under the Air Pollution Control (Construction Dust) Regulation. The following general dust suppression (such as control of storge of dusty materials, etc) requirements would be required to be followed.

- Covering stockpiles of dusty materials with impervious sheeting.
- Wetting surfaces before concrete breaking, cutting, or drilling.
- Minimizing dust emissions so they do not cause a public nuisance

3.4.3 Further, during the construction, just like the common commercial mall renovation works, the external façade will be enclosed by hoarding that if there is any dust generated during the renovation works. Also, with implementation of the control requirements under the Air Pollution Control (Construction Dust) Regulation, the potential dust impact to the surrounding air sensitive uses will be minimized.

4. OVERALL CONCLUSION

4.1 Overall Summary

4.1.1 The Applicant proposed to convert an area of around 974m^2 on the G/F of Palm Springs Plaza (Shop Nos. G1-G3 & G5-G8) to the Proposed RCHE, which will provide 90 private bed spaces. Surrounding the Palm Springs Plaza, residential houses are the uses.

4.1.2 The potential air quality impact during the operation of the proposed RCHE have been reviewed and no adverse air quality impact would be anticipated.

4.1.3 The construction of the Proposed RCHE will involve only alternation and addition works, i.e. similar to renovation activities. There are no major construction activities that would generate dust. Also, all the works will be carried out at indoor. With the implementation of appropriate mitigation measures, no adverse air quality impact would be anticipated during the construction of the proposed RCHE.

Figures




Figure: 1.1	RAMBOLL
Title: Location of Palm Springs Plaza and its Environs	Drawn by: TL Checked by: TC
Project: Section 16 Planning Application for Proposed Social Welfare Facility (Residential Care Home for the Elderly) in "Residential (Group C)" Zone at Palm Springs Plaza (Shop Nos. G1-G3 & G5-G8), Yuen Long, New Territories	Rev.: 1.0 Date: Jul 2026

Q:\Projects\SHKPS-EHEI00\05 Assessments\01 Air\AQIA_v1.0.dwg



Figure: 1.2	RAMBOLL
Title: Layout of the Proposed RCHE	Drawn by: TL
	Checked by: TC
Project: Section 16 Planning Application for Proposed Social Welfare Facility (Residential Care Home for the Elderly) in "Residential (Group C)" Zone at Palm Springs Plaza (Shop Nos. G1-G3 & G5-G8), Yuen Long, New Territories	Rev.: 1.0
	Date: Jul 2026

Q:\Projects\SHKPS-EHEI00\05 Assessments\01 Air\AQIA_v1.0.dwg



Figure: 2.1

Title: 500m Assessment Area and 200m Buffer Distance of the Proposed RCHE

RAMBOLL

Drawn by: TL


Checked by: TC

Project: Section 16 Planning Application for Proposed Social Welfare Facility (Residential Care Home for the Elderly) in "Residential (Group C)" Zone at Palm Springs Plaza (Shop Nos. G1-G3 & G5-G8), Yuen Long, New Territories

Rev.: 1.0

Date: Jul 2026

Q:\Projects\SHKPS-EHEI00\05 Assessments\01 Air\AQIA_v1.0.dwg



Remarks:
No air-sensitive use including openable window, fresh air intake and recreational use in open space shall be located within the buffer zone.

Legend:
- Applications Premises
- 5m Buffer Distance

Figure: 2.2	RAMBOLL
Title: Buffer Distance from the Road Kerb of Palm Springs Boulevard	Drawn by: TL Checked by: TC
Project: Section 16 Planning Application for Proposed Social Welfare Facility (Residential Care Home for the Elderly) in "Residential (Group C)" Zone at Palm Springs Plaza (Shop Nos. G1-G3 & G5-G8), Yuen Long, New Territories	Rev.: 1.0 Date: Jul 2026

Q:\Projects\SHKPS-EHEI00\05 Assessments\01 Air\AQIA_v1.0.dwg




Figure: 3.1	RAMBOLL
Title: Location of Nearest Air Sensitive Uses	Drawn by: TL Checked by: TC
Project: Section 16 Planning Application for Proposed Social Welfare Facility (Residential Care Home for the Elderly) in "Residential (Group C)" Zone at Palm Springs Plaza (Shop Nos. G1-G3 & G5-G8), Yuen Long, New Territories	Rev.: 1.0 Date: Jul 2026

Q:\Projects\SHKPS-EHEI00\05 Assessments\01 Air\AQIA_v1.0.dwg

Appendix 1.1 Approved General Building Plan

PHASE E
(PLANS TO BE SUBMITTED SEPARATELY)

STAGE 2 | STAGE 1

A B C D E F G H I J K L M N O P Q R S T U V W X Y Z

5000 5000 5000 5000 5000 5000 5000 5000 5000 5000 5000 5000 5000 5000 5850 2850 5000 5000 5000 5000 5000 5000 5000 5000 5600 5000 5000

10 9 8 7 6 5 4 3 2 1

ACCESS ROAD (11 m WIDE)

FOOTPATH (2.75m WIDE)

CARPARK SPACE (11000 x 3500E)

SUPERMARKET

TRANSFORMER RM. (capacity =1,500 KVA)

LOADING/UNLOADING AREA

SHOPS

ARCADE

COURTYARD

RESTAURANT

KITCHEN

REFUSE RM.

PLANTER

PAVEMENT

MINI-BUS TERMINAL

LANDSCAPING AREA

BOUNDARY LINE

ACCESS ROAD (12.8 m WIDE)

FOOTPATH (2.75m WIDE)

MM2 838 574 34N 823 673 67E

MM3 838 539 43N 823 693 45E

MM4 838 55' 823 69'

MM5 838 519 43N 823 693 45E

MM6 838 519 92N 823 670 37E

128.02 m

51.96

R6100

R7800

96.88

91.65

134.33

CARPARK LAYOUT PLAN (TO BE READ WITH REF CARPARK LAYOUT DWG No. 207)

GROUND FLOOR PLAN

THIS IS A TRUE COPY OF THE PLAN SUBMITTED BY MA KIM SEE AUTHORIZED PERSON, AND APPROVED BY THE BUILDING AUTHORITY ON 5 AUG 1994
DATED
B. L. D. REF. 2/9024/90
AUTHORIZED PERSON

NOTES:
1. ALL PIPEWORK TO BE ENCLOSED IN FALSE CEILING, OR CONCEALED INSIDE COLUMN, WALL WHEREVER PRACTICABLE.

RECORD PLAN

RECEIVED BY BUILDING DEPARTMENT 2 12 PM MAY 24 1994

B.L.D. REFERENCE 2/9024/90
F.S.D. REFERENCE 8/21357
W.W.O. REFERENCE

NO.	REVISIONS / NOTES	DATE	BY
A	GENERAL REVISION AS PER LATEST ARCH. PLAN	1/94	ST.
B	GENERAL REVISION TO SUIT SITE SITUATION	6/94	TC.
C	DRAINAGE LAYOUT REVISED AT ENTRANCE PLAZA	3/94	TC
D	DRAINAGE LAYOUT AT ENTRANCE PLAZA HAS BEEN REVISED	4/94	ST
E	STAGE 2 DRAINAGE LAYOUT HAS BEEN GENERALLY REVISED	7/94	TC

ARCHITECT
MA LEUNG & ASSOCIATES ARCHITECTS & ENGINEERS (HONG KONG) LTD. 馬黎理查顧問工程師(香港)有限公司

PLANNING & LANDSCAPE CONSULTANT
URBIS Urbis Travers Morgan Limited

CIVIL & STRUCTURAL CONSULTANT
何田建築工程師有限公司 HO TIN & ASSOCIATES ARCHITECTS ENGINEERS LIMITED

E & M CONSULTANT
CONSOLIDATED CONSULTING ENGINEERS LTD. 幸益顧問工程師有限公司

PROJECT
WO SHANG WAI DEVELOPMENT PHASE I

21 NOV 1994


ALL MEASUREMENT MUST BE CHECKED AT THE WORK BY THE CONTRACTOR

DO NOT SCALE DRAWINGS

ALL PRINTS SPECIFICATIONS AND THEIR COPYRIGHT ARE THE PROPERTY OF THE ARCHITECTS AND SHALL BE RETURNED AT THE COMPLETION OF THE WORK

DRAINAGE LAYOUT FOR GROUND FLOOR (COMMERCIAL CENTRE)

SCALE	DATE
1 : 200	SEPT, 92
DRAWN BY	CHECKED BY
JOB NO. CCE 484/CC/	DRAWING NO. D-6 REV. E.



FIRST FLOOR PLAN

1 : 200

SUPERIMPOSED LOAD = 4kPa
AUTOMATIC SPRINKLER SYSTEM TO BE PROVIDED

NOTES :

1. ALL PIPEWORK TO BE ENCLOSED IN FALSE CEILING, OR CONCEALED INSIDE COLUMN, WALL WHEREVER PRACTICABLE.

RECEIVED BY
Nov 24 2 12 PM '94
B.D.(K&N) DEPARTMENT

THIS IS A TRUE COPY OF THE PLAN SUBMITTED BY MA KIM BEE AUTHORIZED PERSON, AND APPROVED BY THE BUILDING AUTHORITY
DATED 5 AUG 1994
B. L. D. REF. 2/9024/90
AUTHORIZED PERSON

RECORD PLAN

B.L.D. REFERENCE
2/9024/90
F.S.D. REFERENCE
8/21357
W.W.O. REFERENCE

NO.	REVISIONS / NOTES	DATE	BY
A	GENERAL REVISION AS PER LATEST ARCH. PLAN	1/94	ST
B	GENERAL REVISION TO SUIT SITE SITUATION	6/94	TC
C	STAGE 2 DRAINAGE LAYOUT HAS BEEN GENERALLY REVISED	5/94	ST
D	STAGE 2 DRAINAGE LAYOUT HAS BEEN GENERALLY REVISED	7/94	TC

ARCHITECT

MA LEUNG & ASSOCIATES
ARCHITECTS & ENGINEERS (HONG KONG) LTD.
馬慧德機師事務所(香港)有限公司

PLANNING & LANDSCAPE CONSULTANT

URBIS Urbis Baron Morgan Limited 城市策劃有限公司

CIVIL & STRUCTURAL CONSULTANT

何田建築工程師有限公司
HO TIN & ASSOCIATES
ARCHITECTS ENGINEERS LIMITED

E & M CONSULTANT

CONSOLIDATED CONSULTING ENGINEERS LTD.
集益顧問工程師有限公司

PROJECT

WO SHANG WAI DEVELOPMENT PHASE I

21 NOV 1994

ALL MEASUREMENT MUST BE CHECKED AT THE WORK BY THE CONTRACTOR

DO NOT SCALE DRAWINGS

ALL PRINTS SPECIFICATIONS AND THEIR COPYRIGHT ARE THE PROPERTY OF THE ARCHITECTS AND SHALL BE RETURNED AT THE COMPLETION OF THE WORK

DRAINAGE LAYOUT FOR FIRST FLOOR (COMMERCIAL CENTRE)

SCALE	DATE
1 : 200	SEPT, 92
DRAWN BY	CHECKED BY
JOB NO	DRAWING NO / REV.
CCE484/CC/	D / D