

## **Annex A**

---

*Updated Report of the Traffic Impact Assessment*

**PROPOSED RESIDENTIAL DEVELOPMENT AT LOT NO. 4822  
IN D.D. 104 AND ADJOINING GOVERNMENT LAND, EAST  
OF KAM POK ROAD, MAI PO, YUEN LONG**

**TRAFFIC IMPACT ASSESSMENT**



## CONTENTS

	PAGE NO.
<b>1. INTRODUCTION</b>	<b>1</b>
<b>1.1 BACKGROUND</b>	<b>1</b>
<b>1.2 STUDY OBJECTIVES</b>	<b>1</b>
<b>1.3 REPORT STRUCTURE</b>	<b>1</b>
<b>2. PROPOSED DEVELOPMENT</b>	<b>2</b>
<b>2.1 SITE LOCATION</b>	<b>2</b>
<b>2.2 DEVELOPMENT PARAMETERS</b>	<b>2</b>
<b>2.3 VEHICULAR ACCESS ARRANGEMENT</b>	<b>2</b>
<b>2.4 INTERNAL TRANSPORT FACILITY</b>	<b>2</b>
<b>3. TRAFFIC CONTEXT</b>	<b>4</b>
<b>3.1 SURROUNDING ROAD NETWORK</b>	<b>4</b>
<b>3.2 EXISTING TRAFFIC CONDITION</b>	<b>4</b>
<b>3.3 EXISTING PUBLIC TRANSPORT SERVICES</b>	<b>6</b>
<b>4. TRAFFIC FORECASTING</b>	<b>7</b>
<b>4.1 DESIGN YEAR</b>	<b>7</b>
<b>4.2 TRAFFIC FORECAST</b>	<b>7</b>
<b>5. TRAFFIC IMPACT ASSESSMENT</b>	<b>15</b>
<b>5.1 TRAFFIC IMPACT ASSESSMENT</b>	<b>15</b>
<b>5.2 SENSITIVITY TEST 1</b>	<b>19</b>
<b>5.3 PEDESTRIAN ASSESSMENT</b>	<b>21</b>
<b>6. SUMMARY &amp; CONCLUSION</b>	<b>23</b>
<b>6.1 SUMMARY</b>	<b>23</b>
<b>6.2 CONCLUSION</b>	<b>23</b>

**APPENDIX A – SWEPT PATH ANALYSIS AT THE PROPOSED VEHICULAR ACCESSES**

**APPENDIX B – PRELIMINARY DIRECTIONAL SIGN AT EGRESS OF THE DEVELOPMENT**

**APPENDIX C – PRELIMINARY PHASING PLAN OF SAN TIN TECHNOPOLE**

**APPENDIX D – PRELIMINARY PHASING PLAN OF NGAU TAU MEI NEW DEVELOPMENT AREA**

**APPENDIX E – JUNCTION CALCULATION SHEETS**

**APPENDIX T1 – POTENTIAL PICK-UP/DROP-OFF LOCATION FOR BUS/SHUTTLE BUS**

## TABLES

Table No.	Title	Page No.
Table 2.1	Key Development Parameters	2
Table 2.2	Proposed Internal Transport Facility Provisions	3
Table 3.1	Identified Local Key Junctions and Road Links	4
Table 3.2	Current Junction Operational Performance	5
Table 3.3	Current Road Link Operational Performance	5
Table 3.4	Existing Public Transport Services	6
Table 4.1	Estimated Trip Generations of Planned/Committed Developments	8
Table 4.2	Trip Rates of Kindergarten	10
Table 4.3	Adopted Trip Rates	10
Table 4.4	Estimated Trip Generation of Proposed Development	11
Table 4.5	Anticipated Peak-Hour Pedestrian Trips of the Proposed development	11
Table 4.6	Transport Modal Split of Yuen Long District	12
Table 4.7	Transport Modal Split of Proposed Development	12
Table 4.8	Transport Modal Split of Proposed Development	13
Table 4.9	Comparison of 2019-based and 2021-based TPEDM Planning Assumptions	14
Table 5.1	Junction Operational Performance at Year 2034	16
Table 5.2	Year 2034 Road Link Operational Performance for Reference Case and Design Case	16
Table 5.3	Year 2034 Queue Length Assessment for Reference Case and Design Case	17
Table 5.4	Year 2034 Junction Operational Performance with Proposed Improvement Scheme	18
Table 5.5	Estimated Trip Generations of Potential Residential Developments	19
Table 5.6	Junction Operational Performance at Year 2034 under Sensitivity Test 1	19
Table 5.7	Year 2034 Road Link Operational Performance for Design Case under Sensitivity Test 1	20
Table 5.8	Year 2034 Junction Operational Performance with Suggested Improvement Scheme	21
Table 5.9	Observed Pedestrian Flows during Peak Hours	21
Table 5.10	Estimated Pedestrian Trips during Peak Hours	21

## DRAWINGS

<b>Fig. No.</b>	<b>Title</b>	<b>Following Page No.</b>
1.1	Site Location	1
2.1	Master Layout Plan	3
3.1	Major Ingress and Egress Routes	6
3.2	Identified Key Junctions and Links	6
3.3	Existing Junction Layout of Fairview Park Interchange (J1)	6
3.4	Existing Junction Layout of Kam Pok Road / Fairview Park Boulevard (J2)	6
3.5	Existing Junction Layout of Kam Pok Road / Vehicular Bridge – South (J3)	6
3.6	Existing Junction Layout of Kam Pok Road / Vehicular Bridge – North (J4)	6
3.7	Existing Junction Layout of Kam Pok Road / Ha Chuk Yuen Road (J5) and Kam Pok Road / Castle Peak Road – Tam Mi (J6)	6
3.8	Existing Junction Layout of Kam Pok Road / Fung Chuk Road (J7)	
3.9	Year 2025 Observed Traffic Flows	6
3.10	Existing Public Transport Services	6
4.1	Locations of the Planned/Committed Developments	14
4.2	Year 2034 Reference Traffic Flows	14
4.3	Development Traffic Flows (net increase)	14
4.4	Year 2034 Design Traffic Flows	14
5.1	Planned Junction Improvement Layout of Fairview Park Interchange (J1)	22
5.2	Planned Junction Improvement Layout of Kam Pok Road / Vehicular Bridge – North / Vehicular Access (J4)	22
5.3	Planned Junction Improvement Layout of Kam Pok Road / Castle Peak Road – Tam Mi (J6)	22
5.4	Proposed Junction Improvement Layout of Fairview Park Interchange (J1)	22
5.5	Proposed Junction Improvement Layout of Kam Pok Road / Castle Peak Road – Tam Mi (J6)	22
5.6	Locations of Potential Developments	22
5.7	Year 2034 Design Traffic Flows (Sensitivity Test 1)	22
5.8	Suggested Junction Improvement Layout of Fairview Park Interchange (J1)	22
5.9	Identified Footpaths	22

## 1. INTRODUCTION

### 1.1 Background

1.1.1 The application site comprises lot No. 4822 in D.D. 104 and adjoining government Land, east Kam Pok Road, Mai Po, Yuen Long, as indicated in **Drawing 1.1**. It falls within an area zoned as “Residential (Group D)” on the Approved Mai Po and Fairview Park Outline Zoning Plan No. S/YL-MP/8.

1.1.2 The application site is the subject of a previous approved Section 16 planning application (No. A/YL-MP/287) for a residential development of 65 houses (Approved Scheme). The Applicant proposes to increase its domestic plot ratio from 0.2 to 1.5. Under the current scheme, the proposed development will provide 5 medium-rise residential blocks with total 1,303 units, a 6-classroom kindergarten and a Neighbourhood Elderly Centre (“NEC”).

1.1.3 MVA Hong Kong Limited has been commissioned by the Applicant to carry out a traffic impact assessment to assess the traffic impact for the proposed residential development to support this rezoning application.

### 1.2 Study Objectives


1.2.1 The objectives of this study are summarised as follows:

- review the current traffic condition and circulation pattern in the adjacent local road network;
- review the proposed development schedule;
- produce future traffic forecasts on the adjacent local road network with considerations of the planned developments in the vicinity; and
- investigate the traffic impact on the adjacent local road network with operation of the proposed development at Design Year, including the cumulative traffic impact induced by the proposed/potential residential developments in the locality.

### 1.3 Report Structure

1.3.1 Following this introductory chapter, there are five further chapters:

- **Chapter 2 – Proposed Development**, presents the development parameters and the internal transport provisions of the proposed scheme;
- **Chapter 3 – Traffic Context**, describes the current traffic condition in the vicinity;
- **Chapter 4 – Traffic Forecasting**, describes the methodology of traffic forecasting exercise and presents the results;
- **Chapter 5 – Traffic Impact Assessment**, presents the assessment findings of the anticipated traffic condition upon occupation of the proposed development, and suggests, if necessary, improvement measures to alleviate the foreseeable traffic problem;
- **Chapter 6 –Conclusion**, summarises the study findings and presents the conclusion accordingly.



-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-
Rev.	Description	Checked	Date	Rev.	Description	Checked	Date

Project Title

PROPOSED RESIDENTIAL DEVELOPMENT AT LOT NO. 4822 IN D.D.104 AND  
ADJOINING GOVERNMENT LAND, EAST OF KAM POK ROAD, MAI PO, YUEN LONG

Drawing Title

**SITE LOCATION**

Designed	HZF	Checked	PTC	Scale	NTS	Date	JUN 2025	Drawing No.	1.1	Rev.	-
----------	-----	---------	-----	-------	-----	------	----------	-------------	-----	------	---

## 2. PROPOSED DEVELOPMENT

### 2.1 Site Location

2.1.1 As indicated in **Drawing 1.1**, the application site is bounded by Kam Pok Road to its west, Fung Chuk Road to its north, Ha Chuk Yuen Road to its east and Ha San Wai Road to its south.

### 2.2 Development Parameters

2.2.1 The application site has a total land area of about 37,870m<sup>2</sup>. It will be developed into a medium-rise residential development of about 1,303 units with an average flat size of about 43.6m<sup>2</sup>. Comparison on the key development parameters between the approved and proposed schemes are summarized in **Table 2.1**. The proposed scheme is anticipated to complete in year 2031. The Master Layout Plan (MLP) is illustrated in **Drawing 2.1** respectively.

**Table 2.1 Key Development Parameters**

Item	Approved Scheme (A/YL-MP/287)	Proposed Scheme
Domestic Plot Ratio	0.2	1.5
Domestic GFA	7,540.4m <sup>2</sup>	56,805m <sup>2</sup>
No. of Unit	65 house	1,303 flats
Average flat Size (GFA)	about 116 m <sup>2</sup>	about 43.6 m <sup>2</sup>
Kindergarten	-	a 6-classroom kindergarten
GIC	-	a NEC

### 2.3 Vehicular Access Arrangement

2.3.1 The vehicular access arrangements in the current proposed scheme basically follow the approved scheme and those under the present government lease of the application site. Two vehicular accesses are proposed for the proposed development. The vehicular access at Kam Pok Road is the main access for residential use and kindergarten. Whilst, the second vehicular access at Ha Chuk Yuen Road is reserved for the proposed NEC and other serving vehicle. The locations of these two proposed vehicular accesses are illustrated in **Drawing No. 2.1**.

2.3.2 Currently, vehicles exceeding 7m in length are prohibited from accessing Ha Chuk Yuen Road. Swept path analysis for a 12.8m long vehicle and a 7m long vehicle have been conducted at the main entrance and second entrance respectively in **Appendix A**. The result demonstrated that sufficient manoeuvring space has been provided for vehicles turning into and out from the proposed vehicular accesses.

2.3.3 Considering Fairview Park Boulevard is a private road, a directional sign will be provided at the development egress within the site to alert drivers to avoid using the private road to access Fairview Park Interchange as shown in **Appendix B**.

### 2.4 Internal Transport Facility

2.4.1 The proposed development would be provided with internal transport facilities in accordance with the latest Hong Kong Planning Standards and Guidelines (HKPSG) and the comments from Transport Department. The proposed provisions are summarised in **Table 2.2**.

**Table 2.2 Proposed Internal Transport Facility Provisions**


Item	High-end of HKPSG Requirements				Parameters	Provision (nos.)
<b>Residential Development</b>						
Private Car	GPS <sup>(1)</sup>	R1 <sup>(1)</sup>		R2 <sup>(1)</sup>	R3 <sup>(1)</sup>	
	1 space per 4 units	FS ≤ 40m <sup>2</sup>	0.5	1	1.1	407 units 896 units
Visitor Parking	40m <sup>2</sup> < FS ≤ 70m <sup>2</sup>					296
Visitor Parking	5 spaces for each block with more than 75 units				5 blocks	25
					Total	377 <sup>(2)</sup>
Motorcycle Parking	1 space per 10 residential car parking spaces <sup>(3)</sup>				352 spaces	36
HGV Loading/ Unloading Bays	1 bay per residential block				5 blocks	5
Bicycle Parking Space	1 space per 7.5 flats <sup>(3)</sup>				1,303 units	174
<b>Kindergarten</b>						
Private Car	1 space per 4 classrooms				6 classrooms	2
Lay-by for taxis and Private Car	1 for every 5 classrooms				6 classrooms	2
Lay-by for school buses	5 lay-bys of size 3m x 7m for mini-bus/nanny van				-	5 lay-bys of size 3m x 7m

Remarks:

- (1) Parking Requirement = GPS x R1 x R2 x R3, where GPS = 1 car space per 4 flats, R1=1.2 for flat size 40m<sup>2</sup> < FS ≤ 70m<sup>2</sup>, R2=1 for the site outside a 500-radius of rail station, R3=1.1 for domestic plot ratio 1<PR≤2.
- (2) Minimum 5 accessible parking spaces will be reserved for persons with disabilities with reference to HKPSG (at least 1 space for visitor parking).
- (3) Based on the comments from TD.

2.4.2 The proposed NEC would mainly serve local residents. Nil parking provision is proposed for NEC with reference to the recently agreed rezoning application (No. Y/YL-MP/10) nearby.

2.4.3 Under the current MLP, the residential carpark would be located in the basement, whilst the loading/unloading bays would be located on the ground floor level along 7.3m wide main internal driveway. For kindergarten carpark and drop-off area, it would be located on ground floor level at the southern end of the main driveway, which will not cause potential traffic queue back onto Kam Pok Road.



-	-	-	Project Title
-	-	-	Drawing Title
-	-	-	MASTER LAYOUT PLAN
A MINOR AMENDMENT	PTC	04DEC25	Designed HZF Checked PTC Scale 1:1000(A3) Date JUN 2025 Drawing No. 2.1 Rev. A

Description

Checked

Date

### 3. TRAFFIC CONTEXT

#### 3.1 Surrounding Road Network

- 3.1.1 With the traffic management measure as described in **Section 2.3.3**, the development traffic from San Tin Highway would access the site via Castle Peak Road – Tam Mi Section and Kam Pok Road. The major ingress and egress routes of the application site are illustrated in **Drawing 3.1**.
- 3.1.2 Kam Pok Road is a standard single-two lane carriageway of 7.3m wide with a 2m wide footpath along its eastern side. It mainly serves the local developments in the vicinity.
- 3.1.3 Ha Chuk Yuen Road and Fung Chuk Road are single track access roads. Vehicles exceeding 7m in length are prohibited from accessing these roads.
- 3.1.4 Fairview Park Boulevard is a dual 2-lane carriageway. It connects the traffic from San Tin Highway to the local developments including Fairview Park.

#### 3.2 Existing Traffic Condition

- 3.2.1 A total of **seven** local junctions and **six** road links have been identified with reference to the major ingress and egress routes of the proposed development for assessment purposes. The key local junctions are listed in **Table 3.1**, whilst their locations are indicated in **Drawing 3.2**.

**Table 3.1 Identified Local Key Junctions and Road Links**

Ref. <sup>(1)</sup>	Junction	Type	Drawing No.
<b>Junction</b>			
J1	Fairview Park Interchange	Roundabout	3.3
J2	Fairview Park Boulevard / Kam Pok Road	Signal	3.4
J3	Kam Pok Road / Vehicular Bridge (South)	Signal	3.5
J4	Kam Pok Road / Vehicular Bridge (North)	Signal	3.6
J5	Kam Pok Road / Ha Chuk Yuen Road	Priority	3.7
J6	Castle Peak Road / Kam Pok Road	Priority	3.7
J7	Kam Pok Road / Fung Chuk Road	Priority	3.8
<b>Road Link</b>			
L1	Castle Peak Road – Tam Mi	Single-2	3.2
L2	Fairview Park Boulevard	Dual-2	3.2
L3	Kam Pok Road	Single 2	3.2
L4	Fung Chuk Road	Single track	3.2
L5	Ha Chuk Yuen Road	Single track	3.2
L6	San Tin Highway	Dual-3	3.2

Remark: (1) Locations refer to **Drawing 3.2**.

#### *Traffic Surveys*

- 3.2.2 A manual classified traffic survey was conducted at the identified junctions and road links to establish the current traffic condition in the vicinity of the site. The survey was carried out during 07:30-09:30 and 17:00-19:00 in the morning and evening peak hour periods on a typical weekday in April 2025.

3.2.3 The results of the survey have indicated that the morning and evening peak hours occur during 08:00 – 09:00 and 17:45 – 18:45 respectively. Based on the survey result, the year 2025 peak-hour traffic flows are shown in **Drawing 3.9**.

### Junction Operational Performance

3.2.4 Junction capacity assessments have been conducted to evaluate the current operational performance of the identified junctions. The assessment results are summarised in **Table 3.2**.

**Table 3.2 Current Junction Operational Performance**

Ref. (1)	Junction	Type	RC/RFC <sup>(2)</sup>	
			AM Peak	PM Peak
J1	Fairview Park Interchange	Roundabout	0.56	0.55
J2	Fairview Park Boulevard / Kam Pok Road	Signal	85%	69%
J3	Kam Pok Road / Vehicular Bridge (South)	Signal	>100%	>100%
J4	Kam Pok Road / Vehicular Bridge (North)	Signal	>100%	>100%
J5	Kam Pok Road / Ha Chuk Yuen Road	Priority	0.05	0.05
J6	Castle Peak Road / Kam Pok Road	Priority	0.13	0.12
J7	Kam Pok Road / Fung Chuk Road	Priority	0.01	0.01

Remarks: (1) Refer to **Drawing 3.2** for junction locations.

(2) RC = reserved capacity for signal junction, RFC = ratio-of-flow to capacity for roundabout/priority junction.

3.2.5 The assessment results in **Table 3.2** indicated that all the identified key junctions are currently operating within capacities during peak hours.

### Road Link Operational Performance

3.2.6 Besides, road link assessments have also been conducted to evaluate the current operational performance of the identified links. The Volume to Capacity (V/C) ratios of each identified road links have been evaluated and the results are summarised in **Table 3.3**.

**Table 3.3 Current Road Link Operational Performance**

Ref. <sup>(1)</sup>	Road Link	Dir	Link Capacity (pcu/hr)	Observed Flows (pcu/hr)		V/C Ratio	
				AM	PM	AM	PM
L1	Castle Peak Road – Tam Mi	Two-way	2,125 <sup>(2)</sup>	895	720	0.42	0.34
L2	Fairview Park Boulevard	EB	2,600 <sup>(3)</sup>	870	675	0.33	0.26
		WB	2,600 <sup>(3)</sup>	575	805	0.22	0.31
L3	Kam Pok Road	Two-way	1,800 <sup>(4)</sup>	145	135	0.08	0.08
L4	Fung Chuk Road	Two-way	100 <sup>(5)</sup>	5	10	0.05	0.1
L5	Ha Chuk Yuen Road	Two-way	100 <sup>(5)</sup>	5	10	0.05	0.1
		NB	6,100 <sup>(6)</sup>	4905	4985	0.80	0.82
L6	San Tin Highway	SB	6,100 <sup>(6)</sup>	5080	4595	0.83	0.75

Remarks: (1) Refer to **Drawing 3.2**.

(2) Road capacity for single 2-lane rural road, with consideration of roadside activities.

(3) Road capacity for dual-2 lane local distributor.

(4) Road capacity for single-2 lane local distributor.

(5) Road capacity for single-track access road.

(6) Road capacity for dual-3 lane trunk road.

3.2.7 The assessment results in **Table 3.3** indicated that all the identified sections are currently operating within capacities.

### 3.3 Existing Public Transport Services

3.3.1 Franchised bus and minibus are the major public transport services in the vicinity of the site. The nearby public transport facilities of the site are indicated in **Drawing 3.10**, whilst the details and servicing schedules are summarised in **Table 3.4**.

**Table 3.4 Existing Public Transport Services**

Route	Origin/Destination	Frequency (min.)	Remark
<b>Franchised Bus</b>			
76 <sup>(1)</sup>	Yau Pok Road Public Housing (South) Terminus <-> Sheung Shui Station (Choi Yuen Road)	30	Circular Route
76K	Ching Ho Estate <-> Long Ping Estate	20-30	-
268 <sup>(1)</sup>	Yau Pok Road Public Housing (South) Terminus <-> Pat Heung Road	30-35	
976	Lok Ma Chau (San Tin) <-> Sai Wan Ho	-	Monday to Friday (except public holidays); From Lok Ma Chau (San Tin): 06:25, 07:15, 07:45 From Sai Wan Ho: 18:10, 18:40, 19:10
976A	Lok Ma Chau (San Tin) <-> Siu Sai Wan (Island Resort)	-	Monday to Friday (except public holidays); From Lok Ma Chau (San Tin): 06:55 From Siu Sai Wan (Island Resort): 17:30
<b>Green Minibus</b>			
36	Yuen Long (Fook Hong St) <-> Tai Sang Wai	15-20	-
36A <sup>(1)</sup>	Yuen Long (Fook Hong Street) <-> Yau Pok Road Light Public Housing	20	Evening Departures (omits Kik Yeung Road);
37	Yuen Long (Fook Hong St) <-> Yau Tam Mei	15-20	-
38	Yuen Long (Fook Hong St) <-> Tai Sang Wai (W)	15-20	-
75	Yuen Long (Fook Hong Street) <-> Lok Ma Chau Spur Line Public Transport Interchange	15-30	-
76	Yuen Long (Fook Hong Street) <-> Siu Hum Tsuen	15-20	-


Remark: (1) The routes were introduced for temporary Light Public Housing at Yau Pok Road.

**LEGEND :**

- APPLICATION SITE
- INGRESS ROUTING
- EGRESS ROUTING
- ▲ MAIN VEHICULAR ACCESS



Fairview Park



-	-	-	-	-	-	-	-
A	TRAFFIC ROUTE UPDATED	PTC	9DEC25	-	-	-	-
Rev.	Description	Checked	Date	Rev.	Description	Checked	Date

Project Title

PROPOSED RESIDENTIAL DEVELOPMENT AT LOT NO. 4822 IN D.D.104 AND  
ADJOINING GOVERNMENT LAND, EAST OF KAM POK ROAD, MAI PO, YUEN LONG

Drawing Title


**MAJOR INGRESS AND EGRESS ROUTES**

Designed	HZF	Checked	PTC	Scale	NTS	Date	JUN 2025	Drawing No.	3.1	Rev.	A
----------	-----	---------	-----	-------	-----	------	----------	-------------	-----	------	---


CHK50868310/TIA/F31-A.CDR/LLH/9DEC25

**SYSTRA**  
MVA

Original Size : A4



-	-	-	-	-	-	-	-
A	MINOR AMENDMENT	PTC	19DEC25	-	-	-	-
Rev.	Description	Checked	Date	Rev.	Description	Checked	Date
Project Title							
PROPOSED RESIDENTIAL DEVELOPMENT AT LOT NO. 4822 IN D.D.104 AND ADJOINING GOVERNMENT LAND, EAST OF KAM POK ROAD, MAI PO, YUEN LONG							
Drawing Title							
<b>IDENTIFIED KEY JUNCTIONS AND ROAD LINKS</b>							
Designed	HZF	Checked	PTC	Scale	NTS	Date	JUN 2025
						Drawing No.	<b>3.2</b>
						Rev.	A




Rev.	Description	Checked	Date	Rev.	Description	Checked	Date
-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-


Project Title  
PROPOSED RESIDENTIAL DEVELOPMENT AT LOT NO. 4822 IN D.D. 104 AND  
ADJOINING GOVERNMENT LAND, EAST OF KAM POK ROAD, MAI PO, YUEN LONG

Drawing Title

## EXISTING JUNCTION LAYOUT OF FAIRVIEW PARK INTERCHANGE (J1)

Designed	HZF	Checked	PTC	Scale	1:1500(A4)	Date	JUN 2025	Drawing No.	3.3	Rev.	-
----------	-----	---------	-----	-------	------------	------	----------	-------------	-----	------	---






Rev.	Description	Checked	Date	Rev.	Description	Checked	Date	Rev.	Description	Checked	Date
Project Title											
Drawing Title											
Designed	HZF	Checked	PTC	Scale	1:500(A4)	Date	JUN 2025	Drawing No.	<b>3.5</b>	Rev.	-


PROPOSED RESIDENTIAL DEVELOPMENT  
 AT LOT NO. 4822 IN D.D. 104 AND ADJOINING  
 GOVERNMENT LAND, EAST OF KAM POK ROAD,  
 MAI PO, YUEN LONG

## EXISTING JUNCTION LAYOUT OF KAM POK ROAD / VEHICULAR BRIDGE - SOUTH (J3)


**SYSTRA**  
 MVA



-	-	-	-	-	-	-	-	-	-	-	-
Rev.	Description	Checked	Date	Rev.	Description	Checked	Date	Rev.	Description	Checked	Date
Project Title				Drawing Title							
PROPOSED RESIDENTIAL DEVELOPMENT AT LOT NO. 4822 IN D.D. 104 AND ADJOINING GOVERNMENT LAND, EAST OF KAM POK ROAD, MAI PO, YUEN LONG				<b>EXISTING JUNCTION LAYOUT OF KAM PO ROAD / VEHICULAR BRIDGE - NORTH (J4)</b>							
Designed	HZF	Checked	PTC	Scale	1:500(A4)	Date	JUN 2025	Drawing No.	<b>3.6</b>	Rev.	-



Project Title	Drawing Title						Drawing No.	Rev.
Designed	Checked	Scale	Date	3.7	Original Size : A3			
PROPOSED RESIDENTIAL DEVELOPMENT AT LOT NO. 4822 IN D.D. 104 AND ADJOINING GOVERNMENT LAND, EAST OF KAM POK ROAD, MAI PO, YUEN LONG	HZF	PTC	1:500(A3)	JUN 2025				
Rev. Description	Checked	Date						




Rev.	Description	Checked	Date	Rev.	Description	Checked	Date	Rev.	Description	Checked	Date
Project Title											
Drawing Title											
Designed	HZF	Checked	PTC	Scale	1:500(A4)	Date	DEC 2025	Drawing No.	<b>3.8</b>	Rev.	-

PROPOSED RESIDENTIAL DEVELOPMENT AT  
 LOT NO. 4822 IN D.D. 104 AND  
 ADJOINING GOVERNMENT LAND,  
 EAST OF KAM POK ROAD, MAI PO, YUEN LONG


## EXISTING JUNCTION LAYOUT OF KAM POK ROAD / FUNG CHUK ROAD (J7)

**SYSTRA**  
 MVA



### YEAR 2025 OBSERVED TRAFFIC FLOWS

Designed	HZF	Checked	PTC	Scale	NTS	Date	DEC 2025	Drawing No.	3.9	Rev.	-
----------	-----	---------	-----	-------	-----	------	----------	-------------	-----	------	---



Rev.	Description	Checked	Date	Rev.	Description	Checked	Date
-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-

Project Title	Checked	Date	Rev.	Description	Checked	Date
PROPOSED RESIDENTIAL DEVELOPMENT AT LOT NO. 4822 IN D.D.104 AND ADJOINING GOVERNMENT LAND, EAST OF KAM POK ROAD, MAI PO, YUEN LONG						

Drawing Title	EXISTING PUBLIC TRANSPORT SERVICES						SYSTRA MVA
Designed HZF	Checked PTC	Scale NTS	Date DEC 2025	Drawing No.	3.10	Rev. -	

## 4. TRAFFIC FORECASTING

### 4.1 Design Year

4.1.1 The tentative completion year of the proposed development is year 2031. Hence, the design year of 2034 three years upon operation of the proposed development, has been adopted for traffic forecast and assessment purposes.

### 4.2 Traffic forecast

#### Toll Plans Changes for Tai Lam Tunnel

4.2.1 The Government has taken over the Tai Lam Tunnel on 31 May 2025 and implemented new tolls with substantially reduced tolls for all vehicle types. With reference to the preliminary traffic assessment under Legislative Council paper No. CB(1)976/2024(05), it is anticipated that some traffic flows at Tolo Highway (Tai Po Kau section) would be diverted onto Tai Lam Tunnel upon Government's takeover. With reference to the result of the above-mentioned assessment, adjustment due to new tolls has been applied into the traffic forecast to reflect the situation accordingly.

#### Effect of Northern Link (NOL)

4.2.2 The planned NOL Main Line will be an railway of about 10.7km long, connecting the existing Kam Sheung Road Station of the Tuen Ma Line and the planned Kwu Tung Station of the East Rail Line, with three intermediate stations at San Tin, Ngau Tam Mei and Au Tau. The NOL Main Line would become the public transportation backbone in the Northern Metropolis (NM) and connect East Rail Line and Tuen Ma Line, forming a railway loop linking the New Territories and the Kowloon urban areas. The NOL Main Line is anticipated for commissioning in Year 2034. The impact of NOL has been considered in the 2-tier model from nearby approved planning application, Y/YL-MP/10.

#### Effect of Northern Metropolis (NM) Highway

4.2.3 The planned NM Highway is a major east-west corridor of about 24 km long, linking the development nodes in the NM including Ngau Tam Mei, San Tin Technopole, Kwu Tung North/Fanling North and New Territories North New Town. Upon commissioning of the NM Highway, it would divert traffic flows between the New Territories East and West during peak hours, thereby alleviating the traffic pressure on existing major highways, in particular for San Tin Highway.

4.2.4 The San Tin Section of NM Highway is expected to be commissioned in Year 2036 while its remaining sections are expected to be commissioned in 2039 and beyond. As the NM Highway will be commissioned after the design year 2034, the impact of NM has not been reflected in the traffic forecast. Nevertheless, the existing road and junction performance is expected to be improved significantly after its commissioning.

#### Adjacent Planned/Committed Developments

- *San Tin Technopole*

4.2.5 San Tin Technopole, located at the core of the NM, is planned as a hub for clustered innovation and technology development in the San Tin area. According to the preliminary phasing plan under the relevant government study (**Appendix C**), the project is planned to be implemented in three phases – Initial Phase, Main Phase and Remaining Phase. The population intakes for

Initial Phase, Main Phase and Remaining Phase are anticipated in 2031, 2034 and 2039 respectively. Considering that the developments in Initial Phase and Main Phase would be completed on or before the design year 2034, the Year 2034 traffic forecast has been updated to include the relevant trips of San Tin Technopole.

- *Ngau Tam Mei New Development Area (NTM NDA)*

4.2.6 The NTM NDA is planned for the development of the NM University Town with integrated residential neighbourhood. The planned Ngau Tam Mei Station of NOL Main Line would be located around the integrated residential community to serve the residents in the areas. The NTM NDA is expected to be served by the planned NM Highway, San Tam Road, San Tin Highway and connected to San Tin Technopole. According to the “Land Use Review Study for Ngau Tam Mei Area – Feasibility Study” (**Appendix D**), the project is planned to be implemented in three phases – First Phase, Second Phase and Remaining Phases. The population intakes for First, Second and Remaining Phases are anticipated in 2033, 2034 and 2036 respectively. Considering that the developments in First and Second Phases would be completed on or before the design year 2034, the Year 2034 traffic forecast has been updated to include the relevant trips of NTM NDA.

- *Other Planned/Committed Developments.*

4.2.7 Apart from the above, there are other planned developments located in the vicinity of the site that are expected to be completed by year 2034 according to the latest available information from public domain. The planned/committed developments considered in the traffic forecast, together with the estimated trips of these developments are listed in **Table 4.1** Their locations are indicated in **Drawing 4.1**.

**Table 4.1 Estimated Trip Generations of Planned/Committed Developments**

Ref.	Planned/Committed Developments	Key Development Parameters	Estimated Two-way Trip Generations (pcu/hr)	
			AM Peak	PM Peak
1	Tung Shing Lei Development (A/YL-NSW/274)	• 1,518 residential units (average flat size = about 46m <sup>2</sup> )	222	151
2	Sha Po North Phase 2 Residential Development (A/YL-KTN/663)	• 1,154 residential units (average flat size = about 42.57m <sup>2</sup> )	132	76
3	Residential Development at west of Castle Peak Road - Tam Mi, Yuen Long (Y/YL-NSW/9)	• 3,115 residential units • 2,900m <sup>2</sup> retail GFA • 1 primary school, 1 kindergarten • Soy Factory	467	249
4	Kam Tin South Priority Sites Development	• 9,060 units of public housing (average flat size = about 50m <sup>2</sup> ) • 2,670 units of private housing (average flat size = about 70m <sup>2</sup> )	1326	855
5	Residential Development at west of Castle Peak Road - Tam Mi, Yuen Long (Y/YL-NSW/8)	• 6,825 residential units • 3,950m <sup>2</sup> retail GFA • 2 GIC facilities and 1 kindergarten	872	499
6	Tung Shing Lei Land Sharing Pilot Scheme Application No. LSPS/002	• 1,261 units of private housing (average flat size = about 40m <sup>2</sup> ) • 1,868 units of public housing (average flat size = about 50m <sup>2</sup> )	357	236
7	Sha Po North Comprehensive Residential Development (A/YL-KTN/604)	• 3,891 residential units (average flat size = about 49m <sup>2</sup> ) • 5,500 m <sup>2</sup> retail GFA	491	312
8	Sha Po Public Housing Development	• 16,300 Flats • 20,668m <sup>2</sup> retail GFA • 5 Kindergarten and 1 Primary School • 38,384m <sup>2</sup> Welfare Facilities • 19,267m <sup>2</sup> GIC	2,540	1,870

Ref.	Planned/Committed Developments	Key Development Parameters	Estimated Two-way Trip Generations (pcu/hr)	
			AM Peak	PM Peak
9	Kam Tin North Residential Development (A/YL-KTN/791)	• 330 flats and 87 houses (average flat/house size = about 38.73m <sup>2</sup> )	38	21
10	Residential Development at Sha Po South (A/YL-KTN/964)	• 615 residential units (average flat size = about 38m <sup>2</sup> )	78	50
11	Development at Wing Kei Tsuen, Nam Sang Wai, Yuen Long (Y/YL-NSW/7)	• 1,997 residential units (average flat size = 48.9m <sup>2</sup> )	252	157
12	Residential Development at Tung Shing Lei, Nam Sang Wai, Yuen Long (A/YL-NSW/293)	• 3,566 Flats • 9 Houses • 5,358m <sup>2</sup> Non Domestic GFA	434	272
13	Comprehensive Development Scheme at north of Kam Pok Road East, Pok Wai, Yuen Long (A/YL-NSW/314)	• 90 residential units	49	52
14	Ngau Tam Mei Area New Development Area <sup>(1)</sup>	• Integrated Hospital • UniTown • Residential Developments Sites R3 & R4	1,584	1,486
15	Social Welfare Facilities at Siu Sheung Road, Nam Sang Wai, Yuen Long (A/YL-NSW/303)	• 127 beds for Residential Care Home for the Elderly • 100 beds for senior hostel	31	27
16	Social Welfare Facilities at Siu Sheung Road, Nam Sang Wai, Yuen Long (A/YL-NSW/292)	• 9,180m <sup>2</sup> GFA	50	48
17	Residential Care Homes for the Elderly at 81 San Tam Road, Ngau Tam Mei, Yuen Long (Y/YL-NTM/9)	• 142 beds (5,400m <sup>2</sup> GFA)	20	20
18	Residential Development at Yau Pok Road, Yuen Long (Y/YL-MP/3) <sup>(2)</sup>	• 106 houses	53	49
19	Proposed Residential Development at Kam Pok Road, Yuen Long (Y/YL-MP/10)	• 2,322 residential units (average flat size = about 42.4m <sup>2</sup> ) • 2,363m <sup>2</sup> retail GFA • 1 kindergarten and 1 NEC	448	250
20	Proposed Comprehensive Development at Wo Shang Wai, Yuen Long (Y/YL-MP/9)	• 3,562 residential units (average flat size = about 75m <sup>2</sup> ) • a 100-place Residential Care Home for the elderly	644	447
21	San Tin Technopole <sup>(3)</sup>	• Information and Technology (I&T) Section of 120,000 employment • ~760,000m <sup>2</sup> Logistics & Storage and Workshop • Public housing of ~25,800 units • Private housing of ~12,200 units	10,170	7,560

Remarks:

- (1) The development schedules under First and Second Phases are assumed based on the planning assumptions in the Recommended Outline Development Plan (RODP) from the EIA report of "Land Use Review Study For Ngau Tam Mei Area – Feasibility Study"
- (2) The site is currently occupied by the existing temporary Light Public Housing at Yau Pok Road. The surveyed trip generations of Light Public Housing were separately excluded from the traffic forecast.
- (3) According to the "EIA study of First Phase Development of the New Territories North – San Tin / Lok Ma Chau Development Node – Investigation", the population intakes for Initial Phase and Main Phase are anticipated on or before 2034. The development schedules under Initial and Main Phases are assumed based on the planning assumptions in the revised RODP.

### Proposed Development Flows

4.2.8 The proposed development will provide 1,303 units with an average flat size of about 43.6m<sup>2</sup> a kindergarten and a NEC. In order to estimate the trips of the proposed development for residential portion, reference has been made to the trip rates in Transport Planning Design Manual (TPDM) published by the TD.

4.2.9 For kindergarten, a trip generation survey has been conducted at the existing similar kindergarten in Yuen Long, Saint Lorraine Kindergarten (Yuen Long) in December 2025. The surveyed trip rates are summarized in **Table 4.2**. The adopted trip rates of kindergarten under the Planning Application Y/YL-MP/10 are also listed below for comparison.

**Table 4.2 Trip Rates of Kindergarten**

	Trip Rate (pcu/hr/student)			
	AM Peak		PM Peak	
	Gen	Attr	Gen	Attr
Existing Saint Lorraine Kindergarten (Yuen Long)	8	8	1	1
Trip rates with reference to the TIA report under Planning Application Y/YL-MP/10	26	26	1	1

4.2.10 Based on **Table 4.2**, the trip rates with reference to the planning application Y/YL-MP/10 are higher and has been adopted for conservative approach. The adopted trip rates are presented in **Table 4.3**.

**Table 4.3 Adopted Trip Rates**

Use	Unit	Trip Rate			
		AM Peak		PM Peak	
		Gen	Attr	Gen	Attr
Residential <sup>(1)</sup>	(pcu/hr/flat)	0.0718	0.0425	0.0286	0.037
Kindergarten <sup>(2)</sup>	(pcu/hr/100 student)	26	26	1	1

Remarks: (1) Mean value of trip rates for Private Housing R(A) with average flat size of 60m<sup>2</sup> from TPDM is adopted.

(2) Adopted trip rates with reference to the TIA report under Planning Application Y/YL-MP/10.

4.2.11 For the proposed NEC, considering that the target group is mainly the elderly living in the locality and the corresponding peak hour would not overlap with the commuting peak hours, it is anticipated that its trip generations are limited during the commuting peak hours.

4.2.12 Based on the above adopted trips rates, the trip generations of the proposed development is estimated. **Table 4.4** summarises the estimated trip generations of the proposed scheme against the approved scheme.

**Table 4.4 Estimated Trip Generation of Proposed Development**

Scheme	Development Parameter	Estimated Trip Generations (pcu/hr)				
		AM Peak		PM Peak		
		Gen	Attr	Gen	Attr	
<b>Approved Scheme</b>	Residential <sup>(1)</sup>	65 houses	15	9	9	11
<b>Proposed Scheme</b>	Residential	1,303 units	94	55	37	48
	Kindergarten	6 classrooms	47	47	5	5
	NEC <sup>(2)</sup>		10	10	10	10
	Shuttle bus Service <sup>(3)</sup>		22	22	22	22
		<b>Total</b>	173	134	74	85
<b>Difference (Proposed Scheme – Approved Scheme)</b>			+158	+125	+65	+74

Remarks: (1) Trip generation extracted from the TIA report for the approved scheme.  
 (2) Nominal Trips.  
 (3) Shuttle bus service is proposed to serve the proposed development. Details of the shuttle bus trips refers to **Section 4.2.4**.

4.2.13 Compared to the approved scheme, the proposed scheme would generate an additional two-way trips of 283 pcu/hr and 139 pcu/hr during the morning and evening peak hour periods respectively as indicated in **Table 4.4**.

*Trips of Public Transport*

4.2.14 With reference to Travel Characteristics Survey 2011 (TCS 2011) published by TD, the pedestrian trips of the proposed development during peak hour is derived as shown in **Table 4.5**.

**Table 4.5 Anticipated Peak-Hour Pedestrian Trips of the Proposed development**

Location	Estimated Population <sup>(1)</sup> [i]	Average daily mechanized trips per person <sup>(2)</sup> [ii]	Peak hour factor <sup>(3)</sup> [iii]	Peak hour Pedestrian Trips (pax/hr) =[i] x [ii] x [iii]
Proposed Development (1,303 units)	3,519	1.83	12%	773

Remarks: (1) Adopting the average domestic household size of 2.7.  
 (2) Average daily mechanised trips per person as extracted from TCS 2011.  
 (3) Weekday morning peak hour factor for all merchandised trips of 20% as a conservative approach (with reference to TCS 2011) and peak direction split of 60% assumed (i.e. 1-way Peak hour factor = 20% x 60% = 12%).

4.2.15 Based on the calculation in **Table 4.5**, it is anticipated that the pedestrian trips of the proposed development is 773 pax/hr during peak hour.

4.2.16 To identify the transport mode shares in local area, reference has been made to the Population Census 2021 published by Census and Statistics Department. The transport modal splits of Yuen Long District are reviewed and summarized in **Table 4.6**.

**Table 4.6 Transport Modal Split of Yuen Long District**

Transport Mode	Main Mode of Transport	Modal Split <sup>(1)(2)</sup>
PT Mode (81.7%)	Mass Transit Railway (MTR/Light Rail)	48.3%
	Coach	4.1%
	Franchised Bus	25.8%
	Public light bus	3.5%
Non-PT Mode (18.3%)	Private car / Passenger van/ Taxi	11%
	On foot only	7.3%
	Total	100%

Note : (1) With reference to the data in Population Census 2021.

(2) The transport mode "Ferry/Vessel" and "Others" has been excluded from the data in the Population Census.

4.2.17 As shown in **Table 4.6**, the modal splits for PT mode is 81.7%. Considering the existing available public transport modes in the study area, the PT mode are further split to "short-haul" and "long-haul" services as summarized in **Table 4.7**.

4.2.18 By applying the derived modal splits to the estimated peak-hour pedestrian trips of the proposed development in **Table 4.5**, the pedestrian trips of the proposed development by transport mode are shown in **Table 4.7**.

**Table 4.7 Transport Modal Split of Proposed Development**

Transport Mode	Modal Split <sup>(1)</sup>	Peak-hour Pedestrian Trip of the Proposed Development
PT Mode (81.7%)	Short-Haul Service	52.4% <sup>(2)</sup>
	Long-Haul Service	29.3% <sup>(3)</sup>
Non-PT Mode		18.3%
	Total	100%
		773

Remarks:

(1) Refer to **Table 4.6**.

(2) Split of short-haul service refer to the shuttle bus to the nearby railway station, which includes the modal splits of railway and coach services.

(3) Split of long-haul service includes the modal splits of franchise bus and public light bus.

4.2.19 Based on the calculation in **Table 4.7**, it is anticipated that the PT demand of the proposed development is 632 pax/hr during peak hour.

4.2.20 According to the recently agreed rezoning application Y/YL-MP/10 nearby, a new transport layby is planned to be provided within the applicant site of Y/YL-MP/10. Under its TIA report, a long-haul bus service to/from urban areas (such as, Hong Kong Island, Kowloon and Kowloon East) and a short-haul bus service to/from Yuen Long Station PTI are proposed to serve the future public transport demand in the area. The proposed bus frequency for both short-haul and long-haul bus services are 15 veh/hr and 8 veh/hr respectively, which has taken into account of the future transport demand arising from the 3 application sites of Y/YL-MP/7, Y/YL-MP/MP/8 and Y/YL-MP/MP/10 nearby.

4.2.21 By taking into account the bus demand arising from the nearby 3 application sites, the anticipated peak-hour bus demand in the area is calculated and summarized in **Table 4.8**.

**Table 4.8 Transport Modal Split of Proposed Development**

Bus Service	Anticipated Peak-hour Bus Demand arising from the nearby application sites <sup>(1)</sup> (pax/hr)	Anticipated Peak-hour Bus Demand arising from the proposed development <sup>(2)</sup>	Total Peak-hour Bus Demand
Short-Haul Bus Service to/from Yuen Long Station PTI	1350	405	1755
Long-Haul Bus Service to/from Urban Areas	727	227	954

Remarks:

(1) Extracted from the TIA report of the approved application site Y/YL-MP/10. The nearby application sites include Y/YL-MP/7, Y/YL-MP/MP/8 and Y/YL-MP/MP/10.

(2) Refer to **Table 4.7**.

4.2.22 To cater the future public transport demand of the proposed development, enhancement of the above-mentioned short-haul and long-haul bus services are suggested. According to assessment result in **Table 4.8**, it is suggested to increase the bus trip of short-haul and long-haul bus service to 20 veh/hr and 11 veh/hr based on a bus capacity of 90 pax/hr. The actual frequency of bus services is subject to the Transport Department's review at a later stage.

4.2.23 The application site will be located about 1 km radius of future Ngau Tam Mei Station upon completion of Northern Link (NOL) project in year 2034. Apart from the above-mentioned bus services, a circular shuttle bus route travelling between the application site and the future public transport interchange near Ngau Tam Mei Station is also suggested for further enhancement. A layby for residents' shuttle bus service/potential bus service will be reserved within the site for pick-up/drop-off. The arrangement of the shuttle bus service is subject to the future application to TD and the future bus route plan in the area.

4.2.24 Under the traffic forecast, the trips of the shuttle bus service has been included in the traffic forecast to present the conservative approach. By adopting the occupancy of 60 persons/coach, an additional trip of 11 coach/hr during peak hours will be included.

#### Year 2034 Traffic Forecast

4.2.25 In order to produce the traffic forecast at the design year of 2034, 2-tier model approach (i.e Strategic Transport Model (STM) and Local Area Model (LAM)) have been adopted. For LAM, the TD's Base District Traffic Models (BDTM) "NTW1" covering Tuen Man and Yuen Long Area have been adopted for the study. The NTW1 traffic model was cordoned off and fine tuned to produce a LAM for providing traffic flows within the study area. The base year traffic flows have been validated against the observed traffic count records and the traffic flows from the application Y/YL-MP/10 to ensure the base year models replicates the existing traffic flows and patterns before the model is used to produce traffic forecast.

4.2.26 For STM, reference has been made to the 2-tier model from the recently agreed rezoning application Y/YL-MP/10 nearby for developing the traffic flows crossing the cordons for local area traffic modelling. The locations of the cordons are shown in **Drawing 3.2**. As the 2-tier model from Y/YL-MP/10 are not developed based on the latest 2021-based TPEDM planning assumptions, a growth factor of 1.05 has been derived from **Table 4.9** and applied to the year 2034 traffic flows to reflect the latest 2021-based TPEDM planning assumptions.


**Table 4.9 Comparison of 2019-based and 2021-based TPEDM Planning Assumptions**

Region	2019-Based TPEDM		2021-Based TPEDM		Growth Factor	
	Year 2031		Year 2031			
	Population	Employment	Population	Employment	Population	Employment
Northwest New Territories	1,396,650	393,100	1,347,800	413,350	0.97	1.05 (adopted)


Remark: (1) Planning data is obtained from the official website from Planning Department.

4.2.27 The traffic trips induced from the identified planned/committed developments as tabulated in **Table 4.1** and the trips of the approved scheme of the application site have been included in the LAM. The 2034 reference traffic flows (with approved scheme) are shown in **Drawing 4.2**.


4.2.28 The net increase of the development trips due to proposed scheme as derived in **Table 4.2** are superimposed onto the year 2034 reference traffic flows, to produce the anticipated year 2034 design traffic flows. The net increase in the development flows between the approved and proposed schemes are presented in **Drawing 4.3** whilst the year 2034 design traffic flows (with proposed scheme) are shown in **Drawing 4.4**.



				Project Title	Drawing Title						SYSTRA MVA					
				LOCALIONS OF PLANNED / COMMITTED DEVELOPMENTS												
B		REVISION OF DRAWING NUMBER	PTC	02JAN26	Designed	HZF	Checked	PTC	Scale	1:25000(A3)	Date	JUN 2025	Drawing No.	4.1	Rev.	
A		MINOR AMENDMENT	PTC	11DEC25												
Rev.		Description	Checked	Date												



B	TRAFFIC FLOWS UPDATED	PTC	9JAN26	-	-	-	-
A	TRAFFIC FLOWS UPDATED	PTC	11DEC25	-	-	-	-
Rev.	Description	Checked	Date	Rev.	Description	Checked	Date
Project Title PROPOSED RESIDENTIAL DEVELOPMENT AT LOT NO. 4822 IN D.D.104 AND ADJOINING GOVERNMENT LAND, EAST OF KAM POK ROAD, MAI PO, YUEN LONG							
Drawing Title <b>YEAR 2034 REFERENCE TRAFFIC FLOWS</b>							
Designed	HZF	Checked	PTC	Scale	NTS	Date	JUL 2025
Drawing No.	<b>4.2</b>			Rev.	B		
CHK50868310/TIA/F42-B.CDR/LLH/9JAN26							



Project Title  
PROPOSED RESIDENTIAL DEVELOPMENT AT LOT NO. 4822 IN D.D.104 AND  
ADJOINING GOVERNMENT LAND, EAST OF KAM POK ROAD, MAI PO, YUEN LONG

Drawing Title


### DEVELOPMENT TRAFFIC FLOWS (NET INCREASE)

Designed	HZF	Checked	PTC	Scale	NTS	Date	JUL 2025	Drawing No.	4.3	Rev.	B
----------	-----	---------	-----	-------	-----	------	----------	-------------	-----	------	---

CHK50868310/TIA/F43-B.CDR/LLH/9JAN26

**SYSTRA**  
MVA

Original Size : A4



-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-
Rev.	Description	Checked	Date	Rev.	Description	Checked	Date
Project Title							
PROPOSED RESIDENTIAL DEVELOPMENT AT LOT NO. 4822 IN D.D.104 AND ADJOINING GOVERNMENT LAND, EAST OF KAM POK ROAD, MAI PO, YUEN LONG							
Drawing Title							
<b>YEAR 2034 DESIGN TRAFFIC FLOWS</b>							
Designed	HZF	Checked	PTC	Scale	NTS	Date	JAN 2026
Drawing No.	<b>4.4</b>			Rev.	-		

## 5. TRAFFIC IMPACT ASSESSMENT

### 5.1 Traffic Impact Assessment

5.1.1 To investigate the traffic impact of the proposed development on the surrounding road network at the design year 2034, operational performance of the identified key local junctions and critical links have been assessed for both reference and design scenarios.

#### **Planned Improvement at Fairview Park Interchange (J1)**

5.1.2 According to RNTPC Paper No. 10/22 dated 9 December 2022 for the CEDD's project "Agreement No. CE 10/2020 (CE)- Site Formation and Infrastructure Works for Proposed Public Housing Developments at Sha Po, Shap Pat Heung and Tai Kei Leng, Yuen Long – Feasibility Study", an improvement works has been planned to Fairview Park Interchange (J1) as illustrated in **Drawing 5.1**. Under the improvement scheme, the southern arm of San Tam Road and the approach arms of Castle Peak Road – Tam Mi (northbound) and San Tin Highway Slip Road (southbound) would be widened. An additional exclusive left-turn lane at San Tin Highway Slip Road (northbound) would also be provided.

5.1.3 Besides, further improvement to this planned junction (J1) has been proposed under the recently agreed rezoning application no. Y/YL-MP/10 as illustrated in **Drawing 5.1**. This improvement works is expected to be completed prior to its commissioning (i.e. before the year 2034). Thus, this planned improvement layout has been adopted in the assessment.

#### **Planned Improvements at junction Kam Pok Road/Vehicular Bridge (North) (J4) and junction Castle Peak Road/Kam Pok Road (J6)**

5.1.4 Apart from junction J1, two additional junction improvements for Kam Pok Road/Vehicular Bridge (North) (J4) and Castle Peak Road/Kam Pok Road (J6) have also been proposed under the agreed rezoning application no. Y/YL-MP/10.

5.1.5 For junction Kam Pok Road/Vehicular Bridge (North) (J4), the existing 3-arm signal-controlled junction is planned to be converted to 4-arm junction, and an additional exclusive left-turn lane would be provided at the approach arm of Kam Pok Road westbound. The planned junction improvement layout is illustrated in **Drawing 5.2**. For junction Castle Peak Road/Kam Pok Road (J6), separate turning would be allowed at the approach arm of Yau Pok Road as illustrated in **Drawing 5.3**. These planned junction improvement works have been adopted in the assessment.

#### **Junction Operational Performance**

5.1.6 Based on the existing/planned layouts, the junction assessment results for the 2034 reference and design scenarios are summarized in **Table 5.1**. The junction calculation sheets are attached in **Appendix E**.

**Table 5.1 Junction Operational Performance at Year 2034**

Ref (2)	Junction	Junction Type	2034 RC/RFC <sup>(1)</sup>			
			Reference (with approved Scheme)		Design (with Proposed Scheme)	
			AM Peak	PM Peak	AM Peak	PM Peak
J1	Fairview Park Interchange <sup>(3)</sup>	Roundabout	0.87	0.89	0.91	0.92
J2	Fairview Park Boulevard / Kam Pok Road	Signal	61%	55%	59%	54%
J3	Kam Pok Road / Vehicular Bridge (South)	Signal	>100%	>100%	90%	>100%
J4	Kam Pok Road / Vehicular Bridge (North) <sup>(4)</sup>	Signal	>100%	>100%	57%	>100%
J5	Kam Pok Road / Ha Chuk Yuen Road	Priority	0.06	0.06	0.07	0.06
J6	Castle Peak Road / Kam Pok Road <sup>(5)</sup>	Priority	0.71	0.34	1.14	0.50
J7	Kam Pok Road / Fung Chuk Road	Priority	0.01	0.01	0.04	0.04

Remarks: (1) RC = reserve capacity, RFC = ratio of flow to capacity.

(2) Locations refer to **Drawing 3.2**.

(3) Based on the planned junction layout as illustrated in **Drawing 5.1**.

(4) Based on the planned junction layout as illustrated in **Drawing 5.2**.

(5) Based on the planned junction layout as illustrated in **Drawing 5.3**.

5.1.7 The results of the assessment as shown in **Table 5.1** indicated that all identified key junctions would operate within capacities under reference case (with approved scheme), except the junction Fairview Park Interchange (J1). Whilst, for the design case (with proposed scheme), all identified key junctions would operate within capacities, except the junction Fairview Park Interchange (J1) and Castle Peak Road/Kam Pok Road (J6).

#### Road Link Performance

5.1.8 Apart from junction capacity assessment, the road link operation performance was also undertaken for both reference and design scenarios. Based on the existing road layouts with traffic forecast, the results of the assessment are summarized in **Tables 5.2**.

**Table 5.2 Year 2034 Road Link Operational Performance for Reference Case and Design Case**

Ref. (1)	Road Link	Dir	Link Capacity (pcu/hr)	Reference Case (with Approved Scheme)				Design Case (with Current Scheme)			
				Traffic Flows (pcu/hr)		V/C Ratio		Traffic Flows (pcu/hr)		V/C Ratio	
				AM	PM	AM	PM	AM	PM	AM	PM
L1	Castle Peak Road – Tam Mi	2-way	2,125 <sup>(2)</sup>	1,500	1,175	0.71	0.55	1,705	1,295	0.80	0.61
L2	Fairview Park Boulevard	EB	2,600 <sup>(3)</sup>	1,020	830	0.39	0.32	1,020	830	0.39	0.32
		WB	2,600 <sup>(3)</sup>	670	955	0.26	0.37	670	955	0.26	0.37
L3	Kam Pok Road	2-way	1,800 <sup>(4)</sup>	615	380	0.34	0.21	885	515	0.49	0.29
L4	Fung Chuk Road	2-way	100 <sup>(5)</sup>	5	10	0.05	0.1	25	30	0.25	0.30
L5	Ha Chuk Yuen Road	2-way	100 <sup>(5)</sup>	5	10	0.05	0.1	25	30	0.25	0.30

Ref. (1)	Road Link	Dir	Link Capacity (pcu/hr)	Reference Case (with Approved Scheme)				Design Case (with Current Scheme)			
				Traffic Flows (pcu/hr)		V/C Ratio		Traffic Flows (pcu/hr)		V/C Ratio	
				AM	PM	AM	PM	AM	PM	AM	PM
L6	San Tin Highway	NB	6,100 <sup>(6)</sup>	7,015	6,415	1.15	1.05	7,065	6,445	1.16	1.06
		SB	6,100 <sup>(6)</sup>	6,130	5,635	1.00	0.92	6,210	5,660	1.02	0.93

Remarks: (1) Refer to **Drawing 3.2**.

(2) Road capacity for single 2-lane rural road, with consideration of roadside activities.

(3) Road capacity for dual-2 lane local distributor.

(4) Road capacity for single-2 lane local distributor.

(5) Road capacity for single-track access road.

(6) Road capacity for dual-3 lane trunk road.

5.1.9 The results of the assessment as shown in **Table 5.2** indicated that all identified road links, except San Tin Highway (L1) would operate within capacities under reference case (with approved scheme) and design case (with current scheme).

5.1.10 Under the design year 2034, the v/c ratio of San Tin Highway would reach between 1.0 and 1.2, meaning that the traffic speed would be reduced, but would still be manageable. As mentioned in **Section 4.2**, a NM Highway has been planned by the government, and the traffic pressure at the existing San Tin Highway would be alleviated upon commissioning of NM Highway.

#### Queue Length Assessment

5.1.11 Queue length assessment at the approach arms of the identified junctions has been conducted for both reference and designs scenarios. The results are summarized in **Table 5.3**.

**Table 5.3 Year 2034 Queue Length Assessment for Reference Case and Design Case**

Ref. (1)	Approach Arm	Road Length of each lane	Year 2034 Average Queue Length (m)			
			Reference Case (with Approved Scheme)		Design Case (with Current Scheme)	
			AM	PM	AM	PM
J1	Fairview Park Boulevard	391	168	8	221	9
	Castle Peak Road - Tam Mi (SB)	590	26	2	76	3
	San Tin Highway Slip Road (SB)	329	53	18	76	21
	San Tam Road (SB)	563	95	8	139	9
	San Tam Road (NB)	202	15	4	17	4
	San Tin Highway Slip Road (NB)	410	17	132	23	195
	Castle Peak Road - Tam Mi (NB)	840	51	10	82	11
J2	Fairview Park Boulevard (EB)	40	54	35	54	35
	Fairview Park Boulevard (WB)	252	43	54	43	54
	Kam Pok Road (SB)	39	22	20	23	20
	Kam Pok Road (NB)	160	25	30	26	31
J3	Vehicular Bridge (EB)	55	1	1	1	1
	Kam Pok Rd (SB)	35	9	7	18	12
	Kam Pok Rd (NB)	78	5	4	16	9

Ref. (1)	Approach Arm	Road Length of each lane	Year 2034 Average Queue Length (m)			
			Reference Case (with Approved Scheme)		Design Case (with Current Scheme)	
			AM	PM	AM	PM
J4	Vehicular Bridge (SB)	54	2	1	2	1
	Kam Pok Road (EB)	334	13	10	28	16
	R(D) Site Access	27	13	3	15	7
	Kam Pok Road (WB)	242	17	12	25	16
J5	Ha Chuk Yuen Road	226	0	0	0	0
J6	Kam Pok Road	59	13	2	186	4
J7	Fung Chuk Road	192	0	0	0	0

5.1.12 The results of the assessment as shown in **Table 5.3** indicated that no traffic queue back to the adjacent junction is anticipated during peak hour under reference case (with approved scheme) and design case (with current scheme), except the approach arm of Fairview Park Boulevard (EB) at J2 and the minor arm of Kam Pok Road at J6. For the approach arm of Fairview Park Boulevard (EB), no development trip is anticipated to pass through. Thus, the anticipated average queue lengths are the same under both reference and design cases, as shown in **Table 5.3**.

*Proposed Junction Improvements for Fairview Park Interchange (J1) and Castle Peak Road/Kam Pok Road (J6)*

5.1.13 To resolve the foreseeable traffic problems, local junction improvement measures have been proposed for the planned junctions Fairview Park Interchange (J1) and Castle Peak Road / Kam Pok Road (J6).

5.1.14 For the planned junction Fairview Park Interchange (J1), it is proposed to widen the approach arms of Fairview Park Boulevard, San Tin Highway Slip Road northbound and San Tam Road southbound, and also provide an exclusive left-turn for San Tin Highway Slip Road southbound to enhance the junction capacity. Details of the improvement scheme are shown in **Drawing 5.4**. For Castle Peak Road/Kam Pok Road (J6), it is proposed to convert the junction from priority-controlled to mini roundabout. Details of the improvement scheme are shown in **Drawing 5.5**. The proposed junction improvements will be implemented by the proposed development.

5.1.15 The operational performances of the junction Fairview Park Interchange (J1) and Castle Peak Road/Kam Pok Road (J6) were re-assessed based on the proposed improvement schemes. The results are summarized in **Table 5.4**.

**Table 5.4 Year 2034 Junction Operational Performance with Proposed Improvement Scheme**

Ref.	Junction	Type	2034 Design Case	
			Reserve Capacity (RC)	
			AM Peak	PM Peak
J1	Fairview Park Interchange <sup>(1)</sup>	Roundabout	0.84	0.80
J6	Castle Peak Road / Kam Pok Road <sup>(2)</sup>	Roundabout	0.51	0.54

Remarks: (1) Based on the proposed junction improvement works on **Drawing 5.4**.

(2) Based on the proposed junction improvement works on **Drawing 5.5**.

5.1.16 The results of the junction assessment as shown in **Table 5.4** indicated that the junction Fairview Park Interchange (J1) and Castle Peak Road/Kam Pok Road (J6) could be alleviated with the proposed improvement schemes at the design year 2034.

## 5.2 Sensitivity Test 1

5.2.1 It is noted that the rezoning applications under nos. Y/YL-MP/7, Y/YL-MP/8 in close vicinity to the site are currently under processing for increasing their development densities. Thus, a sensitivity test was conducted to assess the traffic impact by assuming these potential residential developments will be completed before the design year 2034. The locations of the potential sites are illustrated in **Drawing 5.6**.

5.2.2 The development schedules and estimated trip generations of these planning applications are summarized in **Table 5.5**. The estimated trip generations were included in the traffic forecast for Sensitivity Test 1. The year 2034 design traffic flows under Sensitivity Test 1 is shown in **Drawing 5.7**.

**Table 5.5 Estimated Trip Generations of Potential Residential Developments**

Planning Application	Current Zoning	Proposed Domestic Plot Ratio	No. of Units.	Trip Generations (pcu/hr) <sup>(1)</sup>			
				AM Peak		PM Peak	
				GEN	ATTR	GEN	ATTR
Proposed Residential Development at west of Yau Pok Road (Y/YL-MP/7 & MP/8) <sup>(2)</sup>	REC & R(C)	about 1.2	2,477	246	174	109	131

Remarks: (1) Trip Generations extracted from the latest submitted TIA report of the planning application.

(2) The site is the subject of the previous approved planning application Y/YL-MP/3. Trip generations of the previous approved applications were excluded separately from the traffic forecast.

### Junction Operational Performance for Sensitivity Test 1

5.2.3 Based on the existing/planned layouts, the results of the junction assessment for the design case under Sensitivity Test 1 are summarized in **Table 5.6**. The junction calculation sheets are attached in **Appendix E**.

**Table 5.6 Junction Operational Performance at Year 2034 under Sensitivity Test 1**

Ref <sup>(2)</sup>	Junction	2034 RC/RFC <sup>(1)</sup>	
		Design Case under Sensitivity Test 1	
		AM Peak	PM Peak
J1	Fairview Park Interchange <sup>(3)</sup>	0.96	0.83
J2	Fairview Park Boulevard / Kam Pok Road	45%	46%
J3	Kam Pok Road / Vehicular Bridge (South)	37%	>100%
J4	Kam Pok Road / Vehicular Bridge (North) <sup>(4)</sup>	16%	99%
J5	Kam Pok Road / Ha Chuk Yuen Road	0.08	0.06
J6	Castle Peak Road / Kam Pok Road <sup>(5)</sup>	0.61	0.62
J7	Kam Pok Road / Fung Chuk Road	0.04	0.04

Remarks:

(1) RC = reserve capacity, RFC = ratio of flow to capacity.

(2) Locations refer to **Drawing 3.2**.

(3) Based on the proposed junction layout as illustrated in **Drawing 5.4**.

(4) Based on the planned junction layout as illustrated in **Drawing 5.2**.

(5) Based on the proposed junction layout as illustrated in **Drawing 5.5**.

5.2.4 The results of the assessment as shown in **Table 5.6** indicated that all identified key junctions would operate within capacities under the design case in Sensitivity Test 1, except Fairview Park Interchange (J1).

Road Link Performance for Sensitivity Test 1

5.2.5 Apart from junction capacity assessment, the road link operation performance was also undertaken for both reference and design scenarios. Based on the existing road layouts with traffic forecast, the results of the assessment are summarized in **Table 5.7**.

**Table 5.7 Year 2034 Road Link Operational Performance for Design Case under Sensitivity Test 1**

Ref. (1)	Road Link	Dir	Link Capacity (pcu/hr)	Design Case under Sensitivity Test 1			
				Traffic Flows (pcu/hr)		V/C Ratio	
				AM	PM	AM	PM
L1	Castle Peak Road – Tam Mi	2-way	2,125 <sup>(2)</sup>	1,910	1,420	0.90	0.67
L2	Fairview Park Boulevard	EB	2,600 <sup>(3)</sup>	1,020	830	0.39	0.32
		WB	2,600 <sup>(3)</sup>	670	955	0.26	0.37
L3	Kam Pok Road	2-way	1,800 <sup>(4)</sup>	1,175	675	0.65	0.38
L4	Fung Chuk Road	2-way	100 <sup>(5)</sup>	25	30	0.25	0.30
L5	Ha Chuk Yuen Road	2-way	100 <sup>(5)</sup>	25	30	0.25	0.30
L6	San Tin Highway	NB	6,100 <sup>(6)</sup>	7,145	6,510	1.17	1.07
		SB	6,100 <sup>(6)</sup>	6,335	5,710	1.04	0.94

Remarks: (1) Refer to **Drawing 3.2**.

(2) Road capacity for single 2-lane rural road, with consideration of roadside activities.

(3) Road capacity for dual-2 lane local distributor.

(4) Road capacity for single-2 lane local distributor.

(5) Road capacity for single-track access road.

(6) Road capacity for dual-3 lane trunk road.

5.2.6 The assessment results in **Table 5.7** indicated that all identified road links except San Tin Highway (L6) would operate within capacities under the design case in Sensitivity Test 1. Similar to the design case, the v/c ratio of San Tin Highway would reach between 1.0 and 1.2 under the design 2034 meaning that the traffic speed would be reduced, but would still be manageable. The traffic pressure at the existing San Tin Highway would be alleviated upon commissioning of NM Highway.

Suggested Junction Improvement for Fairview Park Interchange (J1)

5.2.7 To resolve the foreseeable traffic problem under the sensitivity test, a local junction improvement measure has been suggested for the proposed junction Fairview Park Interchange (J1). It is further proposed to widen the approach arms of Castle Peak Road – Tam Mi northbound and provide an exclusive left-turn for Castle Peak Road – Tam Mei southbound to enhance the junction capacity. Details of junction improvement scheme are shown in **Drawing 5.8**.

5.2.8 The operational performance of the junction Fairview Park Interchange (J1) was re-assessed based on the suggested improvement scheme. The result is summarized in **Table 5.8**.

**Table 5.8 Year 2034 Junction Operational Performance with Suggested Improvement Scheme**

Ref.	Junction	Type	2034 Design Case	
			Ratio of flow to capacity	
			AM Peak	PM Peak
J1	Fairview Park Interchange <sup>(1)</sup>	Roundabout	0.84	0.83

Remarks: (1) Based on the suggested junction improvement works on **Drawing 5.8**.

5.2.9 The results of the junction assessment as shown in **Table 5.8** indicated that the junction Fairview Park Interchange (J1) could be alleviated with the suggested improvement scheme at the design year 2034.

### 5.3 Pedestrian Assessment

5.3.1 The footpaths at Kam Pok Road and Fairview Park Boulevard would be the main pedestrian route to/from the application site. Two sections of the concerned footpaths have been identified for assessment and the location of the two sections are shown in **Drawing 5.9**. Based on a pedestrian head count survey on a typical weekday in April 2025, the observed two-way pedestrian flows at the concerned footpaths during the critical AM peak hour are summarized in **Table 5.9**. The observed pedestrian flows are found to be minimal.

**Table 5.9 Observed Pedestrian Flows during Peak Hours**

Ref <sup>(1)</sup>	Section	Existing Footpath Width	Observed Two-way Pedestrian Flows during AM Peak (ped/hr)
P1	Kam Pok Road	1.5m	75
P2	Fairview Park Boulevard	2m	45

Remark: (1) Locations refer to **Drawing 5.9**.

5.3.2 The proposed development will provide 1,303 units with about 3,519 population. There is a planned residential development at Kam Pok Road (i.e. approved planning application Y/YL-MP/10) to the north of the application site. Two other application sites under rezoning applications nos. Y/YL-MP/7 & Y/YL-MP/8 are also located in the close proximity to the site. The estimated pedestrian trips of the proposed development together with these planned/potential developments are summarised in **Table 5.10**.

**Table 5.10 Estimated Pedestrian Trips during Peak Hours**


Development	No. of Units	Estimated Population	Estimated Pedestrian Trips during peak hours (ped/hr)
Proposed Development	1,303	3,519 <sup>(1)</sup>	773 <sup>(1)</sup>
Planned Residential Development at Kam Pok Road with Transport Layby (Approved planning application Y/YL-MP/10)	2,322	6,270 <sup>(2)</sup>	1,005 for PT trips and 372 non-PT trips <sup>(2)</sup>
Potential Residential Development at Yau Pok Road with Transport Laybys under planning applications Y/YL-MP/7 & Y/YL-MP/8	2,477	6,688 <sup>(2)</sup>	1,072 for PT trips and 397 for non-PT trips <sup>(2)</sup>

Remark:


(1) Refer to **Table 4.5**.

(2) Information extracted from its planning application.


5.3.3 As discussed in **Section 4.2.5**, the public transport demands of the planned/potential developments (i.e. Y/YL-MP/7, Y/YL-MP/8 & Y/YL-MP/10) would be served by the future bus services in their proposed Transport Layby within their sites. By assuming that all the pedestrian trips of the proposed development and the non-PT trips of the adjacent developments would all be loaded into the two concerned footpaths for a worst-case scenario, the pedestrian trips generated from all the proposed/planned/potential developments to the nearby footpaths are 1542 ped/hr (i.e.  $773 + 372 + 397 = 1542$ ) during peak hours. The 1.5m wide footpaths at Kam Pok Road, which can serve at a capacity of 2970 ped/hr based on satisfactory LOS C at flow rate of 33 ped/min/m, and the 2m wide footpath at Fairview Park Boulevard, which can serve at a capacity of 3,960 based on satisfactory LOS C at flow rate of 33 ped/min/m, should have sufficient capacities to cater for the future pedestrian demands in the area.




Project Title				Drawing Title							SYSTRA MVA	
PROPOSED RESIDENTIAL DEVELOPMENT AT LOT NO. 4822 IN D.D. 104 AND ADJOINING GOVERNMENT LAND, EAST OF KAM POK ROAD, MAI PO, YUEN LONG				PLANNED JUNCTION IMPROVEMENT LAYOUT OF FAIRVIEW PARK INTERCHANGE (J1)								
Designed	HZF	Checked	PTC	Scale	1:1000(A3)	Date	JUN 2025	Drawing No.	5.1	Rev.	-	
Rev.	Description	Checked	Date									Original Size : A3



-	-	-	-	-	-	-	-	-	-	-	-
Rev.	Description	Checked	Date	Rev.	Description	Checked	Date	Rev.	Description	Checked	Date
Project Title				Drawing Title							
PROPOSED RESIDENTIAL DEVELOPMENT AT LOT NO. 4822 IN D.D. 104 AND ADJOINING GOVERNMENT LAND, EAST OF KAM POK ROAD, MAI PO, YUEN LONG				<b>PLANNED JUNCTION IMPROVEMENT LAYOUT OF KAM POK ROAD / VEHICULAR BRIDGE - NORTH / VEHICULAR ACCESS (J4)</b>							
Designed	HZF	Checked	PTC	Scale	1:500(A4)	Date	JUN 2025	Drawing No.	<b>5.2</b>	Rev.	-



Rev.	Description	Checked	Date	Rev.	Description	Checked	Date	Rev.	Description	Checked	Date
Project Title				Drawing Title							
PROPOSED RESIDENTIAL DEVELOPMENT AT LOT NO. 4882 IN D.D. 104 AND ADJOINING GOVERNMENT LAND, EAST OF KAM POK ROAD, MAI PO, YUEN LONG				PLANNED JUNCTION IMPROVEMENT LAYOUT OF KAM POK ROAD / CASTLE PEAK ROAD - TAM MI (J6)							
Designed	HZF	Checked	PTC	Scale	1:500(A4)	Date	JUN 2025	Drawing No.	5.3	Rev.	-




-	-	-	-	Project Title
-	-	-	-	
-	-	-	-	
A MINOR AMENDMENT	PTC	16JAN26		
Rev. Description	Checked	Date		

PROPOSED RESIDENTIAL DEVELOPMENT AT  
LOT NO. 4822 IN D.D. 104 AND ADJOINING GOVERNMENT LAND,  
EAST OF KAM POK ROAD, MAI PO, YUEN LONG

Drawing Title  
**PROPOSED JUNCTION IMPROVEMENT LAYOUT OF  
FAIRVIEW PARK INTERCHANGE (J1)**

Designed HZF Checked PTC Scale 1:1000(A3) Date JUN 2025 Drawing No. 5.4 Rev. A

**SYSTRA**  
MVA




Project Title **PROPOSED RESIDENTIAL DEVELOPMENT AT LOT NO. 4882 IN D.D. 104 AND  
ADJOINING GOVERNMENT LAND EAST OF KAM POK ROAD, MAI PO, YUEN LONG**

### Drawing Title

## **PROPOSED JUNCTION IMPROVEMENT LAYOUT OF KAM POK ROAD / CASTLE PEAK ROAD - TAM MI (J6)**

FILENAME  
PRINTED

**SYSTRA**  
MVA



LEGEND:

APPLICATION SITE

POTENTIAL DEVELOPMENT

POTENTIAL DEVELOPMENTS:

A) PROPOSED RESIDENTIAL DEVELOPMENTS IN REC & R(C) ZONES AT YAU POK ROAD (Y/YL-MP/7 & MP/8).


A	MINOR AMENDMENT	PTC	08DEC25	-	-	-	-
-	-	-	-	-	-	-	-

Rev.	Description	Checked	Date	Rev.	Description	Checked	Date
------	-------------	---------	------	------	-------------	---------	------


Drawing Title

**LOCATIONS OF POTENTIAL DEVELOPMENTS**

Designed	HZF	Checked	PTC	Scale	N.T.S.(A4)	Date	JUN 2025	Drawing No.	5.6	Rev.	A
----------	-----	---------	-----	-------	------------	------	----------	-------------	-----	------	---



B	TRAFFIC FLOWS UPDATED	PTC	16JAN26	-	-	-	-
A	TRAFFIC FLOWS UPDATED	PTC	11DEC25	-	-	-	-
Rev.	Description	Checked	Date	Rev.	Description	Checked	Date
Project Title							
PROPOSED RESIDENTIAL DEVELOPMENT AT LOT NO. 4822 IN D.D.104 AND ADJOINING GOVERNMENT LAND, EAST OF KAM POK ROAD, MAI PO, YUEN LONG							
Drawing Title							
<b>YEAR 2034 DESIGN TRAFFIC FLOWS (SENSITIVITY TEST 1)</b>							
Designed	HZF	Checked	PTC	Scale	NTS	Date	JUL 2025
						Drawing No.	<b>5.7</b>
						Rev.	<b>B</b>




-	-	-	-	Project Title
-	-	-	-	PROPOSED RESIDENTIAL DEVELOPMENT AT
-	-	-	-	LOT NO. 4822 IN D.D. 104 AND ADJOINING GOVERNMENT LAND,
-	-	-	-	EAST OF KAM POK ROAD, MAI PO, YUEN LONG
A MINOR AMENDMENT	PTC	16JAN26		
Rev. Description	Checked	Date		

Project Title  
PROPOSED RESIDENTIAL DEVELOPMENT AT  
LOT NO. 4822 IN D.D. 104 AND ADJOINING GOVERNMENT LAND,  
EAST OF KAM POK ROAD, MAI PO, YUEN LONG

Drawing Title  
**SUGGESTED JUNCTION IMPROVEMENT LAYOUT OF  
FAIRVIEW PARK INTERCHANGE (J1)**

Designed HZF Checked PTC Scale 1:1000(A3) Date JUN 2025 Drawing No. **5.8** Rev. A



Rev.	Description	Checked	Date	Rev.	Description	Checked	Date
-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-

Project Title	PROPOSED RESIDENTIAL DEVELOPMENT AT LOT NO. 4822 IN D.D.104 AND ADJOINING GOVERNMENT LAND, EAST OF KAM POK ROAD, MAI PO, YUEN LONG
---------------	--

Drawing Title	<b>IDENTIFIED FOOTPATHS</b>	<b>SYSTRA</b> MVA
Designed HZF	Checked PTC	Scale NTS Date DEC 2025 Drawing No. 5.9 Rev. -

## 6. SUMMARY & CONCLUSION

### 6.1 Summary

6.1.1 The application site comprises lot No. 4822 in D.D. 104 and adjoining government Land, east Kam Pok Road, Mai Po, Yuen Long, as indicated in **Drawing 1.1**. The Applicant proposes to increase its domestic plot ratio from 0.2 to 1.5. Under the current scheme, the proposed development will provide 5 medium-rise residential blocks of total 1,303 units, one 6-classroom kindergarten and one Neighbourhood Elderly Centre.

6.1.2 The main development vehicular access will be located at Kam Pok Road. The internal transport facilities provisions will be provided in accordance with the relevant guidelines stipulated in the latest HKPSG and the comments from TD.

6.1.3 Traffic surveys have been conducted to establish the current traffic condition in the vicinity of the site. The results of the junction and link capacity assessments have revealed that all the identified local junctions and road links are currently operating within capacities during peak hours.

6.1.4 The tentative operation year of proposed development is 2031. Thus, the design year of 2034 is adopted for traffic forecast and assessment purposes.

6.1.5 Operational performance of all identified local junctions and road links have been assessed based on the anticipated year 2034 traffic flows and the existing/planned layouts. The results of the assessment as shown in **Table 5.1** and **Table 5.2** revealed that all identified key junctions and road links will operate within capacities except the planned junctions Fairview Park Interchange (J1) and Castle Peak Road / Kam Pok Road (J6).

6.1.6 To resolve the foreseeable traffic problem, local junction improvement measures have been proposed for Fairview Park Interchange (J1) and Castle Peak Road/Kam Pok Road (J6). According to the results of the junction assessment as shown in **Table 5.3**, the junctions J1 and J6 can operate within capacity under the proposed improvement schemes at the design year 2034.

6.1.7 It is noted that two rezoning applications in the vicinity of the application site have been submitted for increasing their development densities. A sensitivity test (i.e. Sensitivity Test 1) has conducted to assess the traffic impact by assuming that these potential residential developments will be completed before the design year 2034. The results of the junction and link assessment under Sensitivity Test 1 revealed that all identified key junctions and road links will operate within capacities except Fairview Park Interchange (J1). A junction improvement scheme has been suggested for Fairview Park Interchange (J1).

### 6.2 Conclusion


6.2.1 In conclusion, the results of the traffic impact assessment have demonstrated that the development traffic generation by the subject site can be absorbed by the nearby road network (with implementation of junction improvement works at Fairview Park Interchange J1 and Castle Peak Road/Kam Pok Road J6) and would not cause any adverse traffic impact. Hence it can be concluded that the proposed development is considered acceptable in traffic engineering perspective.

## **Appendix A**

# **Swept Path Analysis at the Proposed Vehicular Accesses**




**Swept Path Analysis for 12.8m Bus at the Main Entrance**  
**1:500 in A4 Size**



**Swept Path Analysis for 7m Vehicle at the Second Entrance**  
**1:500 in A4 Size**

## **Appendix B**

### **Preliminary Directional Sign at Egress of the Development**



## **Appendix C**

### **Preliminary Phasing Plan of San Tin Technopole**

(Extracted from EIA study of First Phase Development of the New Territories North – San Tin / Lok Ma Chau Development Node – Investigation)

\* Extracted from EIA study of First Phase Development of the New Territories  
North – San Tin / Lok Ma Chau Development Node – Investigation

ISO A1 594mm x 841mm


Approved:

Checked:

Designer:

Project Management Initiatives:

Plot File by: Rens  
2023/11/14  
PATH: PROJECT/TS6067/0882/DRAWINGS/REPORT/A34/APPENDIX 2.1.dgn



**AECOM**

PROJECT  
项目

FIRST PHASE DEVELOPMENT OF  
THE NEW TERRITORIES NORTH –  
SAN TIN / LOK MA CHAU  
DEVELOPMENT NODE –  
INVESTIGATION

CLIENT  
客户

**CEDD**  
Civil Engineering and  
Development Department

**規畫署**  
Planning Department

CONSULTANT  
工程顾问公司

AECOM Asia Company Ltd.,  
www.aecom.com

SUB-CONSULTANTS  
分包工程顾问公司

ISSUE/REVISION  
修订

UR	DATE	DESCRIPTION	CHK.
----	------	-------------	------

STATUS  
阶段

SCALE  
比例  
A3 1:16000

DIMENSION UNIT  
尺寸單位  
METRES

KEY PLAN  
系引圖

PROJECT NO.  
项目编号  
60670882

AGREEMENT NO.  
協議編號  
CE 20/2021

SHEET TITLE  
圖紙名稱  
PRELIMINARY CONSTRUCTION AND  
POPULATION INTAKE SCHEDULE

SHEET NUMBER  
圖紙編號  
60670882/A34/APPENDIX 2.1

This drawing is being prepared for the use of AECOM's client. It may not be used, modified, reproduced or relied upon by third parties, except as agreed by AECOM or as required by law. AECOM accepts no responsibility and denies any liability whatsoever, to any party that uses or relies on this drawing without AECOM's express written consent. Do not scale this document. All measurements must be obtained from the stated dimensions.

## **Appendix D**

# **Preliminary Phasing Plan of Ngau Tam Mei New Development Area**


(Extracted from EIA study of Land Use Review Study For Ngau Tam Mei Area – Feasibility Study)



## **Appendix E**





### **Junction Calculation Sheets**

## Roundabout Capacity Calculation

Job Title: Proposed Residential Development at Lot No. 4822 in D.D. 104 and Adjoining Government Land, East of Kam Pok Road, Mai Po, Yuen Long																				
Junction: Fairview Park Interchange (J1)								Ref. No.:												
Scheme: Observed Case			2025			Job No.:		CHK50868310												
AM			PM																	
ARM A: Fairview Park Boulevard ARM B: Castle Peak Road - Tam Mi (N) ARM C: San Tin Highway Slip Road (N) ARM D: San Tam Road (N) ARM E: San Tam Road (S) ARM F: San Tin Highway Slip Road (S) ARM G: Castle Peak Road - Tam Mi (S)																				
																				
<b>GEOMETRY</b>																				
ARM	v	e	L	r	D	Phi	S													
A	7.00	11.00	14	22	142	35	0.46													
B	5.50	10.50	15	20	142	35	0.53													
C	5.50	8.50	7.5	23	142	30	0.64													
D	6.75	8.50	10	20	142	25	0.28													
E	6.00	8.00	9.5	20	142	35	0.34													
F	6.50	9.00	15	25	142	40	0.27													
G	5.50	6.00	7	22	142	30	0.11													
<b>AM FLOWS</b>																				
from \ to	A	B	C	D	E	F	G	Circ	Entry	Exit										
A	55	5	215	35	145	395	15	1265	865	580										
B	15	25	60	5	125	270	5	1735	505	395										
C	150	60	10	105	230	20	125	1660	700	580										
D	40	10	45	10	225	210	10	1985	550	375										
E	50	65	130	50	5	35	5	1650	340	885										
F	240	135	15	130	95	25	110	895	750	1095										
G	30	95	105	40	60	140	15	1360	485	285										
<b>PM FLOWS</b>																				
from \ to	A	B	C	D	E	F	G	Circ	Entry	Exit										
A	55	20	145	40	145	250	20	1275	675	800										
B	15	25	45	15	115	100	10	1555	325	395										
C	175	45	20	100	265	5	100	1305	710	575										
D	20	20	70	20	140	165	10	1590	445	425										
E	50	35	155	35	10	35	5	1255	325	780										
F	450	150	25	160	90	20	175	905	1070	675										
G	35	100	115	55	15	100	10	1645	430	330										
<b>CALCULATIONS</b>																				
ARM	K	X <sub>2</sub>	M	F	t <sub>D</sub>	f <sub>c</sub>	AM	PM	Q <sub>E</sub>	RFC										
A	0.99	9.09	3640.95	2754	1.00	0.59	1980	1974		0.44	0.34									
B	0.98	7.92	3640.95	2400	1.00	0.54	1433	1529		0.35	0.21									
C	1.01	6.82	3640.95	2065	1.00	0.50	1249	1427		0.56	0.50									
D	1.02	7.87	3640.95	2385	1.00	0.54	1335	1552		0.41	0.29									
E	0.98	7.19	3640.95	2180	1.00	0.51	1312	1511		0.26	0.22									
F	0.98	8.13	3640.95	2464	1.00	0.55	1921	1915		0.39	0.56									
G	1.00	5.91	3640.95	1790	1.00	0.46	1172	1041		0.41	0.41									
										<b>Critical Arm:</b>	C									
										<b>RFC:</b>	0.56									
										<b>AM</b>	<b>PM</b>									
<i>- In accordance with TPDM V2.4</i>																				
Calculated by:	HZF		Date:	Jan-26		Checked by:	PTC													


**TRAFFIC SIGNALS CALCULATION**

 Job No.: CHK50868310
**MVA HONG KONG LIMITED**

Junction: <u>Kam Pok Road / Fairview Park Boulevard (J2)</u>											Design Year: <u>2034</u>			
Description: <u>Year 2025 Observed Traffic Flows</u>							Designed By: <u>HZF</u>			Checked By: <u>PTC</u>				
Approach	Movements	Phase	Stage	Width (m)	Radius (m)	Gradient (%)	Pro. Turning (%)		Revised Saturation Flow (pcu/hr)		AM Peak			
				Left	Right		AM	PM	AM	PM	Flow (pcu/hr)	y Value	Critical y	
Fairview Park Boulevard EB	↑→	A	1	3.4	15		8%	10%	1940	1935	389	0.201	0.201	
Fairview Park Boulevard WB	←↓	A	1	3.5	17		24%	26%	1925	1920	307	0.159	0.198	
Kam Pok Road SB	↔	B	2	5.5	18	18	30% / 50%	33% / 43%	2030	2035	100	0.049	0.049	
Kam Pok Road NB	↔	C	3	3.8	13	20	9% / 50%	16% / 75%	1905	1855	110	0.058	0.058	
Pedestrian Crossing Dp 4 MIN GREEN + FLASH = 10 + 9 = 19 *														
Notes:		Flow: (pcu/hr)							Group		A.B.C.Dp	Group		A.B.C.Dp
									y		0.308	y		0.336
									L (sec)		44	L (sec)		44
									C (sec)		120	C (sec)		120
									y pract.		0.570	y pract.		0.570
									R.C. (%)		85%	R.C. (%)		69%
Stage / Phase Diagrams														
1.		2.		3.		4.		5.						
														
I/G= 3		I/G= 7		I/G= 7		I/G= 7		I/G= 11	19	I/G=		I/G=		
I/G= 3		I/G= 7		I/G= 7		I/G= 7		I/G= 11	19	I/G=		I/G=		
								Date: <u>Jan, 2026</u>		Junction: <u>2</u>		J2		

**TRAFFIC SIGNALS CALCULATION**

 Job No.: CHK50868310
**MVA HONG KONG LIMITED**

Junction: <u>Kam Pok Road / Vehicular Bridge – South (J3)</u>												Design Year: <u>2034</u>					
Description: <u>Year 2025 Observed Traffic Flows</u>												Designed By: <u>HZF</u>	Checked By: <u>PTC</u>				
Approach	Movements	Phase	Stage	Width (m)	Radius (m)		Gradient (%)	Pro. Turning (%)		Revised Saturation Flow (pcu/hr)		AM Peak			PM Peak		
					Left	Right		AM	PM	AM	PM	Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y
Vehicular Bridge (EB)	↑→	A	1	3.600	10	10	80% / 20%	57% / 43%	1715	1715	25	0.015	0.015	35	0.020	0.020	
Kam Pok Rd (SB)	↑→	B	2	3.600		10	20%	21%	1915	1915	100	0.052	0.052	95	0.050	0.050	
Kam Pok Rd (NB)	↔	C	3	3.600	10		20%	20%	1915	1915	25	0.013		25	0.013		
Pedestrian Crossing Dp 4 MIN GREEN + FLASH = 7 + 7 = 14												*	*	*			
Notes:				Flow: (pcu/hr)								Group		A.B.C.Dp	Group		A.B.C.Dp
												y		0.067	y		0.070
												L (sec)		32	L (sec)		32
												C (sec)		60	C (sec)		60
												y pract.		0.420	y pract.		0.420
												R.C. (%)		529%	R.C. (%)		500%
Stage / Phase Diagrams																	
1.			2.			3.			4.			5.					
																	
I/G= 2		I/G= 5			I/G= 5		5	I/G= 3		14	I/G=						
I/G= 2		I/G= 5			I/G= 5		5	I/G= 3		14	I/G=						
Date: <u>Jan, 2026</u>												Junction: <u>3</u> <span style="border: 1px solid black; border-radius: 50%; padding: 2px;">J3</span>					

**TRAFFIC SIGNALS CALCULATION**

 Job No.: CHK50868310
**MVA HONG KONG LIMITED**

Junction: <u>Kam Pok Road / Vehicular Bridge – North (J4)</u>												Design Year: <u>2034</u>					
Description: <u>Year 2025 Observed Traffic Flows</u>												Designed By: <u>HZF</u>	Checked By: <u>PTC</u>				
Approach	Movements	Phase	Stage	Width (m)	Radius (m)		Gradient (%)	Pro. Turning (%)		Revised Saturation Flow (pcu/hr)		AM Peak			PM Peak		
					Left	Right		AM	PM	AM	PM	Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y
Kam Pok Road WB	↑→	C	1	3.650	12		5%	5%	1970	1965	100	0.051	0.051	95	0.048	0.048	
Kam Pok Road EB	←↑	B	3	3.650	10		11%	13%	1950	1945	45	0.023	0.023	40	0.021	0.021	
Vehicular Bridge SB	↑↑	A	2	3.650	10	12	50% / 50%	50% / 50%	1740	1740	10	0.006		10	0.006		
Pedestrian Crossing Dp 4 MIN GREEN + FLASH = 7 + 7 = 14												* * *					
Notes:				Flow: (pcu/hr)								Group		A.B.C.Dp	Group		A.B.C.Dp
												y		0.074	y		0.069
												L (sec)		34	L (sec)		34
												C (sec)		60	C (sec)		60
												y pract.		0.390	y pract.		0.390
												R.C. (%)		428%	R.C. (%)		466%
Stage / Phase Diagrams																	
1.		2.		3.		4.		5.									
I/G= 2		I/G= 5		5	I/G= 5		I/G= 5		14	I/G=							
I/G= 2		I/G= 5		5	I/G= 5		I/G= 5		14	I/G=							
Date: <u>Jan, 2026</u>										Junction: <u>4</u> <span style="border: 1px solid black; border-radius: 50%; padding: 2px;">J4</span>							

### Simplified Priority Junction Capacity Calculation


Job Title:	Proposed Residential Development at Lot No. 4822 in D.D. 104 and Adjoining Government Land, East of Kam Pok Road, Mai Po, Yuen Long			Ref. No.:																																										
Junction:	Kam Pok Road / Ha Chuk Yuen Road (J5)																																													
Scheme:	Observed Case																																													
Year:	2025	Job No.:	CHK50868310	Rev.:																																										
ARM A:	Kam Pok Road WB																																													
ARM B:	Ha Chuk Yuen Road																																													
ARM C:	Kam Pok Road EB																																													
<b>GEOMETRY</b> <table border="1"> <tr> <td>Major road width</td> <td>W</td> <td>9.30</td> <td>Lane widths</td> <td>w(b-a)</td> <td>2.05</td> </tr> <tr> <td>Central Reserve width</td> <td>Wcr</td> <td>0.00</td> <td></td> <td>w(b-c)</td> <td>2.05</td> </tr> <tr> <td>2 Lane Minor Arm (Y/N)</td> <td>N</td> <td></td> <td></td> <td>w(c-b)</td> <td>3.50</td> </tr> <tr> <td>Visibilities</td> <td>Vr(b-a)</td> <td>50</td> <td>Calculated</td> <td>D</td> <td>0.75</td> </tr> <tr> <td></td> <td>Vl(b-a)</td> <td>50</td> <td></td> <td>E</td> <td>0.80</td> </tr> <tr> <td></td> <td>Vr(b-c)</td> <td>50</td> <td></td> <td>F</td> <td>0.92</td> </tr> <tr> <td></td> <td>Vr(c-b)</td> <td>50</td> <td></td> <td>Y</td> <td>0.68</td> </tr> </table>					Major road width	W	9.30	Lane widths	w(b-a)	2.05	Central Reserve width	Wcr	0.00		w(b-c)	2.05	2 Lane Minor Arm (Y/N)	N			w(c-b)	3.50	Visibilities	Vr(b-a)	50	Calculated	D	0.75		Vl(b-a)	50		E	0.80		Vr(b-c)	50		F	0.92		Vr(c-b)	50		Y	0.68
Major road width	W	9.30	Lane widths	w(b-a)	2.05																																									
Central Reserve width	Wcr	0.00		w(b-c)	2.05																																									
2 Lane Minor Arm (Y/N)	N			w(c-b)	3.50																																									
Visibilities	Vr(b-a)	50	Calculated	D	0.75																																									
	Vl(b-a)	50		E	0.80																																									
	Vr(b-c)	50		F	0.92																																									
	Vr(c-b)	50		Y	0.68																																									
<b>ANALYSIS</b> <table border="1"> <thead> <tr> <th></th> <th></th> <th>AM PEAK</th> <th>(PM) PEAK</th> </tr> </thead> <tbody> <tr> <td>TRAFFIC FLOWS</td> <td>q(c-a), q(c-b), q(a-b), q(a-c), q(b-a), q(b-c), f</td> <td>45, 0, 15, 95, 20, 5, 0.20</td> <td>40, 0, 25, 85, 20, 5, 0.20</td> </tr> <tr> <td>CAPACITIES</td> <td>Q(b-a), Q(b-c), Q(c-b), Q(b-ac)</td> <td>1, 1, 1, 1</td> <td>445, 573, 663, 466</td> </tr> <tr> <td>RFC's</td> <td>b-a, b-c, c-b, b-ac</td> <td></td> <td>0.045, 0.009, 0.000, 0.054</td> </tr> <tr> <td>Worst RFC</td> <td></td> <td></td> <td>0.054</td> <td>0.053</td> </tr> </tbody> </table>							AM PEAK	(PM) PEAK	TRAFFIC FLOWS	q(c-a), q(c-b), q(a-b), q(a-c), q(b-a), q(b-c), f	45, 0, 15, 95, 20, 5, 0.20	40, 0, 25, 85, 20, 5, 0.20	CAPACITIES	Q(b-a), Q(b-c), Q(c-b), Q(b-ac)	1, 1, 1, 1	445, 573, 663, 466	RFC's	b-a, b-c, c-b, b-ac		0.045, 0.009, 0.000, 0.054	Worst RFC			0.054	0.053																					
		AM PEAK	(PM) PEAK																																											
TRAFFIC FLOWS	q(c-a), q(c-b), q(a-b), q(a-c), q(b-a), q(b-c), f	45, 0, 15, 95, 20, 5, 0.20	40, 0, 25, 85, 20, 5, 0.20																																											
CAPACITIES	Q(b-a), Q(b-c), Q(c-b), Q(b-ac)	1, 1, 1, 1	445, 573, 663, 466																																											
RFC's	b-a, b-c, c-b, b-ac		0.045, 0.009, 0.000, 0.054																																											
Worst RFC			0.054	0.053																																										
Where $Vl$ and $Vr$ are visibility distances to the left or right of the respective streams $D = (1+0.094(w(b-a)-3.65))(1+0.0009(Vr(b-a)-120))(1+0.0006(Vl(b-a)-150))$ $E = (1+0.094(w(b-c)-3.65))(1+0.0009(Vr(b-c)-120))$ $F = (1+0.094(w(c-b)-3.65))(1+0.0009(Vr(c-b)-120))$ $Y = 1-0.0345W$ $f$ = proportion of minor traffic turning left $Q(b-ac) = Q(b-c)*Q(b-a)/(1-f)*Q(b-c)+f*Q(b-a)$																																														
T.P.D.M.V.2.4 Appendix 1 Capacity of combined streams - in accordance with TPDM V2.4																																														
Calculated by:	HZF	Date:	Jan, 2026	Checked by:																																										
				PTC																																										

### Simplified Priority Junction Capacity Calculation

Job Title:	Proposed Residential Development at Lot No. 4822 in D.D. 104 and Adjoining Government Land, East of Kam Pok Road, Mai Po, Yuen Long			Ref. No.:																																																																													
Junction:	Kam Pok Road / Castle Peak Road – Tam Mi (J6)																																																																																
Scheme:	Observed Case																																																																																
Year:	2025	Job No.:	CHK50868310	Rev.:																																																																													
ARM A:	Castle Peak Road - Tam Mi NB																																																																																
ARM B:	Kam Pok Road EB																																																																																
ARM C:	Castle Peak Road - Tam Mi SB																																																																																
<b>GEOMETRY</b> <table border="1"> <tr> <td>Major road width</td> <td>W</td> <td>6.90</td> <td>Lane widths</td> <td>w(b-a)</td> <td>4.50</td> </tr> <tr> <td>Central Reserve width</td> <td>Wcr</td> <td>0.00</td> <td></td> <td>w(b-c)</td> <td>4.50</td> </tr> <tr> <td>2 Lane Minor Arm (Y/N)</td> <td>N</td> <td></td> <td></td> <td>w(c-b)</td> <td>2.05</td> </tr> <tr> <td>Visibilities</td> <td>Vr(b-a)</td> <td>53</td> <td>Calculated</td> <td>D</td> <td>0.97</td> </tr> <tr> <td></td> <td>Vl(b-a)</td> <td>70</td> <td></td> <td>E</td> <td>1.03</td> </tr> <tr> <td></td> <td>Vr(b-c)</td> <td>70</td> <td></td> <td>F</td> <td>0.78</td> </tr> <tr> <td></td> <td>Vr(c-b)</td> <td>30</td> <td></td> <td>Y</td> <td>0.76</td> </tr> </table>					Major road width	W	6.90	Lane widths	w(b-a)	4.50	Central Reserve width	Wcr	0.00		w(b-c)	4.50	2 Lane Minor Arm (Y/N)	N			w(c-b)	2.05	Visibilities	Vr(b-a)	53	Calculated	D	0.97		Vl(b-a)	70		E	1.03		Vr(b-c)	70		F	0.78		Vr(c-b)	30		Y	0.76																																			
Major road width	W	6.90	Lane widths	w(b-a)	4.50																																																																												
Central Reserve width	Wcr	0.00		w(b-c)	4.50																																																																												
2 Lane Minor Arm (Y/N)	N			w(c-b)	2.05																																																																												
Visibilities	Vr(b-a)	53	Calculated	D	0.97																																																																												
	Vl(b-a)	70		E	1.03																																																																												
	Vr(b-c)	70		F	0.78																																																																												
	Vr(c-b)	30		Y	0.76																																																																												
<b>ANALYSIS</b> <table border="1"> <thead> <tr> <th></th> <th></th> <th>AM PEAK</th> <th>(PM) PEAK</th> </tr> </thead> <tbody> <tr> <td>TRAFFIC FLOWS</td> <td>q(c-a)</td> <td>390</td> <td>285</td> </tr> <tr> <td></td> <td>q(c-b)</td> <td>60</td> <td>45</td> </tr> <tr> <td></td> <td>q(a-b)</td> <td>50</td> <td>65</td> </tr> <tr> <td></td> <td>q(a-c)</td> <td>285</td> <td>350</td> </tr> <tr> <td></td> <td>q(b-a)</td> <td>40</td> <td>40</td> </tr> <tr> <td></td> <td>q(b-c)</td> <td>25</td> <td>20</td> </tr> <tr> <td></td> <td>f</td> <td>0.38</td> <td>0.33</td> </tr> <tr> <td>CAPACITIES</td> <td>Q(b-a)</td> <td>1</td> <td>435</td> <td>440</td> </tr> <tr> <td></td> <td>Q(b-c)</td> <td>1</td> <td>681</td> <td>661</td> </tr> <tr> <td></td> <td>Q(c-b)</td> <td>1</td> <td>509</td> <td>492</td> </tr> <tr> <td></td> <td>Q(b-ac)</td> <td>1</td> <td>505</td> <td>495</td> </tr> <tr> <td>RFC's</td> <td>b-a</td> <td></td> <td>0.092</td> <td>0.091</td> </tr> <tr> <td></td> <td>b-c</td> <td></td> <td>0.037</td> <td>0.030</td> </tr> <tr> <td></td> <td>c-b</td> <td></td> <td>0.118</td> <td>0.091</td> </tr> <tr> <td></td> <td>b-ac</td> <td></td> <td>0.129</td> <td>0.121</td> </tr> <tr> <td>Worst RFC</td> <td></td> <td>0.129</td> <td>0.121</td> <td></td> </tr> </tbody> </table>							AM PEAK	(PM) PEAK	TRAFFIC FLOWS	q(c-a)	390	285		q(c-b)	60	45		q(a-b)	50	65		q(a-c)	285	350		q(b-a)	40	40		q(b-c)	25	20		f	0.38	0.33	CAPACITIES	Q(b-a)	1	435	440		Q(b-c)	1	681	661		Q(c-b)	1	509	492		Q(b-ac)	1	505	495	RFC's	b-a		0.092	0.091		b-c		0.037	0.030		c-b		0.118	0.091		b-ac		0.129	0.121	Worst RFC		0.129	0.121	
		AM PEAK	(PM) PEAK																																																																														
TRAFFIC FLOWS	q(c-a)	390	285																																																																														
	q(c-b)	60	45																																																																														
	q(a-b)	50	65																																																																														
	q(a-c)	285	350																																																																														
	q(b-a)	40	40																																																																														
	q(b-c)	25	20																																																																														
	f	0.38	0.33																																																																														
CAPACITIES	Q(b-a)	1	435	440																																																																													
	Q(b-c)	1	681	661																																																																													
	Q(c-b)	1	509	492																																																																													
	Q(b-ac)	1	505	495																																																																													
RFC's	b-a		0.092	0.091																																																																													
	b-c		0.037	0.030																																																																													
	c-b		0.118	0.091																																																																													
	b-ac		0.129	0.121																																																																													
Worst RFC		0.129	0.121																																																																														
Where $Vl$ and $Vr$ are visibility distances to the left or right of the respective streams $D = (1+0.094(w(b-a)-3.65))(1+0.0009(Vr(b-a)-120))(1+0.0006(Vl(b-a)-150))$ $E = (1+0.094(w(b-c)-3.65))(1+0.0009(Vr(b-c)-120))$ $F = (1+0.094(w(c-b)-3.65))(1+0.0009(Vr(c-b)-120))$ $Y = 1-0.0345W$ $f$ = proportion of minor traffic turning left $Q(b-ac) = Q(b-c)*Q(b-a)/(1-f)*Q(b-c)+f*Q(b-a)$																																																																																	
T.P.D.M.V.2.4 Appendix 1 Capacity of combined streams - in accordance with TPDM V2.4																																																																																	
Calculated by:	HZF	Date:	Jan, 2026	Checked by:																																																																													
				PTC																																																																													

### Simplified Priority Junction Capacity Calculation


Job Title:	Proposed Residential Development at Lot No. 4822 in D.D. 104 and Adjoining Government Land, East of Kam Pok Road, Mai Po, Yuen Long	Ref. No.:
Junction:	Kam Pok Road / Fung Chuk Road (J7)	
Scheme:	Observed Case	
Year:	2025	Job No.: CHK50868310
ARM A:	Kam Pok Road SB	Rev.:
ARM B:	Fung Chuk Road	
ARM C:	Kam Pok Road NB	



Calculated by: HZF Date: Jan, 2026 Checked by: PTC

T.P.D.M.V.2.4  
Appendix 1

# Roundabout Capacity Calculation

Job Title: Proposed Residential Development at Lot No. 4822 in D.D. 104 and Adjoining Government Land, East of Kam Pok Road, Mai Po, Yuen Long																			
Junction: Fairview Park Interchange (J1)								Ref. No.:											
Scheme: Reference Case (with Planned Junction Layout)																			
Year: 2034	Job No.: CHK50868310			Rev.: -															
<b>AM</b> <b>PM</b> ARM A: Fairview Park Boulevard ARM B: Castle Peak Road - Tam Mi (N) ARM C: San Tin Highway Slip Road (N) ARM D: San Tam Road (N) ARM E: San Tam Road (S) ARM F: San Tin Highway Slip Road (S) ARM G: Castle Peak Road - Tam Mi (S)																			
																			
<b>GEOMETRY</b>																			
ARM	v	e	L	r	D	Phi	S												
A	7.00	11.80	20	25	140	35	0.38												
B	7.30	12.00	36	30	140	25	0.21												
C	7.30	13.00	13	45	140	30	0.70												
D	7.30	11.00	23	25	140	35	0.26												
E	7.30	12.00	27	25	140	45	0.28												
F	6.00	12.50	20	25	140	40	0.52												
G	6.50	11.20	22	25	140	35	0.34												
<b>AM FLOWS</b>																			
from \ to	A	B	C	D	E	F	G	Circ	Entry	Exit									
A	10	20	210	40	230	480	30	2840	1020	670									
B	10	10	145	10	250	390	30	3210	845	650									
C	95	75	10	100	485	10	225	2800	1000	1255									
D	65	20	45	10	280	210	95	3325	725	475									
E	40	35	465	120	10	535	20	2155	1225	1895									
F	335	330	10	110	630	10	Free Flow	1420	1425	1960									
G	115	160	370	85	10	325	0	2445	1065	400									
<b>PM FLOWS</b>																			
from \ to	A	B	C	D	E	F	G	Circ	Entry	Exit									
A	10	10	170	55	210	345	30	2540	830	955									
B	35	10	95	10	170	190	30	2740	540	630									
C	190	125	20	85	425	20	210	2390	1075	890									
D	80	20	90	20	250	95	75	2950	630	515									
E	100	30	305	115	10	295	20	1845	875	1735									
F	445	310	10	175	660	20	Free Flow	1535	1620	1185									
G	95	125	200	55	10	220	10	2780	715	375									
<b>CALCULATIONS</b>																			
ARM	K	X <sub>2</sub>	M	F	t <sub>D</sub>	f <sub>c</sub>	AM	PM	AM	PM									
A	0.99	9.71	2980.96	2944	1.00	0.62	1179	1363	0.87	0.61									
B	1.03	10.62	2980.96	3216	1.00	0.66	1148	1467	0.74	0.37									
C	1.03	9.67	2980.96	2931	1.00	0.62	1238	1497	0.81	0.72									
D	0.99	9.74	2980.96	2952	1.00	0.62	886	1117	0.82	0.56									
E	0.96	10.32	2980.96	3127	1.00	0.64	1666	1857	0.74	0.47									
F	0.98	9.19	2980.96	2783	1.00	0.60	1889	1822	0.75	0.89									
G	0.99	9.29	2980.96	2815	1.00	0.60	1337	1138	0.80	0.63									
<b>Critical Arm:</b> A <b>F</b> <b>RFC:</b> <b>0.87</b> <b>0.89</b> <b>AM</b> <b>PM</b>																			
<i>- In accordance with TPDM V2.4</i>																			
Calculated by: HZF	Date: Jan-26	Checked by: PTC																	

**TRAFFIC SIGNALS CALCULATION**

 Job No.: CHK50868310
**MVA HONG KONG LIMITED**

Junction: <u>Kam Pok Road / Fairview Park Boulevard (J2)</u>										Design Year: <u>2034</u>									
Description: <u>Year 2034 Reference Traffic Flows</u>										Designed By: <u>HZF</u>	Checked By: <u>PTC</u>								
Approach	Movements	Phase	Stage	Width (m)	Radius (m)		Gradient (%)	Pro. Turning (%)		Revised Saturation Flow (pcu/hr)		AM Peak			PM Peak				
					Left	Right		AM	PM	AM	PM	Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y		
Fairview Park Boulevard EB	↑→	A	1	3.4	15		8%	9%		1940	1935	428	0.221	0.221	276	0.143			
Fairview Park Boulevard WB	←↓	A	1	3.5	17		24%	26%		1925	1920	336	0.175	0.175	418	0.218	0.218		
Fairview Park Boulevard WB	←→	A	1	3.5						1965	1965	344	0.175	0.175	427	0.217			
Kam Pok Road SB	↔	B	2	5.5	18	18	16% / 44%	18% / 45%		2060	2055	125	0.061	0.061	110	0.054	0.054		
Kam Pok Road NB	↔	C	3	3.8	13	20	7% / 43%	14% / 72%		1920	1865	140	0.073	0.073	180	0.097	0.097		
Pedestrian Crossing				Dp	4	MIN GREEN + FLASH =	10	+	9	=	19	*	*	*	*	*	*		
Notes:				Flow: (pcu/hr)								Group		A.B.C.Dp	Group		A.B.C.Dp		
												y	0.355	y	0.368	L (sec)	44	L (sec)	44
												C (sec)	120	C (sec)	120	y pract.	0.570	y pract.	0.570
												R.C. (%)	61%	R.C. (%)	55%				
Stage / Phase Diagrams																			
1.		2.		3.		4.		5.											
I/G= 3		I/G= 7		I/G= 7		I/G= 11		19		I/G=									
I/G= 3		I/G= 7		I/G= 7		I/G= 11		19		I/G=									
Date: <u>Jan, 2026</u>								Junction: <u>2</u>								<u>J2</u>			

**TRAFFIC SIGNALS CALCULATION**

 Job No.: CHK50868310
**MVA HONG KONG LIMITED**

Junction: <u>Kam Pok Road / Vehicular Bridge – South (J3)</u>												Design Year: <u>2034</u>							
Description: <u>Year 2034 Reference Traffic Flows</u>												Designed By: <u>HZF</u>	Checked By: <u>PTC</u>						
Approach	Movements	Phase	Stage	Width (m)	Radius (m)		Gradient (%)	Pro. Turning (%)		Revised Saturation Flow (pcu/hr)		AM Peak			PM Peak				
					Left	Right		AM	PM	AM	PM	Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y		
Vehicular Bridge (EB) ↑↑				A	1	3.600	10	10	100% / 0%	100% / 0%	1715	1715	15	0.009		10	0.006		
Kam Pok Rd (SB) ↑↑				B	2	3.600		10	8%	9%	1950	1950	130	0.067	0.067	110	0.056		
Kam Pok Rd (NB) ↑↑				C	3	3.600	10		8%	11%	1950	1945	60	0.031	0.031	45	0.023		
Pedestrian Crossing				Dp	4	MIN GREEN + FLASH =	7		+	7	=	14		*		*			
Notes:				Flow: (pcu/hr)								Group		A.B.C.Dp	Group		A.B.C.Dp		
												y		0.097	y		0.080		
												L (sec)		32	L (sec)		32		
												C (sec)		60	C (sec)		60		
												y pract.		0.420	y pract.		0.420		
												R.C. (%)		331%	R.C. (%)		428%		
Stage / Phase Diagrams																			
1.				2.				3.				4.				5.			
I/G= 2	5	I/G= 5			I/G= 5		I/G= 5		I/G= 3	14	I/G=								
I/G= 2	5	I/G= 5			I/G= 5		I/G= 5		I/G= 3	14	I/G=								
Date: <u>Jan, 2026</u>												Junction: <u>3</u> <span style="border: 1px solid black; border-radius: 50%; padding: 2px;">J3</span>							

## TRAFFIC SIGNALS CALCULATION

Job No.: CHK50868310

MVA HONG KONG LIMITED

Junction: <u>Kam Pok Road / Vehicular Bridge – North / Vehicular Access (J4)</u>												Design Year: <u>2034</u>					
Description: <u>Year 2034 Reference Traffic Flows (with Planned Junction Layout)</u>												Designed By: <u>HZF</u>	Checked By: <u>PTC</u>				
Approach	Movements	Phase	Stage	Width (m)	Radius (m)		Gradient (%)	Pro. Turning (%)		Revised Saturation Flow (pcu/hr)		AM Peak			PM Peak		
					Left	Right		AM	PM	AM	PM	Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y
Vehicular Bridge SB	A	1	3.500	10	12		100% / 0%	100% / 0%	1710	1710	15	0.009		10	0.006		
Kam Pok Road EB	D	2	3.650	10	12		0% / 22%	0% / 33%	1925	1900	90	0.047	0.047	75	0.039	0.039	
R(D) Site Access	C	3	5.500	20	12		100%	100%	2015	2015	25	0.012		10	0.005		
	C	3	4.000						1790	1790	230	0.128	0.128	95	0.053	0.053	
Kam Pok Road WB	B	4	3.650	15	12		8%	8%	1800	1800	170	0.094	0.094	105	0.058		
	B	4	3.650						1960	1960	125	0.064	0.064	125	0.064	0.064	
Pedestrian Crossing	Ep	3	MIN GREEN + FLASH =	10	+	10	=	20									
	Fp	1	MIN GREEN + FLASH =	11	+	10	=	21									
	Gp	1,2,4	MIN GREEN + FLASH =	5	+	5	=	10									
Notes:				Flow: (pcu/hr)								Group	Fp,D,C,B	A,D,C,B	Group	Fp,D,C,B	A,D,C,B
												y	0.270	0.270	y	0.156	0.156
												L (sec)	18	31	L (sec)	18	31
												C (sec)	90	90	C (sec)	90	90
												y pract.	0.720	0.590	y pract.	0.720	0.590
												R.C. (%)	167%	119%	R.C. (%)	361%	277%
Stage / Phase Diagrams																	
1.		2.		3.		4.		5.									
I/G= 7	5	I/G= 12			I/G= 5		I/G= 5		I/G= 5		I/G=						
I/G= 7	5	I/G= 12			I/G= 5		I/G= 5		I/G= 5		I/G=						
Date: <u>Jan, 2026</u>												Junction:	4				J4

### Simplified Priority Junction Capacity Calculation

Job Title:	Proposed Residential Development at Lot No. 4822 in D.D. 104 and Adjoining Government Land, East of Kam Pok Road, Mai Po, Yuen Long			Ref. No.:
Junction:	Kam Pok Road / Ha Chuk Yuen Road (J5)			
Scheme:	Reference Case			
Year:	2034	Job No.:	CHK50868310	Rev.:
ARM A:	Kam Pok Road WB			
ARM B:	Ha Chuk Yuen Road			
ARM C:	Kam Pok Road EB			
<b>GEOMETRY</b>				
Major road width	W	9.30	Lane widths	w(b-a) 2.05 w(b-c) 2.05 w(c-b) 3.50
Central Reserve width	Wcr	0.00		
2 Lane Minor Arm (Y/N)	N			
Visibilities	Vr(b-a)	50	Calculated	D 0.75 E 0.80 F 0.92 Y 0.68
	Vl(b-a)	50		
	Vr(b-c)	50		
	Vr(c-b)	50		
<b>ANALYSIS</b>				
			AM PEAK	(PM) PEAK
TRAFFIC FLOWS		q(c-a) q(c-b) q(a-b) q(a-c) q(b-a) q(b-c) f	320 0 15 290 20 5 0.20	150 0 25 220 20 5 0.20
CAPACITIES		Q(b-a) Q(b-c) Q(c-b) Q(b-ac)	Factor 1 1 1 1	377 535 619 401
RFC's		b-a b-c c-b b-ac		0.053 0.009 0.000 0.062
Worst RFC				0.062 0.058
Where $Vl$ and $Vr$ are visibility distances to the left or right of the respective streams $D = (1+0.094(w(b-a)-3.65))(1+0.0009(Vr(b-a)-120))(1+0.0006(Vl(b-a)-150))$ $E = (1+0.094(w(b-c)-3.65))(1+0.0009(Vr(b-c)-120))$ $F = (1+0.094(w(c-b)-3.65))(1+0.0009(Vr(c-b)-120))$ $Y = 1-0.0345W$ $f$ = proportion of minor traffic turning left $Q(b-ac) = Q(b-c)*Q(b-a)/(1-f)*Q(b-c)+f*Q(b-a)$				
T.P.D.M.V.2.4 Appendix 1 Capacity of combined streams - in accordance with TPDM V2.4				
Calculated by:	HZF	Date:	Jan, 2026	Checked by: PTC


### Simplified Priority Junction Capacity Calculation

Job Title:	Proposed Residential Development at Lot No. 4822 in D.D. 104 and Adjoining Government Land, East of Kam Pok Road, Mai Po, Yuen Long			Ref. No.:																																																																													
Junction:	Kam Pok Road / Castle Peak Road – Tam Mi (J6)																																																																																
Scheme:	Reference Case (with Planned Junction Layout)																																																																																
Year:	2034	Job No.:	CHK50868310	Rev.:																																																																													
ARM A:	Castle Peak Road - Tam Mi NB																																																																																
ARM B:	Kam Pok Road EB																																																																																
ARM C:	Castle Peak Road - Tam Mi SB																																																																																
<b>GEOMETRY</b> <table border="1"> <tr> <td>Major road width</td> <td>W</td> <td>6.90</td> <td>Lane widths</td> <td>w(b-a)</td> <td>4.30</td> </tr> <tr> <td>Central Reserve width</td> <td>Wcr</td> <td>1.50</td> <td></td> <td>w(b-c)</td> <td>4.30</td> </tr> <tr> <td>2 Lane Minor Arm (Y/N)</td> <td>Y</td> <td></td> <td></td> <td>w(c-b)</td> <td>2.05</td> </tr> <tr> <td>Visibilities</td> <td>Vr(b-a)</td> <td>53</td> <td>Calculated</td> <td>D</td> <td>0.95</td> </tr> <tr> <td></td> <td>Vl(b-a)</td> <td>70</td> <td></td> <td>E</td> <td>1.01</td> </tr> <tr> <td></td> <td>Vr(b-c)</td> <td>70</td> <td></td> <td>F</td> <td>0.78</td> </tr> <tr> <td></td> <td>Vr(c-b)</td> <td>30</td> <td></td> <td>Y</td> <td>0.76</td> </tr> </table>					Major road width	W	6.90	Lane widths	w(b-a)	4.30	Central Reserve width	Wcr	1.50		w(b-c)	4.30	2 Lane Minor Arm (Y/N)	Y			w(c-b)	2.05	Visibilities	Vr(b-a)	53	Calculated	D	0.95		Vl(b-a)	70		E	1.01		Vr(b-c)	70		F	0.78		Vr(c-b)	30		Y	0.76																																			
Major road width	W	6.90	Lane widths	w(b-a)	4.30																																																																												
Central Reserve width	Wcr	1.50		w(b-c)	4.30																																																																												
2 Lane Minor Arm (Y/N)	Y			w(c-b)	2.05																																																																												
Visibilities	Vr(b-a)	53	Calculated	D	0.95																																																																												
	Vl(b-a)	70		E	1.01																																																																												
	Vr(b-c)	70		F	0.78																																																																												
	Vr(c-b)	30		Y	0.76																																																																												
<b>ANALYSIS</b> <table border="1"> <thead> <tr> <th></th> <th></th> <th>AM PEAK</th> <th>(PM) PEAK</th> </tr> </thead> <tbody> <tr> <td>TRAFFIC FLOWS</td> <td>q(c-a)</td> <td>555</td> <td>395</td> </tr> <tr> <td></td> <td>q(c-b)</td> <td>135</td> <td>75</td> </tr> <tr> <td></td> <td>q(a-b)</td> <td>170</td> <td>170</td> </tr> <tr> <td></td> <td>q(a-c)</td> <td>385</td> <td>465</td> </tr> <tr> <td></td> <td>q(b-a)</td> <td>250</td> <td>130</td> </tr> <tr> <td></td> <td>q(b-c)</td> <td>90</td> <td>45</td> </tr> <tr> <td></td> <td>f</td> <td>0.26</td> <td>0.26</td> </tr> <tr> <td>CAPACITIES</td> <td>Q(b-a)</td> <td>1</td> <td>353</td> <td>381</td> </tr> <tr> <td></td> <td>Q(b-c)</td> <td>1</td> <td>628</td> <td>605</td> </tr> <tr> <td></td> <td>Q(c-b)</td> <td>1</td> <td>461</td> <td>444</td> </tr> <tr> <td></td> <td>Q(b-ac)</td> <td>1</td> <td>399</td> <td>421</td> </tr> <tr> <td>RFC's</td> <td>b-a</td> <td></td> <td>0.708</td> <td>0.341</td> </tr> <tr> <td></td> <td>b-c</td> <td></td> <td>0.143</td> <td>0.074</td> </tr> <tr> <td></td> <td>c-b</td> <td></td> <td>0.293</td> <td>0.169</td> </tr> <tr> <td></td> <td>b-ac</td> <td></td> <td>0.000</td> <td>0.000</td> </tr> <tr> <td>Worst RFC</td> <td></td> <td></td> <td>0.708</td> <td>0.341</td> </tr> </tbody> </table>							AM PEAK	(PM) PEAK	TRAFFIC FLOWS	q(c-a)	555	395		q(c-b)	135	75		q(a-b)	170	170		q(a-c)	385	465		q(b-a)	250	130		q(b-c)	90	45		f	0.26	0.26	CAPACITIES	Q(b-a)	1	353	381		Q(b-c)	1	628	605		Q(c-b)	1	461	444		Q(b-ac)	1	399	421	RFC's	b-a		0.708	0.341		b-c		0.143	0.074		c-b		0.293	0.169		b-ac		0.000	0.000	Worst RFC			0.708	0.341
		AM PEAK	(PM) PEAK																																																																														
TRAFFIC FLOWS	q(c-a)	555	395																																																																														
	q(c-b)	135	75																																																																														
	q(a-b)	170	170																																																																														
	q(a-c)	385	465																																																																														
	q(b-a)	250	130																																																																														
	q(b-c)	90	45																																																																														
	f	0.26	0.26																																																																														
CAPACITIES	Q(b-a)	1	353	381																																																																													
	Q(b-c)	1	628	605																																																																													
	Q(c-b)	1	461	444																																																																													
	Q(b-ac)	1	399	421																																																																													
RFC's	b-a		0.708	0.341																																																																													
	b-c		0.143	0.074																																																																													
	c-b		0.293	0.169																																																																													
	b-ac		0.000	0.000																																																																													
Worst RFC			0.708	0.341																																																																													
Where $Vl$ and $Vr$ are visibility distances to the left or right of the respective streams $D = (1+0.094(w(b-a)-3.65))(1+0.0009(Vr(b-a)-120))(1+0.0006(Vl(b-a)-150))$ $E = (1+0.094(w(b-c)-3.65))(1+0.0009(Vr(b-c)-120))$ $F = (1+0.094(w(c-b)-3.65))(1+0.0009(Vr(c-b)-120))$ $Y = 1-0.0345W$ $f$ = proportion of minor traffic turning left $Q(b-ac) = Q(b-c)*Q(b-a)/(1-f)*Q(b-c)+f*Q(b-a)$																																																																																	
T.P.D.M.V.2.4 Appendix 1 Capacity of combined streams - in accordance with TPDM V2.4																																																																																	
Calculated by:	HZF	Date:	Jan, 2026	Checked by:																																																																													
				PTC																																																																													

### Simplified Priority Junction Capacity Calculation

Job Title:	Proposed Residential Development at Lot No. 4822 in D.D. 104 and Adjoining Government Land, East of Kam Pok Road, Mai Po, Yuen Long			Ref. No.:																																																																				
Junction:	Kam Pok Road / Fung Chuk Road (J7)																																																																							
Scheme:	Reference Case																																																																							
Year:	2025	Job No.:	CHK50868310	Rev.:																																																																				
ARM A:	Kam Pok Road SB																																																																							
ARM B:	Fung Chuk Road																																																																							
ARM C:	Kam Pok Road NB																																																																							
<b>GEOMETRY</b> <table border="1"> <tr> <td>Major road width</td> <td>W</td> <td>7.30</td> <td>Lane widths</td> <td>w(b-a)</td> <td>2.00</td> </tr> <tr> <td>Central Reserve width</td> <td>Wcr</td> <td>0.00</td> <td></td> <td>w(b-c)</td> <td>2.00</td> </tr> <tr> <td>2 Lane Minor Arm (Y/N)</td> <td>N</td> <td></td> <td></td> <td>w(c-b)</td> <td>3.50</td> </tr> <tr> <td>Visibilities</td> <td>Vr(b-a)</td> <td>12</td> <td>Calculated</td> <td>D</td> <td>0.70</td> </tr> <tr> <td></td> <td>Vl(b-a)</td> <td>8.5</td> <td></td> <td>E</td> <td>0.76</td> </tr> <tr> <td></td> <td>Vr(b-c)</td> <td>12</td> <td></td> <td>F</td> <td>0.90</td> </tr> <tr> <td></td> <td>Vr(c-b)</td> <td>21</td> <td></td> <td>Y</td> <td>0.75</td> </tr> </table>					Major road width	W	7.30	Lane widths	w(b-a)	2.00	Central Reserve width	Wcr	0.00		w(b-c)	2.00	2 Lane Minor Arm (Y/N)	N			w(c-b)	3.50	Visibilities	Vr(b-a)	12	Calculated	D	0.70		Vl(b-a)	8.5		E	0.76		Vr(b-c)	12		F	0.90		Vr(c-b)	21		Y	0.75																										
Major road width	W	7.30	Lane widths	w(b-a)	2.00																																																																			
Central Reserve width	Wcr	0.00		w(b-c)	2.00																																																																			
2 Lane Minor Arm (Y/N)	N			w(c-b)	3.50																																																																			
Visibilities	Vr(b-a)	12	Calculated	D	0.70																																																																			
	Vl(b-a)	8.5		E	0.76																																																																			
	Vr(b-c)	12		F	0.90																																																																			
	Vr(c-b)	21		Y	0.75																																																																			
<b>ANALYSIS</b> <table border="1"> <thead> <tr> <th></th> <th></th> <th>AM PEAK</th> <th>(PM) PEAK</th> </tr> </thead> <tbody> <tr> <td>TRAFFIC FLOWS</td> <td>q(c-a)</td> <td>70</td> <td>50</td> </tr> <tr> <td></td> <td>q(c-b)</td> <td>0</td> <td>5</td> </tr> <tr> <td></td> <td>q(a-b)</td> <td>0</td> <td>0</td> </tr> <tr> <td></td> <td>q(a-c)</td> <td>115</td> <td>115</td> </tr> <tr> <td></td> <td>q(b-a)</td> <td>0</td> <td>0</td> </tr> <tr> <td></td> <td>q(b-c)</td> <td>5</td> <td>5</td> </tr> <tr> <td></td> <td>f</td> <td>1.00</td> <td>1.00</td> </tr> <tr> <td>CAPACITIES</td> <td>Q(b-a)</td> <td>407</td> <td>408</td> </tr> <tr> <td></td> <td>Q(b-c)</td> <td>544</td> <td>544</td> </tr> <tr> <td></td> <td>Q(c-b)</td> <td>641</td> <td>641</td> </tr> <tr> <td></td> <td>Q(b-ac)</td> <td>544</td> <td>544</td> </tr> <tr> <td>RFC's</td> <td>b-a</td> <td>0.000</td> <td>0.000</td> </tr> <tr> <td></td> <td>b-c</td> <td>0.009</td> <td>0.009</td> </tr> <tr> <td></td> <td>c-b</td> <td>0.000</td> <td>0.008</td> </tr> <tr> <td></td> <td>b-ac</td> <td>0.009</td> <td>0.009</td> </tr> <tr> <td>Worst RFC</td> <td></td> <td>0.009</td> <td>0.009</td> </tr> </tbody> </table>							AM PEAK	(PM) PEAK	TRAFFIC FLOWS	q(c-a)	70	50		q(c-b)	0	5		q(a-b)	0	0		q(a-c)	115	115		q(b-a)	0	0		q(b-c)	5	5		f	1.00	1.00	CAPACITIES	Q(b-a)	407	408		Q(b-c)	544	544		Q(c-b)	641	641		Q(b-ac)	544	544	RFC's	b-a	0.000	0.000		b-c	0.009	0.009		c-b	0.000	0.008		b-ac	0.009	0.009	Worst RFC		0.009	0.009
		AM PEAK	(PM) PEAK																																																																					
TRAFFIC FLOWS	q(c-a)	70	50																																																																					
	q(c-b)	0	5																																																																					
	q(a-b)	0	0																																																																					
	q(a-c)	115	115																																																																					
	q(b-a)	0	0																																																																					
	q(b-c)	5	5																																																																					
	f	1.00	1.00																																																																					
CAPACITIES	Q(b-a)	407	408																																																																					
	Q(b-c)	544	544																																																																					
	Q(c-b)	641	641																																																																					
	Q(b-ac)	544	544																																																																					
RFC's	b-a	0.000	0.000																																																																					
	b-c	0.009	0.009																																																																					
	c-b	0.000	0.008																																																																					
	b-ac	0.009	0.009																																																																					
Worst RFC		0.009	0.009																																																																					
Where $Vl$ and $Vr$ are visibility distances to the left or right of the respective streams $D = (1+0.094(w(b-a)-3.65))(1+0.0009(Vr(b-a)-120))(1+0.0006(Vl(b-a)-150))$ $E = (1+0.094(w(b-c)-3.65))(1+0.0009(Vr(b-c)-120))$ $F = (1+0.094(w(c-b)-3.65))(1+0.0009(Vr(c-b)-120))$ $Y = 1-0.0345W$ $f$ = proportion of minor traffic turning left $Q(b-ac) = Q(b-c)*Q(b-a)/(1-f)*Q(b-c)+f*Q(b-a)$																																																																								
T.P.D.M.V.2.4 Appendix 1 Capacity of combined streams - in accordance with TPDM V2.4																																																																								
Calculated by:	HZF	Date:	Jan, 2026	Checked by:	PTC																																																																			





## Roundabout Capacity Calculation

Job Title: Proposed Residential Development at Lot No. 4822 in D.D. 104 and Adjoining Government Land, East of Kam Pok Road, Mai Po, Yuen Long																			
Junction: Fairview Park Interchange (J1)								Ref. No.:											
Scheme: Design Case (with Planned Junction Layout)																			
Year: 2034	Job No.:			CHK50868310			Rev.:	-											
AM PM																			
ARM A: Fairview Park Boulevard																			
ARM B: Castle Peak Road - Tam Mi (N)																			
ARM C: San Tin Highway Slip Road (N)																			
ARM D: San Tam Road (N)																			
ARM E: San Tam Road (S)																			
ARM F: San Tin Highway Slip Road (S)																			
ARM G: Castle Peak Road - Tam Mi (S)																			
																			
GEOMETRY																			
ARM	v	e	L	r	D	Phi	S												
A	7.00	11.80	20	25	140	35	0.38												
B	7.30	12.00	36	30	140	25	0.21												
C	7.30	13.00	13	45	140	30	0.70												
D	7.30	11.00	23	25	140	35	0.26												
E	7.30	12.00	27	25	140	45	0.28												
F	6.00	12.50	20	25	140	40	0.52												
G	6.50	11.20	22	25	140	35	0.34												
AM FLOWS																			
from \ to	A	B	C	D	E	F	G	Circ	Entry	Exit									
A	10	20	210	40	230	480	30	2925	1020	670									
B	10	10	170	35	250	465	30	3210	970	735									
C	95	80	10	100	485	10	225	2900	1005	1280									
D	65	45	45	10	280	210	95	3405	750	500									
E	40	35	465	120	10	535	20	2260	1225	1895									
F	335	385	10	110	630	10	Free Flow	1450	1480	2035									
G	115	160	370	85	10	325	0	2530	1065	400									
PM FLOWS																			
from \ to	A	B	C	D	E	F	G	Circ	Entry	Exit									
A	10	10	170	55	210	345	30	2605	830	955									
B	35	10	105	35	170	215	30	2740	600	695									
C	190	135	20	85	425	20	210	2440	1085	900									
D	80	45	90	20	250	95	75	2985	655	540									
E	100	30	305	115	10	295	20	1905	875	1735									
F	445	340	10	175	660	20	Free Flow	1570	1650	1210									
G	95	125	200	55	10	220	10	2845	715	375									
CALCULATIONS																			
ARM	K	X <sub>2</sub>	M	F	t <sub>D</sub>	f <sub>c</sub>	AM	PM	Q <sub>E</sub>	RFC									
A	0.99	9.71	2980.96	2944	1.00	0.62	1127	1323	0.91	0.63									
B	1.03	10.62	2980.96	3216	1.00	0.66	1148	1467	0.84	0.41									
C	1.03	9.67	2980.96	2931	1.00	0.62	1174	1466	0.86	0.74									
D	0.99	9.74	2980.96	2952	1.00	0.62	837	1095	0.90	0.60									
E	0.96	10.32	2980.96	3127	1.00	0.64	1602	1820	0.76	0.48									
F	0.98	9.19	2980.96	2783	1.00	0.60	1872	1802	0.79	0.92									
G	0.99	9.29	2980.96	2815	1.00	0.60	1287	1099	0.83	0.65									
Critical Arm: A F																			
RFC: 0.91 0.92																			
AM PM																			
- In accordance with TPDM V2.4																			
Calculated by: HZF	Date: Jan-26	Checked by:			PTC														

## TRAFFIC SIGNALS CALCULATION

Job No.: CHK50868310

MVA HONG KONG LIMITED

Junction: <u>Kam Pok Road / Fairview Park Boulevard (J2)</u>										Design Year: <u>2034</u>							
Description: <u>Year 2034 Design Traffic Flows</u>										Designed By: <u>HZF</u>	Checked By: <u>PTC</u>						
Approach	Movements	Phase	Stage	Width (m)	Radius (m)		Gradient (%)	Pro. Turning (%)		Revised Saturation Flow (pcu/hr)		AM Peak			PM Peak		
					Left	Right		AM	PM	AM	PM	Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y
Fairview Park Boulevard EB	↑→	A	1	3.4	15		8%	9%		1940	1935	428	0.221	0.221	276	0.143	
Fairview Park Boulevard WB	←↓	A	1	3.5	17		24%	26%		1925	1920	336	0.175	0.175	418	0.218	0.218
Fairview Park Boulevard WB	←→	A	1	3.5			15% / 42%	18% / 45%		1965	1965	344	0.175	0.175	427	0.217	
Kam Pok Road SB	↔	B	2	5.5	18	18				2065	2055	130	0.063	0.063	110	0.054	0.054
Kam Pok Road NB	↔	C	3	3.8	13	20	7% / 41%	14% / 70%		1920	1865	145	0.076	0.076	185	0.099	0.099
Pedestrian Crossing Dp 4 MIN GREEN + FLASH = 10 + 9 = 19 *																	
Notes:				Flow: (pcu/hr)								Group		A.B.C.Dp	Group		A.B.C.Dp
												y		0.359	y		0.370
												L (sec)		44	L (sec)		44
												C (sec)		120	C (sec)		120
												y pract.		0.570	y pract.		0.570
												R.C. (%)		59%	R.C. (%)		54%
Stage / Phase Diagrams																	
1.		2.		3.		4.		5.									
																	
I/G= 3		I/G= 7		I/G= 7		I/G= 7		I/G= 11		19		I/G=					
I/G= 3		I/G= 7		I/G= 7		I/G= 7		I/G= 11		19		I/G=					
Date: <u>Jan, 2026</u>										Junction: <u>2</u>		J2					

**TRAFFIC SIGNALS CALCULATION**





 Job No.: CHK50868310
**MVA HONG KONG LIMITED**

Junction: <u>Kam Pok Road / Vehicular Bridge – South (J3)</u>												Design Year: <u>2034</u>						
Description: <u>Year 2034 Design Traffic Flows</u>												Designed By: <u>HZF</u>	Checked By: <u>PTC</u>					
Approach	Movements	Phase	Stage	Width (m)	Radius (m)		Gradient (%)	Pro. Turning (%)		Revised Saturation Flow (pcu/hr)		AM Peak			PM Peak			
					Left	Right		AM	PM	AM	PM	Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y	
Vehicular Bridge (EB)	↑↑	A	1	3.600	10	10		100% / 0%	100% / 0%	1715	1715	15	0.009		10	0.006		
Kam Pok Rd (SB)	↑↑	B	2	3.600		10		4%	6%	1960	1960	235	0.120	0.120	170	0.087	0.087	
Kam Pok Rd (NB)	↑↑	C	3	3.600	10			3%	5%	1970	1960	200	0.102	0.102	100	0.051	0.051	
Pedestrian Crossing				Dp	4	MIN GREEN + FLASH =		7	+	7	=	14	*	*	*	*	*	
Notes:				Flow: (pcu/hr)								↑ N	Group		A,B,C,Dp	Group		A,B,C,Dp
														y	0.221	y	0.138	
												L (sec)	32	L (sec)	32			
												C (sec)	60	C (sec)	60			
												y pract.	0.420	y pract.	0.420			
												R.C. (%)	90%	R.C. (%)	205%			
Stage / Phase Diagrams																		
1.			2.			3.			4.			5.						
I/G= 2	5	I/G= 5				I/G= 5			I/G= 3	14	I/G=							
I/G= 2	5	I/G= 5				I/G= 5			I/G= 3	14	I/G=							
Date: <u>Jan, 2026</u>												Junction: <u>3</u>						

## TRAFFIC SIGNALS CALCULATION

Job No.: CHK50868310

MVA HONG KONG LIMITED

Junction: <u>Kam Pok Road / Vehicular Bridge – North / Vehicular Access (J4)</u>												Design Year: <u>2034</u>					
Description: <u>Year 2034 Design Traffic Flows (with Planned Junction Layout)</u>												Designed By: <u>HZF</u>	Checked By: <u>PTC</u>				
Approach	Movements	Phase	Stage	Width (m)	Radius (m)		Gradient (%)	Pro. Turning (%)		Revised Saturation Flow (pcu/hr)		AM Peak			PM Peak		
					Left	Right		AM	PM	AM	PM	Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y
Vehicular Bridge SB	A	1	3.500	10	12		100% / 0%	100% / 0%	1710	1710	15	0.009		10	0.006		
Kam Pok Road EB	D	2	3.650	10	12		0% / 8%	0% / 19%	1960	1935	240	0.122	0.122	135	0.070	0.070	
R(D) Site Access	C	3	5.500	20	12		100%	100%	2015	2015	25	0.012		10	0.005		
	C	3	4.000						1790	1790	230	0.128	0.128	95	0.053	0.053	
Kam Pok Road WB	B	4	3.650	15	12		4%	5%	1800	1800	170	0.094		105	0.058		
	B	4	3.650						1970	1965	245	0.124	0.124	195	0.099	0.099	
Pedestrian Crossing	Ep	3	MIN GREEN + FLASH =	10	+	10	=	20									
	Fp	1	MIN GREEN + FLASH =	11	+	10	=	21									
	Gp	1,2,4	MIN GREEN + FLASH =	5	+	5	=	10									
Notes:				Flow: (pcu/hr)								Group	Fp,D,C,B	A,D,C,B	Group	Fp,D,C,B	A,D,C,B
				0(0)		15(10)											
				0(0)		10(10)						y	0.375	0.375	y	0.222	0.222
				220(110)		235(185)						L (sec)	18	31	L (sec)	18	31
				20(25)		230(95)						C (sec)	90	90	C (sec)	90	90
				25(10)		170(105)						y pract.	0.720	0.590	y pract.	0.720	0.590
												R.C. (%)	92%	57%	R.C. (%)	224%	166%
Stage / Phase Diagrams																	
1.		2.		3.		4.		5.									
																	
I/G= 7	5	I/G= 12				I/G= 5			I/G= 5			I/G=			I/G=		
I/G= 7	5	I/G= 12				I/G= 5			I/G= 5			I/G=			I/G=		
Date: <u>Jan, 2026</u>												Junction: <u>4</u>			J4		

### Simplified Priority Junction Capacity Calculation

Job Title:	Proposed Residential Development at Lot No. 4822 in D.D. 104 and Adjoining Government Land, East of Kam Pok Road, Mai Po, Yuen Long																																												
Junction:	Kam Pok Road / Ha Chuk Yuen Road (J5)																																												
Scheme:	Design Case																																												
Year:	2034	Job No.:	CHK50868310																																										
ARM A:	Kam Pok Road WB	Rev.:																																											
ARM B:	Ha Chuk Yuen Road																																												
ARM C:	Kam Pok Road EB																																												
<b>GEOMETRY</b> <table border="1"> <tr> <td>Major road width</td> <td>W</td> <td>9.30</td> <td>Lane widths</td> <td>w(b-a)</td> <td>2.05</td> </tr> <tr> <td>Central Reserve width</td> <td>Wcr</td> <td>0.00</td> <td></td> <td>w(b-c)</td> <td>2.05</td> </tr> <tr> <td>2 Lane Minor Arm (Y/N)</td> <td>N</td> <td></td> <td></td> <td>w(c-b)</td> <td>3.50</td> </tr> <tr> <td>Visibilities</td> <td>Vr(b-a)</td> <td>50</td> <td>Calculated</td> <td>D</td> <td>0.75</td> </tr> <tr> <td></td> <td>Vl(b-a)</td> <td>50</td> <td></td> <td>E</td> <td>0.80</td> </tr> <tr> <td></td> <td>Vr(b-c)</td> <td>50</td> <td></td> <td>F</td> <td>0.92</td> </tr> <tr> <td></td> <td>Vr(c-b)</td> <td>50</td> <td></td> <td>Y</td> <td>0.68</td> </tr> </table>				Major road width	W	9.30	Lane widths	w(b-a)	2.05	Central Reserve width	Wcr	0.00		w(b-c)	2.05	2 Lane Minor Arm (Y/N)	N			w(c-b)	3.50	Visibilities	Vr(b-a)	50	Calculated	D	0.75		Vl(b-a)	50		E	0.80		Vr(b-c)	50		F	0.92		Vr(c-b)	50		Y	0.68
Major road width	W	9.30	Lane widths	w(b-a)	2.05																																								
Central Reserve width	Wcr	0.00		w(b-c)	2.05																																								
2 Lane Minor Arm (Y/N)	N			w(c-b)	3.50																																								
Visibilities	Vr(b-a)	50	Calculated	D	0.75																																								
	Vl(b-a)	50		E	0.80																																								
	Vr(b-c)	50		F	0.92																																								
	Vr(c-b)	50		Y	0.68																																								
<b>ANALYSIS</b> <table border="1"> <thead> <tr> <th></th> <th></th> <th>AM PEAK</th> <th>(PM) PEAK</th> </tr> </thead> <tbody> <tr> <td>TRAFFIC FLOWS</td> <td>q(c-a) q(c-b) q(a-b) q(a-c) q(b-a) q(b-c) f</td> <td>470 0 15 410 20 5 0.20</td> <td>215 0 25 290 20 5 0.20</td> </tr> <tr> <td>CAPACITIES</td> <td>Q(b-a) Q(b-c) Q(c-b) Q(b-ac)</td> <td>1 1 1 1</td> <td>Factor 338 511 591 363</td> <td>389 534 616 411</td> </tr> <tr> <td>RFC's</td> <td>b-a b-c c-b b-ac</td> <td></td> <td>0.059 0.010 0.000 0.069</td> <td>0.051 0.009 0.000 0.061</td> </tr> <tr> <td>Worst RFC</td> <td></td> <td></td> <td>0.069</td> <td>0.061</td> </tr> </tbody> </table>						AM PEAK	(PM) PEAK	TRAFFIC FLOWS	q(c-a) q(c-b) q(a-b) q(a-c) q(b-a) q(b-c) f	470 0 15 410 20 5 0.20	215 0 25 290 20 5 0.20	CAPACITIES	Q(b-a) Q(b-c) Q(c-b) Q(b-ac)	1 1 1 1	Factor 338 511 591 363	389 534 616 411	RFC's	b-a b-c c-b b-ac		0.059 0.010 0.000 0.069	0.051 0.009 0.000 0.061	Worst RFC			0.069	0.061																			
		AM PEAK	(PM) PEAK																																										
TRAFFIC FLOWS	q(c-a) q(c-b) q(a-b) q(a-c) q(b-a) q(b-c) f	470 0 15 410 20 5 0.20	215 0 25 290 20 5 0.20																																										
CAPACITIES	Q(b-a) Q(b-c) Q(c-b) Q(b-ac)	1 1 1 1	Factor 338 511 591 363	389 534 616 411																																									
RFC's	b-a b-c c-b b-ac		0.059 0.010 0.000 0.069	0.051 0.009 0.000 0.061																																									
Worst RFC			0.069	0.061																																									
Where $Vl$ and $Vr$ are visibility distances to the left or right of the respective streams $D = (1+0.094(w(b-a)-3.65))(1+0.0009(Vr(b-a)-120))(1+0.0006(Vl(b-a)-150))$ $E = (1+0.094(w(b-c)-3.65))(1+0.0009(Vr(b-c)-120))$ $F = (1+0.094(w(c-b)-3.65))(1+0.0009(Vr(c-b)-120))$ $Y = 1-0.0345W$ $f$ = proportion of minor traffic turning left $Q(b-ac) = Q(b-c)*Q(b-a)/(1-f)*Q(b-c)+f*Q(b-a)$																																													
T.P.D.M.V.2.4 Appendix 1 Capacity of combined streams - in accordance with TPDM V2.4																																													
Calculated by:	HZF	Date:	Jan, 2026																																										
Checked by:		PTC																																											

## Simplified Priority Junction Capacity Calculation


Job Title:	Proposed Residential Development at Lot No. 4822 in D.D. 104 and Adjoining Government Land, East of Kam Pok Road, Mai Po, Yuen Long			Ref. No.:																																										
Junction:	Kam Pok Road / Castle Peak Road – Tam Mi (J6)																																													
Scheme:	Design Case (with Planned Junction Layout)																																													
Year:	2034			Job No.: CHK50868310																																										
ARM A:	Castle Peak Road - Tam Mi NB			Rev.:																																										
ARM B:	Kam Pok Road EB																																													
ARM C:	Castle Peak Road - Tam Mi SB																																													
<b>GEOMETRY</b> <table border="1"> <tr> <td>Major road width</td> <td>W</td> <td>6.90</td> <td>Lane widths</td> <td>w(b-a)</td> <td>4.30</td> </tr> <tr> <td>Central Reserve width</td> <td>Wcr</td> <td>1.50</td> <td></td> <td>w(b-c)</td> <td>4.30</td> </tr> <tr> <td>2 Lane Minor Arm (Y/N)</td> <td>Y</td> <td></td> <td></td> <td>w(c-b)</td> <td>2.05</td> </tr> <tr> <td>Visibilities</td> <td>Vr(b-a)</td> <td>53</td> <td>Calculated</td> <td>D</td> <td>0.95</td> </tr> <tr> <td></td> <td>Vl(b-a)</td> <td>70</td> <td></td> <td>E</td> <td>1.01</td> </tr> <tr> <td></td> <td>Vr(b-c)</td> <td>70</td> <td></td> <td>F</td> <td>0.78</td> </tr> <tr> <td></td> <td>Vr(c-b)</td> <td>30</td> <td></td> <td>Y</td> <td>0.76</td> </tr> </table>					Major road width	W	6.90	Lane widths	w(b-a)	4.30	Central Reserve width	Wcr	1.50		w(b-c)	4.30	2 Lane Minor Arm (Y/N)	Y			w(c-b)	2.05	Visibilities	Vr(b-a)	53	Calculated	D	0.95		Vl(b-a)	70		E	1.01		Vr(b-c)	70		F	0.78		Vr(c-b)	30		Y	0.76
Major road width	W	6.90	Lane widths	w(b-a)	4.30																																									
Central Reserve width	Wcr	1.50		w(b-c)	4.30																																									
2 Lane Minor Arm (Y/N)	Y			w(c-b)	2.05																																									
Visibilities	Vr(b-a)	53	Calculated	D	0.95																																									
	Vl(b-a)	70		E	1.01																																									
	Vr(b-c)	70		F	0.78																																									
	Vr(c-b)	30		Y	0.76																																									
<b>ANALYSIS</b> <table border="1"> <thead> <tr> <th></th> <th></th> <th>AM PEAK</th> <th>(PM) PEAK</th> </tr> </thead> <tbody> <tr> <td>TRAFFIC FLOWS</td> <td>q(c-a) q(c-b) q(a-b) q(a-c) q(b-a) q(b-c) f</td> <td>555 175 250 385 375 115 0.23</td> <td>395 85 235 465 185 55 0.23</td> </tr> <tr> <td>CAPACITIES</td> <td>Q(b-a) Q(b-c) Q(c-b) Q(b-ac)</td> <td>1 1 1 1</td> <td>330 619 444 371</td> </tr> <tr> <td>RFC's</td> <td>b-a b-c c-b b-ac</td> <td>Factor</td> <td>1.136 0.186 0.394 0.000</td> </tr> <tr> <td>Worst RFC</td> <td></td> <td></td> <td>1.136</td> <td>0.499</td> </tr> </tbody> </table>							AM PEAK	(PM) PEAK	TRAFFIC FLOWS	q(c-a) q(c-b) q(a-b) q(a-c) q(b-a) q(b-c) f	555 175 250 385 375 115 0.23	395 85 235 465 185 55 0.23	CAPACITIES	Q(b-a) Q(b-c) Q(c-b) Q(b-ac)	1 1 1 1	330 619 444 371	RFC's	b-a b-c c-b b-ac	Factor	1.136 0.186 0.394 0.000	Worst RFC			1.136	0.499																					
		AM PEAK	(PM) PEAK																																											
TRAFFIC FLOWS	q(c-a) q(c-b) q(a-b) q(a-c) q(b-a) q(b-c) f	555 175 250 385 375 115 0.23	395 85 235 465 185 55 0.23																																											
CAPACITIES	Q(b-a) Q(b-c) Q(c-b) Q(b-ac)	1 1 1 1	330 619 444 371																																											
RFC's	b-a b-c c-b b-ac	Factor	1.136 0.186 0.394 0.000																																											
Worst RFC			1.136	0.499																																										
Where $Vl$ and $Vr$ are visibility distances to the left or right of the respective streams $D = (1+0.094(w(b-a)-3.65))(1+0.0009(Vr(b-a)-120))(1+0.0006(Vl(b-a)-150))$ $E = (1+0.094(w(b-c)-3.65))(1+0.0009(Vr(b-c)-120))$ $F = (1+0.094(w(c-b)-3.65))(1+0.0009(Vr(c-b)-120))$ $Y = 1-0.0345W$ $f$ = proportion of minor traffic turning left $Q(b-ac) = Q(b-c)*Q(b-a)/(1-f)*Q(b-c)+f*Q(b-a)$																																														
T.P.D.M.V.2.4 Appendix 1 Capacity of combined streams - in accordance with TPDM V2.4																																														
Calculated by:	HZF	Date:	Jan, 2026	Checked by:	PTC																																									

### Simplified Priority Junction Capacity Calculation


Job Title:	Proposed Residential Development at Lot No. 4822 in D.D. 104 and Adjoining Government Land, East of Kam Pok Road, Mai Po, Yuen Long		
Junction:	Kam Pok Road / Fung Chuk Road (J7)		
Scheme:	Design Case	Ref. No.:	
Year:	2025	Job No.:	CHK50868310
ARM A:	Kam Pok Road SB	Rev.:	
ARM B:	Fung Chuk Road		
ARM C:	Kam Pok Road NB		

ARM C	AM (PM)	210 (105)		
	0 (5)			
ARM A	AM (PM)	225 (175)		
	10 (10)			
Minor ARM B	AM (PM)	5 (10)		
	(5) (10)			
<b>GEOMETRY</b>				
Major road width	W	7.30	Lane widths	w(b-a) 2.00
Central Reserve width	Wcr	0.00		w(b-c) 2.00
2 Lane Minor Arm (Y/N)	N			w(c-b) 3.50
Visibilities	Vr(b-a)	12	Calculated	D 0.70
	Vl(b-a)	8.5		E 0.76
	Vr(b-c)	12		F 0.90
	Vr(c-b)	21		Y 0.75
<b>ANALYSIS</b>				
			AM PEAK	(PM) PEAK
TRAFFIC FLOWS	q(c-a)		210	105
	q(c-b)		0	5
	q(a-b)		10	10
	q(a-c)		225	175
	q(b-a)		10	10
	q(b-c)		5	5
	f		0.33	0.33
CAPACITIES	Q(b-a)	Factor	369	390
	Q(b-c)	1	521	531
	Q(c-b)	1	612	624
	Q(b-ac)	1	409	428
RFC's	b-a		0.027	0.026
	b-c		0.010	0.009
	c-b		0.000	0.008
	b-ac		0.037	0.035
Worst RFC			0.037	0.035
Where Vl and Vr are visibility distances to the left or right of the respective streams				
$D = (1+0.094(w(b-a)-3.65))(1+0.0009(Vr(b-a)-120))(1+0.0006(Vl(b-a)-150))$				
$E = (1+0.094(w(b-c)-3.65))(1+0.0009(Vr(b-c)-120))$				
$F = (1+0.094(w(c-b)-3.65))(1+0.0009(Vr(c-b)-120))$				
$Y = 1-0.0345W$				
f = proportion of minor traffic turning left				
$Q(b-ac) = Q(b-c)*Q(b-a)/(1-f)*Q(b-c)+f*Q(b-a)$				
Capacity of combined streams - in accordance with TPDM V2.4				
Calculated by:	HZF	Date:	Jan, 2026	Checked by: PTC


# Roundabout Capacity Calculation

Job Title: Proposed Residential Development at Lot No. 4822 in D.D. 104 and Adjoining Government Land, East of Kam Pok Road, Mai Po, Yuen Long																			
Junction: Fairview Park Interchange (J1)								Ref. No.:											
Scheme: Design Case (with Proposed Junction Layout)																			
Year: 2034	Job No.: CHK50868310			Rev.: -															
<b>AM</b> <b>PM</b> ARM A: Fairview Park Boulevard ARM B: Castle Peak Road - Tam Mi (N) ARM C: San Tin Highway Slip Road (N) ARM D: San Tam Road (N) ARM E: San Tam Road (S) ARM F: San Tin Highway Slip Road (S) ARM G: Castle Peak Road - Tam Mi (S)																			
																			
<b>GEOMETRY</b>																			
<b>ARM</b>	<b>v</b>	<b>e</b>	<b>L</b>	<b>r</b>	<b>D</b>	<b>Phi</b>	<b>S</b>												
A	7.00	12.20	34	25	140	35	0.24												
B	7.30	12.00	36	30	140	25	0.21												
C	7.30	13.00	13	45	140	30	0.70												
D	7.30	13.00	40	25	140	45	0.23												
E	7.30	12.00	27	25	140	45	0.28												
F	6.00	13.00	36	25	140	40	0.31												
G	6.50	11.20	22	25	140	35	0.34												
<b>AM FLOWS</b>																			
<b>from \ to</b>	<b>A</b>	<b>B</b>	<b>C</b>	<b>D</b>	<b>E</b>	<b>F</b>	<b>G</b>	<b>Circ</b>	<b>Entry</b>										
A	10	20	210	40	230	480	30	2925	1020										
B	10	10	170	35	250	465	30	3210	970										
C	95	80	10	Free Flow	485	10	225	2900	905										
D	65	45	45	10	280	210	95	3405	750										
E	40	35	465	120	10	535	20	2260	1225										
F	335	385	10	110	630	10	Free Flow	1450	1480										
G	115	160	370	85	10	325	0	2530	1065										
<b>PM FLOWS</b>																			
<b>from \ to</b>	<b>A</b>	<b>B</b>	<b>C</b>	<b>D</b>	<b>E</b>	<b>F</b>	<b>G</b>	<b>Circ</b>	<b>Entry</b>										
A	10	10	170	55	210	345	30	2605	830										
B	35	10	105	35	170	215	30	2740	600										
C	190	135	20	Free Flow	425	20	210	2440	1000										
D	80	45	90	20	250	95	75	2985	655										
E	100	30	305	115	10	295	20	1905	875										
F	445	340	10	175	660	20	Free Flow	1570	1650										
G	95	125	200	55	10	220	10	2845	715										
<b>CALCULATIONS</b>																			
<b>ARM</b>	<b>K</b>	<b>X<sub>2</sub></b>	<b>M</b>	<b>F</b>	<b>t<sub>D</sub></b>	<b>f<sub>c</sub></b>	<b>AM</b>	<b>PM</b>	<b>AM</b>										
A	0.99	10.49	2980.96	3179	1.00	0.65	1266	1472	0.81										
B	1.03	10.62	2980.96	3216	1.00	0.66	1148	1467	0.84										
C	1.03	9.67	2980.96	2931	1.00	0.62	1174	1466	0.77										
D	0.96	11.21	2980.96	3398	1.00	0.68	1033	1307	0.73										
E	0.96	10.32	2980.96	3127	1.00	0.64	1602	1820	0.76										
F	0.98	10.32	2980.96	3125	1.00	0.64	2138	2063	0.69										
G	0.99	9.29	2980.96	2815	1.00	0.60	1287	1099	0.83										
<b>Critical Arm:</b> <b>B</b> <b>F</b>																			
<b>RFC:</b> <b>0.84</b> <b>0.80</b>																			
<b>AM</b> <b>PM</b>																			
<i>- In accordance with TPDM V2.4</i>																			
Calculated by: HZF	Date: Jan-26	Checked by: PTC																	

# Roundabout Capacity Calculation

Job Title: Proposed Residential Development at Lot No. 4822 in D.D. 104 and Adjoining Government Land, East of Kam Pok Road, Mai Po, Yuen Long													
Junction: Kam Pok Road / Castle Peak Road – Tam Mi (J6)						Ref. No.:							
Scheme: Design Case (with Junction Improvement Layout)													
Year: 2034	Job No.:		CHK50868310		Rev.:	-							
<b>AM</b> <b>PM</b> ARM A: Castle Peak Road - Tam Mi NB ARM B: Kam Pok Road EB ARM C: Castle Peak Road - Tam Mi SB													
													
<b>GEOMETRY</b>													
ARM	v	e	L	r	D	Phi	S						
A	3.50	4.50	12	50	26	30	0.13						
B	7.30	5.00	5	17.5	26	45	-0.74						
C	3.30	3.10	7	80	26	5	-0.05						
<b>AM FLOWS</b>													
from \ to	A	B	C			Circ	Entry	Exit					
A	0	250	385			175	635	375					
B	375	0	115			385	490	425					
C	FF	175	0			375	175	500					
<b>PM FLOWS</b>													
from \ to	A	B	C			Circ	Entry	Exit					
A	0	235	465			85	700	185					
B	185	0	55			465	240	320					
C	FF	85	0			185	85	520					
<b>CALCULATIONS</b>													
ARM	K	X <sub>2</sub>	M	F	t <sub>D</sub>	f <sub>c</sub>	Q <sub>E</sub>	RFC					
A	1.03	4.29	0.03	1300	1.48	0.58	1234	1287					
B	0.94	12.17	0.03	3688	1.48	1.07	3083	3002					
C	1.12	3.08	0.03	933	1.48	0.50	836	944					
<b>Critical Arm:</b> <b>A</b> <b>A</b> <b>RFC:</b> <b>0.51</b> <b>0.54</b> <b>AM</b> <b>PM</b>													
<i>- In accordance with TPDM V2.4</i>													
Calculated by:	HZF	Date:	Jan-26	Checked by:	PTC								


# Roundabout Capacity Calculation

Job Title: Proposed Residential Development at Lot No. 4822 in D.D. 104 and Adjoining Government Land, East of Kam Pok Road, Mai Po, Yuen Long																			
Junction: Fairview Park Interchange (J1)								Ref. No.:											
Scheme: Design Case under Sensitivity Test 1 (with Proposed Junction Layout)																			
Year: 2034	Job No.: CHK50868310			Rev.: -															
<b>AM</b> <b>PM</b> ARM A: Fairview Park Boulevard ARM B: Castle Peak Road - Tam Mi (N) ARM C: San Tin Highway Slip Road (N) ARM D: San Tam Road (N) ARM E: San Tam Road (S) ARM F: San Tin Highway Slip Road (S) ARM G: Castle Peak Road - Tam Mi (S)																			
																			
<b>GEOMETRY</b>																			
ARM	v	e	L	r	D	Phi	S												
A	7.00	12.20	34	25	140	35	0.24												
B	7.30	12.00	36	30	140	25	0.21												
C	7.30	13.00	13	45	140	30	0.70												
D	7.30	13.00	34	25	140	35	0.27												
E	7.30	12.00	27	25	140	45	0.28												
F	6.00	13.00	36	25	140	40	0.31												
G	6.50	11.20	22	25	140	35	0.34												
<b>AM FLOWS</b>																			
from \ to	A	B	C	D	E	F	G	Circ	Entry	Exit									
A	10	20	210	40	230	480	30	2995	1020	670									
B	10	10	200	35	250	570	30	3210	1105	805									
C	95	85	10	Free Flow	485	10	225	3005	910	1310									
D	65	45	45	10	280	210	95	3515	750	400									
E	40	35	465	120	10	535	20	2370	1225	1895									
F	335	450	10	110	630	10	Free Flow	1455	1545	2140									
G	115	160	370	85	10	325	0	2600	1065	400									
<b>PM FLOWS</b>																			
from \ to	A	B	C	D	E	F	G	Circ	Entry	Exit									
A	10	10	170	55	210	345	30	2675	830	955									
B	35	10	115	35	170	260	30	2740	655	765									
C	190	155	20	Free Flow	425	20	210	2485	1020	910									
D	80	45	90	20	250	95	75	3050	655	455									
E	100	30	305	115	10	295	20	1970	875	1735									
F	445	390	10	175	660	20	Free Flow	1590	1700	1255									
G	95	125	200	55	10	220	10	2915	715	375									
<b>CALCULATIONS</b>																			
ARM	K	X <sub>2</sub>	M	F	t <sub>D</sub>	f <sub>c</sub>	AM	PM	AM	PM									
A	0.99	10.49	2980.96	3179	1.00	0.65	1221	1427	0.84	0.58									
B	1.03	10.62	2980.96	3216	1.00	0.66	1148	1467	0.96	0.45									
C	1.03	9.67	2980.96	2931	1.00	0.62	1108	1437	0.82	0.71									
D	0.99	11.01	2980.96	3336	1.00	0.67	965	1275	0.78	0.51									
E	0.96	10.32	2980.96	3127	1.00	0.64	1534	1780	0.80	0.49									
F	0.98	10.32	2980.96	3125	1.00	0.64	2135	2050	0.72	0.83									
G	0.99	9.29	2980.96	2815	1.00	0.60	1245	1057	0.86	0.68									
<b>Critical Arm:</b> <b>B</b> <b>F</b> <b>RFC:</b> <b>0.96</b> <b>0.83</b> <b>AM</b> <b>PM</b>																			
<i>- In accordance with TPDM V2.4</i>																			
Calculated by: HZF	Date: Jan-26	Checked by: PTC																	

## TRAFFIC SIGNALS CALCULATION


Job No.: CHK50868310

MVA HONG KONG LIMITED

Junction: <u>Kam Pok Road / Fairview Park Boulevard (J2)</u>												Design Year: <u>2034</u>			
Description: <u>Year 2034 Design Traffic Flows (Sensitivity Test 1)</u>												Designed By: <u>HZF</u>	Checked By: <u>PTC</u>		
Approach	Movements	Phase	Stage	Width (m)	Radius (m)		Gradient (%)	Pro. Turning (%)		Revised Saturation Flow (pcu/hr)		AM Peak			
					Left	Right		AM	PM	AM	PM	Flow (pcu/hr)	y Value	Critical y	
Fairview Park Boulevard EB	↑→	A	1	3.4	15		8%	9%		1940	1935	428	0.221	0.221	
	→	A	1	3.4						1955	1955	432	0.221		
Fairview Park Boulevard WB	←↓	A	1	3.5	17		24%	26%		1925	1920	336	0.175		
	←	A	1	3.5						1965	1965	344	0.175		
Kam Pok Road SB	↔	B	2	5.5	18	18	12% / 32%	15% / 38%		2090	2070	170	0.081	0.081	
												130	0.063	0.063	
Kam Pok Road NB	↔	C	3	3.8	13	20	6% / 34%	12% / 63%		1935	1880	175	0.090	0.090	
												205	0.109	0.109	
Pedestrian Crossing Dp 4 MIN GREEN + FLASH = 10 + 9 = 19 *															
Notes:		Flow: (pcu/hr)										Group		A.B.C.Dp	
												y	0.393	y	0.390
												L (sec)	44	L (sec)	44
												C (sec)	120	C (sec)	120
												y pract.	0.570	y pract.	0.570
												R.C. (%)	45%	R.C. (%)	46%
Stage / Phase Diagrams															
1.		2.		3.		4.		5.							
															
I/G= 3		I/G= 7		I/G= 7		I/G= 11	19	I/G=							
I/G= 3		I/G= 7		I/G= 7		I/G= 11	19	I/G=				Date: Jan, 2026	Junction: 2		J2

**TRAFFIC SIGNALS CALCULATION**

 Job No.: CHK50868310
**MVA HONG KONG LIMITED**

Junction: <u>Kam Pok Road / Vehicular Bridge – South (J3)</u>												Design Year: <u>2034</u>							
Description: <u>Year 2034 Design Traffic Flows (Sensitivity Test 1)</u>												Designed By: <u>HZF</u>	Checked By: <u>PTC</u>						
Approach	Movements	Phase	Stage	Width (m)	Radius (m)		Gradient (%)	Pro. Turning (%)		Revised Saturation Flow (pcu/hr)		AM Peak							
					Left	Right		AM	PM	AM	PM	Flow (pcu/hr)	y Value	Critical y					
Vehicular Bridge (EB)	↑↑	A	1	3.600	10	10		82% / 18%	83% / 17%	1715	1715	140	0.082	0.082					
Kam Pok Rd (SB)	↑↑	B	2	3.600		10		26%	26%	1900	1900	330	0.174	0.174					
Kam Pok Rd (NB)	↑↑	C	3	3.600	10			11%	16%	1945	1930	230	0.118	0.118					
Pedestrian Crossing	Dp	4	MIN GREEN + FLASH =			7	+	7	=	14		*		*					
Notes:		Flow: (pcu/hr)										Group		A.B.C.Dp					
													y	0.374	y	0.186			
												L (sec)	26	L (sec)	32				
												C (sec)	60	C (sec)	60				
												y pract.	0.510	y pract.	0.420				
												R.C. (%)	37%	R.C. (%)	126%				
Stage / Phase Diagrams																			
1.		2.		3.		4.		5.											
																			
I/G= 2		I/G= 5		I/G= 5		I/G= 3		14		I/G=									
I/G= 2	5	I/G= 5		I/G= 5		I/G= 3		14		I/G=									
Date: <u>Jan, 2026</u>										Junction: <u>3</u>									

## TRAFFIC SIGNALS CALCULATION

Job No.: CHK50868310

MVA HONG KONG LIMITED

Junction: <u>Kam Pok Road / Vehicular Bridge – North / Vehicular Access (J4)</u>												Design Year: <u>2034</u>													
Description: <u>Year 2034 Design Traffic Flows (Sensitivity Test 1) (with Planned Junction Layout)</u>												Designed By: <u>HZF</u>	Checked By: <u>PTC</u>												
Approach	Movements	Phase	Stage	Width (m)	Radius (m)		Gradient (%)	Pro. Turning (%)		Revised Saturation Flow (pcu/hr)		AM Peak			PM Peak										
					Left	Right		AM	PM	AM	PM	Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y								
Vehicular Bridge SB	↑↑	A	1	3.500	10	12		81% / 19%	80% / 20%	1715	1715	105	0.061	0.061	50	0.029									
Kam Pok Road EB	↑↑	D	2	3.650	10	12		4% / 6%	5% / 14%	1955	1930	360	0.184	0.184	185	0.096	0.096								
R(D) Site Access	↑↑	C	3	5.500	20	12		100%	100%	2015	2015	25	0.012		10	0.005									
	↑↑	C	3	4.000						1790	1790	230	0.128	0.128	95	0.053	0.053								
Kam Pok Road WB	↑↑	B	4	3.650	15	12		15%	18%	1800	1800	170	0.094		105	0.058									
	↑↑	B	4	3.650						1945	1940	365	0.188	0.188	285	0.147	0.147								
Pedestrian Crossing	Ep	3	MIN GREEN + FLASH =	10	+	10	=	20																	
	Fp	1	MIN GREEN + FLASH =	11	+	10	=	21																	
	Gp	1,2,4	MIN GREEN + FLASH =	5	+	5	=	10																	
Notes:				Flow: (pcu/hr)								Group	Fp,D,C,B	A,D,C,B	Group	Fp,D,C,B	A,D,C,B								
Stage / Phase Diagrams												y	0.500	0.562	y	0.296	0.296								
												L (sec)	18	25	L (sec)	18	31								
												C (sec)	90	90	C (sec)	90	90								
												y pract.	0.720	0.650	y pract.	0.720	0.590								
												R.C. (%)	44%	16%	R.C. (%)	143%	99%								
I/G= 7		I/G= 12		I/G= 5		I/G= 5		I/G= 5		I/G= 5		I/G=		I/G=		I/G=									
I/G= 7	5	I/G= 12		I/G= 5		I/G= 5		I/G= 5		I/G= 5		I/G=		I/G=		I/G=									
Date: <u>Jan, 2026</u>												Junction: <u>4</u>		J4											

### Simplified Priority Junction Capacity Calculation

Job Title:	Proposed Residential Development at Lot No. 4822 in D.D. 104 and Adjoining Government Land, East of Kam Pok Road, Mai Po, Yuen Long			Ref. No.:
Junction:	Kam Pok Road / Ha Chuk Yuen Road (J5)			
Scheme:	Design Case under Sensitivity Test 1			
Year:	2034	Job No.:	CHK50868310	Rev.:
ARM A:	Kam Pok Road WB			
ARM B:	Ha Chuk Yuen Road			
ARM C:	Kam Pok Road EB			
<b>GEOMETRY</b>				
Major road width	W	9.30	Lane widths	w(b-a) 2.05 w(b-c) 2.05 w(c-b) 3.50
Central Reserve width	Wcr	0.00		
2 Lane Minor Arm (Y/N)	N			
Visibilities	Vr(b-a) Vl(b-a) Vr(b-c) Vr(c-b)	50 50 50 50	Calculated	D 0.75 E 0.80 F 0.92 Y 0.68
<b>ANALYSIS</b>				
TRAFFIC FLOWS	q(c-a) q(c-b) q(a-b) q(a-c) q(b-a) q(b-c) f		AM PEAK 640 0 15 530 20 5 0.20	(PM) PEAK 285 0 25 380 20 5 0.20
CAPACITIES	Q(b-a) Q(b-c) Q(c-b) Q(b-ac)	Factor 1 1 1 1	296 488 564 321	364 516 596 387
RFC's	b-a b-c c-b b-ac		0.068 0.010 0.000 0.078	0.055 0.010 0.000 0.065
Worst RFC			0.078	0.065
Where Vl and Vr are visibility distances to the left or right of the respective streams				
$D = (1+0.094(w(b-a)-3.65))(1+0.0009(Vr(b-a)-120))(1+0.0006(Vl(b-a)-150))$ $E = (1+0.094(w(b-c)-3.65))(1+0.0009(Vr(b-c)-120))$ $F = (1+0.094(w(c-b)-3.65))(1+0.0009(Vr(c-b)-120))$ $Y = 1-0.0345W$				
$f = \text{proportion of minor traffic turning left}$ $Q(b-ac) = Q(b-c)*Q(b-a)/(1-f)*Q(b-c)+f*Q(b-a)$				
Capacity of combined streams - in accordance with TPDM V2.4 <b>T.P.D.M.V.2.4</b> <b>Appendix 1</b>				
Calculated by:	HZF	Date:	Jan, 2026	Checked by: PTC


## Simplified Priority Junction Capacity Calculation

Job Title:	Proposed Residential Development at Lot No. 4822 in D.D. 104 and Adjoining Government Land, East of Kam Pok Road, Mai Po, Yuen Long	Ref. No.:			
Junction:	Kam Pok Road / Castle Peak Road – Tam Mi (J6)				
Scheme:	Design Case under Sensitivity Test 1 (with Planned Junction Layout)				
Year:	2034	Job No.: CHK50868310			
ARM A:	Castle Peak Road - Tam Mi NB	Rev.:			
ARM B:	Kam Pok Road EB				
ARM C:	Castle Peak Road - Tam Mi SB				
<b>GEOMETRY</b>					
Major road width	W	6.90	Lane widths	w(b-a)	4.30
Central Reserve width	W <sub>cr</sub>	1.50		w(b-c)	4.30
2 Lane Minor Arm (Y/N)	Y			w(c-b)	2.05
Visibilities	V <sub>r(b-a)</sub>	53	Calculated	D	0.95
	V <sub>l(b-a)</sub>	70		E	1.01
	V <sub>r(b-c)</sub>	70		F	0.78
	V <sub>r(c-b)</sub>	30		Y	0.76
<b>ANALYSIS</b>			AM PEAK	(PM) PEAK	
TRAFFIC FLOWS	q(c-a)		555	395	
	q(c-b)		225	100	
	q(a-b)		325	305	
	q(a-c)		385	465	
	q(b-a)		510	240	
	q(b-c)		155	70	
	f		0.23	0.23	
CAPACITIES	Q(b-a)	Factor	303	358	
	Q(b-c)	1	611	590	
	Q(c-b)	1	428	415	
	Q(b-ac)	1	343	393	
RFC's	b-a		1.683	0.670	
	b-c		0.254	0.119	
	c-b		0.526	0.241	
	b-ac		0.000	0.000	
Worst RFC			1.683	0.670	
Where V <sub>l</sub> and V <sub>r</sub> are visibility distances to the left or right of the respective streams					
D = (1+0.094(w(b-a)-3.65))(1+0.0009(V <sub>r(b-a)</sub> -120))(1+0.0006(V <sub>l(b-a)</sub> -150))					
E = (1+0.094(w(b-c)-3.65))(1+0.0009(V <sub>r(b-c)</sub> -120))					
F = (1+0.094(w(c-b)-3.65))(1+0.0009(V <sub>r(c-b)</sub> -120))					
Y = 1-0.0345W					
f = proportion of minor traffic turning left					
Q(b-ac) = Q(b-c)*Q(b-a)/(1-f)*Q(b-c)+f*Q(b-a)					
Capacity of combined streams					
- in accordance with TPDM V2.4					
Calculated by:	HZF	Date:	Jan, 2026	Checked by:	PTC
T.P.D.M.V.2.4 Appendix 1					


### Simplified Priority Junction Capacity Calculation

Job Title:	Proposed Residential Development at Lot No. 4822 in D.D. 104 and Adjoining Government Land, East of Kam Pok Road, Mai Po, Yuen Long				
Junction:	Kam Pok Road / Fung Chuk Road (J7)				
Scheme:	Design Case under Sensitivity Test 1				
Year:	2025	Job No.:	CHK50868310		
ARM A:	Kam Pok Road SB	Rev.:			
ARM B:	Fung Chuk Road				
ARM C:	Kam Pok Road NB				
<b>GEOMETRY</b>					
Major road width	W	7.30	Lane widths	w(b-a)	2.00
Central Reserve width	Wcr	0.00		w(b-c)	2.00
2 Lane Minor Arm (Y/N)	N			w(c-b)	3.50
Visibilities	Vr(b-a)	12	Calculated	D	0.70
	Vl(b-a)	8.5		E	0.76
	Vr(b-c)	12		F	0.90
	Vr(c-b)	21		Y	0.75
<b>ANALYSIS</b>					
		AM PEAK	(PM) PEAK		
TRAFFIC FLOWS	q(c-a)	320	155		
	q(c-b)	0	5		
	q(a-b)	10	10		
	q(a-c)	320	235		
	q(b-a)	10	10		
	q(b-c)	5	5		
	f	0.33	0.33		
CAPACITIES	Q(b-a)	1	338	372	
	Q(b-c)	1	501	519	
	Q(c-b)	1	588	609	
	Q(b-ac)	1	379	410	
RFC's	b-a		0.030	0.027	
	b-c		0.010	0.010	
	c-b		0.000	0.008	
	b-ac		0.040	0.037	
Worst RFC		0.040	0.037		
Where $Vl$ and $Vr$ are visibility distances to the left or right of the respective streams $D = (1+0.094(w(b-a)-3.65))(1+0.0009(Vr(b-a)-120))(1+0.0006(Vl(b-a)-150))$ $E = (1+0.094(w(b-c)-3.65))(1+0.0009(Vr(b-c)-120))$ $F = (1+0.094(w(c-b)-3.65))(1+0.0009(Vr(c-b)-120))$ $Y = 1-0.0345W$ $f$ = proportion of minor traffic turning left $Q(b-ac) = Q(b-c)*Q(b-a)/(1-f)*Q(b-c)+f*Q(b-a)$					
Capacity of combined streams - in accordance with TPDM V2.4 T.P.D.M.V.2.4 Appendix 1					
Calculated by:	HZF	Date:	Jan, 2026	Checked by:	PTC

# Roundabout Capacity Calculation

Job Title: Proposed Residential Development at Lot No. 4822 in D.D. 104 and Adjoining Government Land, East of Kam Pok Road, Mai Po, Yuen Long																									
Junction: Fairview Park Interchange (J1)								Ref. No.:																	
Scheme: Design Case under Sensitivity Test 1 (with Suggested Junction Improvement Layout)																									
Year: 2034	Job No.: CHK50868310			Rev.: -																					
AM PM																									
ARM A:	Fairview Park Boulevard																								
ARM B:	Castle Peak Road - Tam Mi (N)																								
ARM C:	San Tin Highway Slip Road (N)																								
ARM D:	San Tam Road (N)																								
ARM E:	San Tam Road (S)																								
ARM F:	San Tin Highway Slip Road (S)																								
ARM G:	Castle Peak Road - Tam Mi (S)																								
																									
GEOMETRY																									
ARM	v	e	L	r	D	Phi	S																		
A	7.00	12.20	34	25	140	35	0.24																		
B	7.30	12.00	36	30	140	25	0.21																		
C	7.30	13.00	13	45	140	30	0.70																		
D	7.30	13.00	40	25	140	45	0.23																		
E	7.30	12.00	27	25	140	45	0.28																		
F	6.00	13.00	36	25	140	40	0.31																		
G	6.50	12.00	25	25	140	35	0.35																		
AM FLOWS																									
from \ to	A	B	C	D	E	F	G	Circ	Entry	Exit															
A	10	20	210	40	230	480	30	2995	1020	670															
B	10	10	Free Flow	35	250	570	30	3210	905	805															
C	95	85	10	Free Flow	485	10	225	3005	910	1110															
D	65	45	45	10	280	210	95	3515	750	400															
E	40	35	465	120	10	535	20	2370	1225	1895															
F	335	450	10	110	630	10	Free Flow	1455	1545	2140															
G	115	160	370	85	10	325	0	2600	1065	400															
PM FLOWS																									
from \ to	A	B	C	D	E	F	G	Circ	Entry	Exit															
A	10	10	170	55	210	345	30	2675	830	955															
B	35	10	Free Flow	35	170	260	30	2740	540	765															
C	190	155	20	Free Flow	425	20	210	2485	1020	795															
D	80	45	90	20	250	95	75	3050	655	455															
E	100	30	305	115	10	295	20	1970	875	1735															
F	445	390	10	175	660	20	Free Flow	1590	1700	1255															
G	95	125	200	55	10	220	10	2915	715	375															
CALCULATIONS																									
ARM	K	X <sub>2</sub>	M	F	t <sub>D</sub>	f <sub>c</sub>	AM	PM	AM	PM															
A	0.99	10.49	2980.96	3179	1.00	0.65	1221	1427	0.84	0.58															
B	1.03	10.62	2980.96	3216	1.00	0.66	1148	1467	0.79	0.37															
C	1.03	9.67	2980.96	2931	1.00	0.62	1108	1437	0.82	0.71															
D	0.96	11.21	2980.96	3398	1.00	0.68	961	1265	0.78	0.52															
E	0.96	10.32	2980.96	3127	1.00	0.64	1534	1780	0.80	0.49															
F	0.98	10.32	2980.96	3125	1.00	0.64	2135	2050	0.72	0.83															
G	0.99	9.73	2980.96	2947	1.00	0.62	1329	1135	0.80	0.63															
Critical Arm: A F																									
RFC: 0.84 0.83																									
AM PM																									
- In accordance with TPDM V2.4																									
Calculated by: HZF	Date: Jan-26	Checked by: PTC																							


# Roundabout Capacity Calculation

Job Title: Proposed Residential Development at Lot No. 4822 in D.D. 104 and Adjoining Government Land, East of Kam Pok Road, Mai Po, Yuen Long																		
Junction: Kam Pok Road / Castle Peak Road – Tam Mi (J6)						Ref. No.:												
Scheme: Design Case under Sensitivity Test 1 (with Junction Improvement Layout)																		
Year: 2034	Job No.:		CHK50868310		Rev.:	-												
AM PM																		
ARM A:	Castle Peak Road - Tam Mi NB																	
ARM B:	Kam Pok Road EB																	
ARM C:	Castle Peak Road - Tam Mi SB																	
																		
<b>GEOMETRY</b>																		
ARM	v	e	L	r	D	Phi	S											
A	3.50	4.50	12	50	26	30	0.13											
B	7.30	5.00	5	17.5	26	45	-0.74											
C	3.30	3.10	7	80	26	5	-0.05											
<b>AM FLOWS</b>																		
from \ to	A	B	C			Circ	Entry	Exit										
A	0	340	385			235	725	535										
B	535	0	160			385	695	575										
C	FF	235	0			535	235	545										
<b>PM FLOWS</b>																		
from \ to	A	B	C			Circ	Entry	Exit										
A	0	320	465			105	785	250										
B	250	0	70			465	320	425										
C	FF	105	0			250	105	535										
<b>CALCULATIONS</b>																		
ARM	K	X <sub>2</sub>	M	F	t <sub>D</sub>	f <sub>c</sub>	Q <sub>E</sub>	RFC										
A	1.03	4.29	0.03	1300	1.48	0.58	1198	PM										
B	0.94	12.17	0.03	3688	1.48	1.07	3083	AM										
C	1.12	3.08	0.03	933	1.48	0.50	746	AM										
Critical Arm: A A																		
RFC: 0.61 0.62																		
AM PM																		
<i>- In accordance with TPDM V2.4</i>																		
Calculated by: HZF	Date: Jan-26	Checked by: PTC																

# **Appendix T1**

## **Potential Pick-Up/Drop-Off**

### **Location For Bus/Shuttle Bus**



**Swept Path Analysis for 12.8m Bus  
1:500 in A4 Size**